

FCC Radio Test Report

FCC ID: 2AXJ4KS220**This report concerns: Class II Permissive Change**


Report No. : BTL-FCCP-1-2304G030
Equipment : Kasa Smart Wi-Fi Light Switch Dimmer
Model Name : KS220, KS225
Brand Name : tp-link
Applicant : TP-Link Corporation Limited
Address : Room 901, 9/F., New East Ocean Centre, 9 Science Museum Road, Tsim Sha Tsui, Kowloon, Hong Kong
Manufacturer : TP-Link Corporation Limited
Address : Room 901, 9/F., New East Ocean Centre, 9 Science Museum Road, Tsim Sha Tsui, Kowloon, Hong Kong

Radio Function : Bluetooth Low Energy

FCC Rule Part(s) : FCC CFR Title 47, Part 15, Subpart C
Measurement : ANSI C63.10-2013
Procedure(s)

Date of Receipt : 2023/4/12
Date of Test : 2023/5/17 ~ 2023/6/20
Issued Date : 2023/7/17

The above equipment has been tested and found in compliance with the requirement of the above standards by BTL Inc.

Prepared by : 
Eddie Lee, Engineer

Approved by : 
Jerry Chuang, Supervisor

**BTL Inc.**

No.18, Ln. 171, Sec. 2, Jiuzong Rd., Neihu Dist., Taipei City 114, Taiwan

Tel: +886-2-2657-3299 Fax: +886-2-2657-3331 Web: www.newbtl.com Service mail: btl_qa@newbtl.com

Declaration

BTL represents to the client that testing is done in accordance with standard procedures as applicable and that test instruments used has been calibrated with standards traceable to international standard(s) and/or national standard(s).

BTL's reports apply only to the specific samples tested under conditions. It is manufacture's responsibility to ensure that additional production units of this model are manufactured with the identical electrical and mechanical components. **BTL** shall have no liability for any declarations, inferences or generalizations drawn by the client or others from **BTL** issued reports.

This report is the confidential property of the client. As a mutual protection to the clients, the public and ourselves, the test report shall not be reproduced, except in full, without our written approval.

BTL's laboratory quality assurance procedures are in compliance with the **ISO/IEC 17025** requirements, and accredited by the conformity assessment authorities listed in this test report.

BTL is not responsible for the sampling stage, so the results only apply to the sample as received.

The information, data and test plan are provided by manufacturer which may affect the validity of results, so it is manufacturer's responsibility to ensure that the apparatus meets the essential requirements of applied standards and in all the possible configurations as representative of its intended use.

Limitation

For the use of the authority's logo is limited unless the Test Standard(s)/Scope(s)/Item(s) mentioned in this test report is (are) included in the conformity assessment authorities acceptance respective.

Please note that the measurement uncertainty is provided for informational purpose only and are not use in determining the Pass/Fail results.

CONTENTS

REVISION HISTORY	4
1 SUMMARY OF TEST RESULTS	5
1.1 TEST FACILITY	6
1.2 MEASUREMENT UNCERTAINTY	6
1.3 TEST ENVIRONMENT CONDITIONS	6
1.4 DUTY CYCLE	7
2 GENERAL INFORMATION	8
2.1 DESCRIPTION OF EUT	8
2.2 TEST MODES	9
2.3 BLOCK DIAGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED	10
2.4 SUPPORT UNITS	10
3 AC POWER LINE CONDUCTED EMISSIONS TEST	11
3.1 LIMIT	11
3.2 TEST PROCEDURE	11
3.3 DEVIATION FROM TEST STANDARD	11
3.4 TEST SETUP	12
3.5 TEST RESULT	12
4 RADIATED EMISSIONS TEST	13
4.1 LIMIT	13
4.2 TEST PROCEDURE	13
4.3 DEVIATION FROM TEST STANDARD	14
4.4 TEST SETUP	14
4.5 EUT OPERATING CONDITIONS	14
4.6 TEST RESULT – BELOW 30 MHZ	14
4.7 TEST RESULT – 30 MHZ TO 1 GHZ	14
5 OUTPUT POWER TEST	15
5.1 APPLIED PROCEDURES / LIMIT	15
5.2 TEST PROCEDURE	15
5.3 DEVIATION FROM STANDARD	15
5.4 TEST SETUP	15
5.5 EUT OPERATION CONDITIONS	15
5.6 TEST RESULTS	15
6 LIST OF MEASURING EQUIPMENTS	16
7 EUT TEST PHOTO	17
8 EUT PHOTOS	17
APPENDIX A AC POWER LINE CONDUCTED EMISSIONS	18
APPENDIX B RADIATED EMISSIONS - 30 MHZ TO 1 GHZ	23
APPENDIX C OUTPUT POWER	26

REVISION HISTORY

Report No.	Version	Description	Issued Date	Note
BTL-FCCP-1-2304G030	R00	Original Report.	2023/6/29	Invalid
BTL-FCCP-1-2304G030	R01	Revised report to address TCB's comments.	2023/7/17	Valid

1 SUMMARY OF TEST RESULTS

Test procedures according to the technical standards.

Standard(s) Section	Description	Test Result	Judgement	Remark
15.207	AC Power Line Conducted Emissions	APPENDIX A	Pass	-----
15.205 15.209 15.247(d)	Radiated Emissions (Below 1 GHz)	APPENDIX B	Pass	-----
15.247(a)(2)	Bandwidth	-----	N/A	NOTE (1)
15.247(b)(3)	Output Power	APPENDIX C	Pass	-----
15.247(e)	Power Spectral Density	-----	N/A	NOTE (1)
15.247(d)	Antenna conducted Spurious Emission	-----	N/A	NOTE (1)
15.203	Antenna Requirement	-----	N/A	NOTE (1)

NOTE:

- (1) "N/A" denotes test is not applicable in this Test Report.
- (2) The report format version is TP.1.1.1.
- (3) This a support report for FCC ID: 2AXJ4KS220. The device has been adjusted the position of the Wi-Fi board and replace the power board. Only critical items are tested and recorded in this report.

1.1 TEST FACILITY

The test locations stated below are under the TAF Accreditation Number 0659.

The test location(s) used to collect the test data in this report are:

No. 68-1, Ln. 169, Sec. 2, Datong Rd., Xizhi Dist., New Taipei City 221, Taiwan
(FCC DN: TW0659)

C05 CB08 CB11 SR10 SR11

No. 72, Ln. 169, Sec. 2, Datong Rd., Xizhi Dist., New Taipei City 221, Taiwan
(FCC DN: TW0659)

C06 CB21

1.2 MEASUREMENT UNCERTAINTY

The reported uncertainty of measurement $y \pm U$, where expanded uncertainty U is based on a standard uncertainty multiplied by a coverage factor of $k = 2$, providing a level of confidence of approximately **95 %**. The measurement instrumentation uncertainty considerations contained in CISPR 16-4-2. The BTL measurement uncertainty is less than the CISPR 16-4-2 U_{cispr} requirement.

A. AC power line conducted emissions test:

Test Site	Method	Measurement Frequency Range	U (dB)
C05	CISPR	150 kHz ~ 30MHz	3.44

B. Radiated emissions test :

Test Site	Measurement Frequency Range	U,(dB)
CB21	0.03 GHz ~ 0.2 GHz	4.17
	0.2 GHz ~ 1 GHz	4.72
	1 GHz ~ 6 GHz	5.21

C. Conducted test :

Test Item	U,(dB)
Output power	0.3669

NOTE:

Unless specifically mentioned, the uncertainty of measurement has not been taken into account to declare the compliance or non-compliance to the specification.


1.3 TEST ENVIRONMENT CONDITIONS

Test Item	Environment Condition	Test Voltage	Tested by
AC Power Line Conducted Emissions	21 °C, 62 %	AC 120V	Cora Lin
Radiated emissions below 1 GHz	23 °C, 58 %	AC 120V	Mark Wang
Output Power	24 °C, 41 %	AC 120V	Jay Tien

1.4 DUTY CYCLE

If duty cycle is $\geq 98\%$, duty factor is not required.
 If duty cycle is $< 98\%$, duty factor shall be considered.

Remark	Delta 1			Delta 2	On Time/Period	10 log(1/Duty Cycle)
Mode	ON (ms)	Numbers (ON)	On Time (B) (ms)	Period (ON+OFF) (ms)	Duty Cycle (%)	Duty Factor (dB)
BLE (1 Mbps)	0.395	1	0.395	0.625	63.20%	1.99



2 GENERAL INFORMATION

2.1 DESCRIPTION OF EUT

Equipment	Kasa Smart Wi-Fi Light Switch Dimmer
Model Name	KS220, KS225
Brand Name	tp-link
Model Difference	Model KS225 is identical to model KS220 except the model designation.
Power Source	AC Mains
Power Rating	120V~ 60Hz 300W Incandescent/Halogen 150W LED
Products Covered	N/A
Operation Band	2400 MHz ~ 2483.5 MHz
Operation Frequency	2402 MHz ~ 2480 MHz
Modulation Technology	GFSK
Transfer Rate	1Mbps
Test Software	RTLBTAPP V5.2.2.40
Conducted Output Power Max.	3.33 dBm (0.0022 W)
Test Model	KS220
Sample Status	Engineering Sample
EUT Modification(s)	N/A

NOTE:

- (1) The above EUT information is declared by manufacturer and for more detailed features description, please refers to the manufacturer's specifications or user's manual.
- (2) Channel List:

Channel	Frequency (MHz)	Channel	Frequency (MHz)
00	2402	20	2442
01	2404	21	2444
02	2406	22	2446
03	2408	23	2448
04	2410	24	2450
05	2412	25	2452
06	2414	26	2454
07	2416	27	2456
08	2418	28	2458
09	2420	29	2460
10	2422	30	2462
11	2424	31	2464
12	2426	32	2466
13	2428	33	2468
14	2430	34	2470
15	2432	35	2472
16	2434	36	2474
17	2436	37	2476
18	2438	38	2478
19	2440	39	2480

- (3) Table for Filed Antenna:

Ant.	Brand	Model	Antenna Type	Connector	Gain (dBi)
1	tp-link	6035500079	PIFA	N/A	2.98

The above Antenna information are derived from the antenna data sheet provided by manufacturer and for more detailed features description, please refer to the manufacturer's specifications, the laboratory shall not be held responsible.

2.2 TEST MODES

Test Items	Test mode	Channel	Note
AC power line conducted emissions	Normal/Idle	-----	-----
Transmitter Radiated Emissions (below 1 GHz)	1 Mbps	19	-----
Output Power	1 Mbps	00/19/39	-----


NOTE:

(1) All X, Y and Z axes are evaluated, but only the worst case (Y axis) is recorded.


2.3 BLOCK DIAGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED

Equipment letters and Cable numbers refer to item numbers described in the tables of clause 2.4.

AC power line conducted emissions



Radiated Emissions



2.4 SUPPORT UNITS

Item	Equipment	Brand	Model No.	Series No.	Remarks
-	-	-	-	-	-

Item	Shielded	Ferrite Core	Length	Cable Type	Remarks
1	N/A	N/A	1 m	Power cord	Furnished by test lab.

3 AC POWER LINE CONDUCTED EMISSIONS TEST

3.1 LIMIT

Frequency (MHz)	Limit (dB μ V)	
	Quasi-peak	Average
0.15 - 0.5	66 - 56 *	56 - 46 *
0.50 - 5.0	56	46
5.0 - 30.0	60	50

NOTE:

- (1) The tighter limit applies at the band edges.
- (2) The limit of " * " marked band means the limitation decreases linearly with the logarithm of the frequency in the range.
- (3) The test result calculated as following:
 Measurement Value = Reading Level + Correct Factor
 Correct Factor = Insertion Loss + Cable Loss + Attenuator Factor (if use)
 Margin Level = Measurement Value – Limit Value
 Calculation example:

Reading Level		Correct Factor		Measurement Value
38.22	+	3.45	=	41.67

Measurement Value		Limit Value		Margin Level
41.67	-	60	=	-18.33

The following table is the setting of the receiver.

Receiver Parameter	Setting
Attenuation	10 dB
Start Frequency	0.15 MHz
Stop Frequency	30 MHz
IF Bandwidth	9 KHz

3.2 TEST PROCEDURE

- a. The EUT was placed 0.8 m above the horizontal ground plane with the EUT being connected to the power mains through a line impedance stabilization network (LISN).
 All other support equipment were powered from an additional LISN(s).
 The LISN provides 50 Ohm/50uH of impedance for the measuring instrument.
- b. Interconnecting cables that hang closer than 40 cm to the ground plane shall be folded back and forth in the center forming a bundle to keep the cable above 40 cm.
- c. Excess I/O cables that are not connected to a peripheral shall be bundled in the center.
 The end of the cable will be terminated, using the correct terminating impedance.
 The overall length shall not exceed 1 m.
- d. The LISN is spaced at least 80 cm from the nearest part of the EUT chassis.
- e. For the actual test configuration, please refer to the related Item – EUT TEST PHOTO.


NOTE:

- (1) In the results, each reading is marked as Peak, QP or AVG per the detector used.
 BW=9 kHz (6 dB Bandwidth)
- (2) All readings are Peak unless otherwise stated QP or AVG in column of Note. Both the QP and the AVG readings must be less than the limit for compliance.

3.3 DEVIATION FROM TEST STANDARD

No deviation.

3.4 TEST SETUP



3.5 TEST RESULT

Please refer to the APPENDIX A.

4 RADIATED EMISSIONS TEST

4.1 LIMIT

In case the emission fall within the restricted band specified on 15.205, then the 15.209 limit in the table below has to be followed.

LIMITS OF RADIATED EMISSIONS MEASUREMENT (9 kHz to 1000 MHz)

Frequency (MHz)	Field Strength (microvolts/meter)	Measurement Distance (meters)
0.009~0.490	2400/F(KHz)	300
0.490~1.705	24000/F(KHz)	30
1.705~30.0	30	30
30~88	100	3
88~216	150	3
216~960	200	3
960~1000	500	3

NOTE:

- (1) The limit for radiated test was performed according to FCC CFR Title 47, Part 15, Subpart C.
- (2) The tighter limit applies at the band edges.
- (3) Emission level (dBuV/m)=20log Emission level (uV/m).
- (4) The test result calculated as following:

Measurement Value = Reading Level + Correct Factor

Correct Factor = Antenna Factor + Cable Loss - Amplifier Gain(if use)

Margin Level = Measurement Value - Limit Value

Calculation example:

Reading Level		Correct Factor		Measurement Value
41.91	+	-8.36	=	33.55

Measurement Value		Limit Value		Margin Level
33.55	-	43.50	=	-9.95

Spectrum Parameter	Setting
Attenuation	Auto
Start ~ Stop Frequency	9KHz~90KHz for PK/AVG detector
Start ~ Stop Frequency	90KHz~110KHz for QP detector
Start ~ Stop Frequency	110KHz~490KHz for PK/AVG detector
Start ~ Stop Frequency	490KHz~30MHz for QP detector
Start ~ Stop Frequency	30MHz~1000MHz for QP detector



4.2 TEST PROCEDURE

- a. The measuring distance of 3 m shall be used for measurements. The EUT was placed on the top of a rotating table 0.8 meter above the ground at a 3 meter semi-anechoic chamber. The table was rotated 360 degrees to determine the position of the highest radiation.(below 1GHz)
- b. The height of the equipment or of the substitution antenna shall be 0.8 m or 1.5 m, the height of the test antenna shall vary between 1 m to 4 m. Both horizontal and vertical polarizations of the antenna are set to make the measurement.
- c. For each suspected emission, the EUT was arranged to its worst case and then the antenna was tuned to heights find the maximum reading (used Bore sight function).
- d. The initial step in collecting radiated emission data is a receiver peak detector mode pre-scanning the measurement frequency range. Significant peaks are then marked and then Quasi Peak detector mode re-measured.
- e. All readings are Peak unless otherwise stated QP in column of Note. Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform. (below 1GHz)
- f. For the actual test configuration, please refer to the related Item – EUT TEST PHOTO.

4.3 DEVIATION FROM TEST STANDARD

No deviation.

4.4 TEST SETUP



4.5 EUT OPERATING CONDITIONS

The EUT was programmed to be in continuously transmitting mode.

4.6 TEST RESULT – BELOW 30 MHZ

There were no emissions found below 30 MHz within 20 dB of the limit.

4.7 TEST RESULT – 30 MHZ TO 1 GHZ

Please refer to the APPENDIX B.

5 OUTPUT POWER TEST

5.1 APPLIED PROCEDURES / LIMIT

Section	Test Item	Limit	Frequency Range (MHz)	Result
15.247(b)(3)	Maximum Output Power	1 watt or 30dBm	2400-2483.5	PASS


5.2 TEST PROCEDURE

- a. The EUT was directly connected to the power meter and antenna output port as show in the block diagram below,
- b. The maximum peak conducted output power was performed in accordance with FCC KDB 558074 D01 15.247 Meas Guidance.

5.3 DEVIATION FROM STANDARD

No deviation.

5.4 TEST SETUP



5.5 EUT OPERATION CONDITIONS

The EUT tested system was configured as the statements of 3.5 unless otherwise a special operating condition is specified in the follows during the testing.

5.6 TEST RESULTS

Please refer to the APPENDIX C.

6 LIST OF MEASURING EQUIPMENTS

AC Power Line Conducted Emissions						
Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated Date	Calibrated Until
1	TWO-LINE V-NETWORK	R&S	ENV216	101521	2022/9/28	2023/9/27
2	Test Cable	EMCI	EMCRG58-BM-B M-9000	220331	2023/3/30	2024/3/29
3	EMI Test Receiver	R&S	ESR 7	101433	2022/11/16	2023/11/15
4	Measurement Software	EZ	EZ EMC (Version NB-03A1-01)	N/A	N/A	N/A

Radiated Emissions						
Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated Date	Calibrated Until
1	Preamplifier	EMCI	EMC330N	980850	2022/9/19	2023/9/18
2	Test Cable	EMCI	EMC104-SM-SM-1000	220319	2023/3/14	2024/3/13
3	Test Cable	EMCI	EMC104-SM-SM-3000	220322	2023/3/14	2024/3/13
4	Test Cable	EMCI	EMC104-SM-SM-7000	220324	2023/3/14	2024/3/13
5	EXA Signal Analyzer	keysight	N9020B	MY57120120	2023/2/24	2024/2/23
6	Log-bicon Antenna	Schwarzbeck	VULB9168	1369	2023/5/9	2024/5/8
7	6dB Attenuator	EMCI	EMCI-N-6-06	AT-06001	2023/5/9	2024/5/8
8	Measurement Software	EZ	EZ EMC (Version NB-03A1-01)	N/A	N/A	N/A

Output Power						
Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated Date	Calibrated Until
1	Power Meter	Anritsu	ML2495A	1128008	2023/5/12	2024/5/11
2	Power Sensor	Anritsu	MA2411B	1126001	2023/5/12	2024/5/11
3	Spectrum Analyzer	R&S	FSP 40	100129	2023/3/27	2024/3/26

Remark: "N/A" denotes no model name, no serial no. or no calibration specified.
All calibration period of equipment list is one year.

7 EUT TEST PHOTO


Please refer to document Appendix No.: TP-2304G030-FCCP-1 (APPENDIX-TEST PHOTOS).

8 EUT PHOTOS

Please refer to document Appendix No.: EP-2304G030-1 (APPENDIX-EUT PHOTOS).

APPENDIX A AC POWER LINE CONDUCTED EMISSIONS

Test Mode	Normal	Tested Date	2023/05/24
Test Frequency	-	Phase	Line




No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Margin dB	Detector	Comment
1		0.1612	35.70	9.66	45.36	65.40	-20.04	QP	
2		0.1612	30.91	9.66	40.57	55.40	-14.83	AVG	
3		0.3232	32.12	9.63	41.75	59.62	-17.87	QP	
4	*	0.3232	28.04	9.63	37.67	49.62	-11.95	AVG	
5		0.8857	21.69	9.63	31.32	56.00	-24.68	QP	
6		0.8857	18.31	9.63	27.94	46.00	-18.06	AVG	
7		2.3437	13.79	9.69	23.48	56.00	-32.52	QP	
8		2.3437	10.80	9.69	20.49	46.00	-25.51	AVG	
9		10.0342	1.80	9.81	11.61	60.00	-48.39	QP	
10		10.0342	-2.07	9.81	7.74	50.00	-42.26	AVG	
11		28.2682	14.17	9.95	24.12	60.00	-35.88	QP	
12		28.2682	7.96	9.95	17.91	50.00	-32.09	AVG	

REMARKS:

- (1) Measurement Value = Reading Level + Correct Factor.
- (2) Margin Level = Measurement Value - Limit Value.


Test Mode	Normal	Tested Date	2023/05/24
Test Frequency	-	Phase	Neutral



No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Margin dB	Detector	Comment
1		0.1522	36.27	9.67	45.94	65.88	-19.94	QP	
2	*	0.1522	33.40	9.67	43.07	55.88	-12.81	AVG	
3		0.5055	25.70	9.64	35.34	56.00	-20.66	QP	
4		0.5055	21.64	9.64	31.28	46.00	-14.72	AVG	
5		1.1535	18.68	9.65	28.33	56.00	-27.67	QP	
6		1.1535	14.42	9.65	24.07	46.00	-21.93	AVG	
7		2.3865	14.42	9.70	24.12	56.00	-31.88	QP	
8		2.3865	11.17	9.70	20.87	46.00	-25.13	AVG	
9		8.0340	9.74	9.79	19.53	60.00	-40.47	QP	
10		8.0340	4.80	9.79	14.59	50.00	-35.41	AVG	
11		28.1333	9.99	10.16	20.15	60.00	-39.85	QP	
12		28.1333	5.30	10.16	15.46	50.00	-34.54	AVG	

REMARKS:
 (1) Measurement Value = Reading Level + Correct Factor.
 (2) Margin Level = Measurement Value - Limit Value.

Test Mode	Idle	Tested Date	2023/05/24
Test Frequency	-	Phase	Line




No.	Mk.	Freq.	Reading Level	Correct Factor	Measurement	Limit	Margin	Detector	Comment
		MHz	dBuV	dB	dBuV	dBuV	dB		
1		0.1590	35.57	9.66	45.23	65.52	-20.29	QP	
2		0.1590	30.94	9.66	40.60	55.52	-14.92	AVG	
3		0.3300	32.22	9.63	41.85	59.45	-17.60	QP	
4	*	0.3300	29.01	9.63	38.64	49.45	-10.81	AVG	
5		0.9825	21.77	9.63	31.40	56.00	-24.60	QP	
6		0.9825	18.35	9.63	27.98	46.00	-18.02	AVG	
7		1.6305	17.11	9.68	26.79	56.00	-29.21	QP	
8		1.6305	13.86	9.68	23.54	46.00	-22.46	AVG	
9		8.0340	8.35	9.76	18.11	60.00	-41.89	QP	
10		8.0340	5.54	9.76	15.30	50.00	-34.70	AVG	
11		28.1243	10.17	9.95	20.12	60.00	-39.88	QP	
12		28.1243	5.17	9.95	15.12	50.00	-34.88	AVG	

REMARKS:

- (1) Measurement Value = Reading Level + Correct Factor.
- (2) Margin Level = Measurement Value - Limit Value.

Test Mode	Idle	Tested Date	2023/05/24
Test Frequency	-	Phase	Neutral




No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Margin dB	Detector	Comment
1		0.1522	36.23	9.67	45.90	65.88	-19.98	QP	
2		0.1522	33.26	9.67	42.93	55.88	-12.95	AVG	
3		0.3682	31.09	9.64	40.73	58.54	-17.81	QP	
4	*	0.3682	27.63	9.64	37.27	48.54	-11.27	AVG	
5		0.9780	22.26	9.64	31.90	56.00	-24.10	QP	
6		0.9780	18.91	9.64	28.55	46.00	-17.45	AVG	
7		2.4855	12.67	9.70	22.37	56.00	-33.63	QP	
8		2.4855	8.54	9.70	18.24	46.00	-27.76	AVG	
9		10.0455	10.59	9.84	20.43	60.00	-39.57	QP	
10		10.0455	7.69	9.84	17.53	50.00	-32.47	AVG	
11		28.2435	14.01	10.16	24.17	60.00	-35.83	QP	
12		28.2435	10.57	10.16	20.73	50.00	-29.27	AVG	

REMARKS:
 (1) Measurement Value = Reading Level + Correct Factor.
 (2) Margin Level = Measurement Value - Limit Value.

APPENDIX B RADIATED EMISSIONS - 30 MHZ TO 1 GHZ

Test Mode	BLE 5.0 (1 Mbps)	Test Date	2023/5/26
Test Frequency	2440MHz	Polarization	Vertical
Temp	23°C	Hum.	58%




No.	Mk.	Freq.	Reading Level	Correct Factor	Measurement	Limit	Over	Detector	Comment
		MHz	dBuV	dB	dBuV/m	dBuV/m	dB		
1		35.9817	36.14	-12.40	23.74	40.00	-16.26	peak	
2	*	69.6407	43.75	-14.03	29.72	40.00	-10.28	peak	
3		189.3710	46.71	-14.51	32.20	43.50	-11.30	peak	
4		560.0080	33.61	-5.11	28.50	46.00	-17.50	peak	
5		640.0007	32.98	-3.39	29.59	46.00	-16.41	peak	
6		799.9860	34.36	-0.91	33.45	46.00	-12.55	peak	

REMARKS:

- (1) Measurement Value = Reading Level + Correct Factor.
- (2) Margin Level = Measurement Value - Limit Value.

Test Mode	BLE 5.0 (1 Mbps)	Test Date	2023/5/26
Test Frequency	2440MHz	Polarization	Horizontal
Temp	23°C	Hum.	58%



No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV/m	Limit dBuV/m	Over dB	Detector	Comment
1		69.4467	40.34	-13.99	26.35	40.00	-13.65	peak	
2		110.6070	43.19	-15.13	28.06	43.50	-15.44	peak	
3		190.3410	47.62	-14.62	33.00	43.50	-10.50	QP	
4		640.0330	35.13	-3.39	31.74	46.00	-14.26	peak	
5		719.9933	36.53	-2.23	34.30	46.00	-11.70	peak	
6	*	799.9860	43.27	-0.91	42.36	46.00	-3.64	QP	


REMARKS:

- (1) Measurement Value = Reading Level + Correct Factor.
- (2) Margin Level = Measurement Value - Limit Value.

APPENDIX C OUTPUT POWER

Test Mode :	BLE (1Mbps)	Tested Date	2023/6/20
-------------	-------------	-------------	-----------

Frequency (MHz)	Conducted Output Power		Max. Limit		Result
	(dBm)	(W)	(dBm)	(W)	
2402	2.90	0.0019	30.00	1.0000	Complies
2440	3.33	0.0022	30.00	1.0000	Complies
2480	2.95	0.0020	30.00	1.0000	Complies



End of Test Report