9.1.12. LTE BAND 66

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 31300
Configuration: EUT Only
Mode: LTE Band 66, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1720.0MHz)										
3.44	-63.0	H	3.0	-15.1	37.7	1.0	-51.8	-13.0	-38.8	
5.16	-65.8	H	3.0	-15.5	36.8	1.0	-51.4	-13.0	-38.4	
6.88	-66.5	H	3.0	-13.4	36.4	1.0	-48.8	-13.0	-35.8	
3.44	-63.5	V	3.0	-16.4	37.7	1.0	-53.1	-13.0	-40.1	
5.16	-64.3	V	3.0	-13.9	36.8	1.0	-49.7	-13.0	-36.7	
6.88	-65.3	V	3.0	-12.4	36.4	1.0	-47.8	-13.0	-34.8	
Mid Channel (1745.0MHz)										
3.49	-63.0	H	3.0	-15.1	37.6	1.0	-51.8	-13.0	-38.8	
5.24	-66.2	H	3.0	-15.7	36.8	1.0	-51.5	-13.0	-38.5	
6.98	-66.6	H	3.0	-13.4	36.4	1.0	-48.8	-13.0	-35.8	
3.49	-64.1	V	3.0	-16.9	37.6	1.0	-53.6	-13.0	-40.6	
5.24	-65.1	V	3.0	-14.5	36.8	1.0	-50.3	-13.0	-37.3	
6.98	-66.2	V	3.0	-13.2	36.4	1.0	-48.6	-13.0	-35.6	
High Channel (1770.0MHz)										
3.54	-63.2	H	3.0	-15.3	37.6	1.0	-51.9	-13.0	-38.9	
5.31	-65.9	H	3.0	-15.3	36.8	1.0	-51.1	-13.0	-38.1	
7.08	-66.7	H	3.0	-13.4	36.3	1.0	-48.7	-13.0	-35.7	
3.54	-63.3	V	3.0	-16.9	37.6	1.0	-52.5	-13.0	-39.5	
5.31	-65.8	V	3.0	-15.1	36.8	1.0	-50.9	-13.0	-37.9	
7.08	-66.2	V	3.0	-13.1	36.3	1.0	-48.4	-13.0	-35.4	

Rev. 02.24.17

LTE B66 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 31300
Configuration: EUT Only
Mode: LTE Band 66, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1720.0MHz)										
3.44	-63.7	H	3.0	-15.9	37.7	1.0	-52.6	-13.0	-39.6	
5.16	-64.3	H	3.0	-14.0	36.8	1.0	-49.9	-13.0	-36.9	
6.88	-66.2	H	3.0	-13.1	36.4	1.0	-48.6	-13.0	-35.6	
3.44	-63.0	V	3.0	-16.9	37.7	1.0	-52.6	-13.0	-39.6	
5.16	-64.3	V	3.0	-13.9	36.8	1.0	-49.7	-13.0	-36.7	
6.88	-66.2	V	3.0	-13.2	36.4	1.0	-48.7	-13.0	-35.7	
Mid Channel (1745.0MHz)										
3.49	-63.0	H	3.0	-15.1	37.6	1.0	-51.7	-13.0	-38.7	
5.24	-66.3	H	3.0	-15.9	36.8	1.0	-51.7	-13.0	-38.7	
6.98	-66.1	H	3.0	-12.8	36.4	1.0	-48.2	-13.0	-35.2	
3.49	-63.4	V	3.0	-16.1	37.6	1.0	-52.8	-13.0	-39.8	
5.24	-64.8	V	3.0	-14.2	36.8	1.0	-50.0	-13.0	-37.0	
6.98	-66.4	V	3.0	-13.4	36.4	1.0	-48.8	-13.0	-35.8	
High Channel (1770.0MHz)										
3.54	-63.4	H	3.0	-15.5	37.6	1.0	-52.1	-13.0	-39.1	
5.31	-65.7	H	3.0	-15.1	36.8	1.0	-51.0	-13.0	-38.0	
7.08	-66.0	H	3.0	-12.6	36.3	1.0	-47.9	-13.0	-34.9	
3.54	-63.6	V	3.0	-16.3	37.6	1.0	-52.9	-13.0	-39.9	
5.31	-66.1	V	3.0	-15.4	36.8	1.0	-51.2	-13.0	-38.2	
7.08	-67.2	V	3.0	-14.1	36.3	1.0	-49.4	-13.0	-36.4	

Rev. 02.24.17

LTE B66 20MHz 16QAM

9.1.13. LTE BAND 71

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/17/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 71, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (673MHz)										
1.35	-65.3	H	3.0	-26.9	34.2	1.0	-59.0	-13.0	-46.0	
2.02	-66.1	H	3.0	-22.6	33.5	1.0	-55.1	-13.0	-42.1	
2.69	-64.8	H	3.0	-19.5	34.4	1.0	-52.9	-13.0	-39.9	
1.35	-67.2	V	3.0	-26.3	34.2	1.0	-58.5	-13.0	-45.5	
2.02	-67.4	V	3.0	-23.8	33.5	1.0	-56.3	-13.0	-43.3	
2.69	-66.8	V	3.0	-21.0	34.4	1.0	-54.4	-13.0	-41.4	
Mid Channel (680.5MHz)										
1.36	-66.5	H	3.0	-27.0	34.1	1.0	-60.1	-13.0	-47.1	
2.04	-66.8	H	3.0	-23.2	33.5	1.0	-55.8	-13.0	-42.8	
2.72	-66.7	H	3.0	-21.2	34.4	1.0	-54.6	-13.0	-41.6	
1.36	-66.0	V	3.0	-24.0	34.1	1.0	-57.1	-13.0	-44.1	
2.04	-66.7	V	3.0	-23.0	33.5	1.0	-55.6	-13.0	-42.6	
2.72	-66.8	V	3.0	-20.8	34.4	1.0	-54.2	-13.0	-41.2	
High Channel (688MHz)										
1.38	-66.7	H	3.0	-27.1	34.1	1.0	-60.2	-13.0	-47.2	
2.06	-66.8	H	3.0	-23.2	33.6	1.0	-55.8	-13.0	-42.8	
2.75	-66.9	H	3.0	-21.3	34.5	1.0	-54.7	-13.0	-41.7	
1.38	-67.0	V	3.0	-24.9	34.1	1.0	-57.9	-13.0	-44.9	
2.06	-66.7	V	3.0	-23.0	33.6	1.0	-55.5	-13.0	-42.5	
2.75	-67.6	V	3.0	-21.5	34.5	1.0	-54.9	-13.0	-41.9	

Rev. 12.18.15

LTE B71 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/17/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 71, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (673MHz)										
1.35	-67.8	H	3.0	-27.6	34.2	1.0	-60.7	-13.0	-47.7	
2.02	-66.8	H	3.0	-23.3	33.5	1.0	-55.8	-13.0	-42.8	
2.69	-66.9	H	3.0	-21.6	34.4	1.0	-55.0	-13.0	-42.0	
1.35	-66.0	V	3.0	-24.1	34.2	1.0	-57.3	-13.0	-44.3	
2.02	-65.8	V	3.0	-22.2	33.5	1.0	-54.7	-13.0	-41.7	
2.69	-66.5	V	3.0	-20.7	34.4	1.0	-54.1	-13.0	-41.1	
Mid Channel (680.5MHz)										
1.36	-66.5	H	3.0	-27.0	34.1	1.0	-60.1	-13.0	-47.1	
2.04	-66.9	H	3.0	-23.3	33.5	1.0	-55.9	-13.0	-42.9	
2.72	-66.8	H	3.0	-21.3	34.4	1.0	-54.7	-13.0	-41.7	
1.36	-66.3	V	3.0	-24.3	34.1	1.0	-57.4	-13.0	-44.4	
2.04	-66.5	V	3.0	-22.8	33.5	1.0	-55.4	-13.0	-42.4	
2.72	-65.2	V	3.0	-19.2	34.4	1.0	-52.6	-13.0	-39.6	
High Channel (688MHz)										
1.38	-67.6	H	3.0	-28.0	34.1	1.0	-61.1	-13.0	-48.1	
2.06	-66.4	H	3.0	-22.8	33.6	1.0	-55.4	-13.0	-42.4	
2.75	-66.9	H	3.0	-21.3	34.5	1.0	-54.7	-13.0	-41.7	
1.38	-66.3	V	3.0	-24.2	34.1	1.0	-57.2	-13.0	-44.2	
2.06	-66.7	V	3.0	-23.0	33.6	1.0	-55.5	-13.0	-42.5	
2.75	-67.4	V	3.0	-21.2	34.5	1.0	-54.7	-13.0	-41.7	

Rev. 12.18.15

LTE B71 20MHz 16QAM

UL VERIFICATION SERVICES INC. FORM NO: CCSUP4031B
47173 BENICIA STREET, FREMONT, CA 94538, USA TEL: (510) 771-1000 FAX: (510) 661-0888
This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.2. FIELD STRENGTH OF SPURIOUS RADIATION (ANT2)

9.2.1. LTE BAND 2

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/10/18
Test Engineer: 12482
Configuration: EUT only
Mode: LTE Band 2, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber G | Pre-amplifer: 3m Chamber G | Filter: Filter | Limit: EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.70	-62.1	H	3.0	-15.3	36.2	1.0	-50.5	-13.0	-37.5	
5.56	-64.3	H	3.0	-14.0	36.1	1.0	-49.1	-13.0	-36.1	
7.44	-69.0	H	3.0	-15.9	35.2	1.0	-50.1	-13.0	-37.1	
3.70	-63.7	V	3.0	-16.5	36.2	1.0	-51.7	-13.0	-38.7	
5.56	-62.5	V	3.0	-12.4	36.1	1.0	-47.5	-13.0	-34.5	
7.44	-69.4	V	3.0	-16.4	35.2	1.0	-50.5	-13.0	-37.5	
Mid Channel (1880MHz)										
3.76	-62.6	H	3.0	-15.7	36.2	1.0	-50.9	-13.0	-37.9	
5.61	-65.0	H	3.0	-14.6	36.1	1.0	-49.7	-13.0	-36.7	
7.52	-68.8	H	3.0	-15.6	35.1	1.0	-49.8	-13.0	-36.8	
3.74	-62.7	V	3.0	-15.4	36.2	1.0	-50.6	-13.0	-37.6	
5.61	-59.2	V	3.0	-9.0	36.1	1.0	-44.1	-13.0	-31.1	
7.52	-68.5	V	3.0	-15.4	35.1	1.0	-49.5	-13.0	-36.5	
High Channel (1900MHz)										
3.80	-66.8	H	3.0	-19.8	36.2	1.0	-55.0	-13.0	-42.0	
5.70	-67.4	H	3.0	-16.9	36.1	1.0	-51.9	-13.0	-38.9	
7.60	-69.7	H	3.0	-16.4	35.1	1.0	-50.5	-13.0	-37.5	
3.80	-66.2	V	3.0	-18.7	36.2	1.0	-53.9	-13.0	-40.9	
5.70	-67.6	V	3.0	-17.3	36.1	1.0	-52.3	-13.0	-39.3	
7.60	-68.6	V	3.0	-15.4	35.1	1.0	-49.4	-13.0	-36.4	

Rev. 05.21.15

LTE B2 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/10/18
Test Engineer: 12482
Configuration: EUT Only
Mode: LTE Band 2, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber G | Pre-amplifer: 3m Chamber G | Filter: Filter | Limit: EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-67.4	H	3.0	-20.6	36.2	1.0	-55.8	-13.0	-42.8	
5.58	-64.0	H	3.0	-13.6	36.1	1.0	-48.8	-13.0	-35.8	
7.44	-69.3	H	3.0	-16.2	35.2	1.0	-50.4	-13.0	-37.4	
3.72	-67.8	V	3.0	-20.6	36.2	1.0	-55.8	-13.0	-42.8	
5.58	-64.2	V	3.0	-14.0	36.1	1.0	-49.1	-13.0	-36.1	
7.44	-69.8	V	3.0	-16.8	35.2	1.0	-51.0	-13.0	-38.0	
Mid Channel (1880MHz)										
3.76	-66.1	H	3.0	-19.2	36.2	1.0	-54.4	-13.0	-41.4	
5.64	-66.9	H	3.0	-16.4	36.1	1.0	-51.5	-13.0	-38.5	
7.52	-68.8	H	3.0	-15.7	35.1	1.0	-49.8	-13.0	-36.8	
3.76	-66.9	V	3.0	-19.6	36.2	1.0	-54.8	-13.0	-41.8	
5.64	-67.4	V	3.0	-17.1	36.1	1.0	-52.2	-13.0	-39.2	
7.52	-67.2	V	3.0	-14.1	35.1	1.0	-48.2	-13.0	-35.2	
High Channel (1900MHz)										
3.80	-66.8	H	3.0	-19.9	36.2	1.0	-55.0	-13.0	-42.0	
5.70	-67.5	H	3.0	-17.0	36.1	1.0	-52.0	-13.0	-39.0	
7.60	-69.1	H	3.0	-15.9	35.1	1.0	-49.9	-13.0	-36.9	
3.80	-66.9	V	3.0	-19.4	36.2	1.0	-54.6	-13.0	-41.6	
5.70	-68.0	V	3.0	-17.6	36.1	1.0	-52.7	-13.0	-39.7	
7.60	-69.8	V	3.0	-16.6	35.1	1.0	-50.7	-13.0	-37.7	

Rev. 05.21.15

LTE B2 20MHz 16QAM

9.2.2. LTE BAND 5

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/11/18
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 5, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber F | Pre-amplifer: 3m Chamber F | Filter: Filter | Limit: EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (829MHz)										
1.66	-68.0	H	3.0	-26.7	33.7	1.0	-59.4	-13.0	-46.4	
2.49	-68.9	H	3.0	-24.7	34.1	1.0	-57.8	-13.0	-44.8	
3.32	-68.8	H	3.0	-20.5	34.6	1.0	-54.1	-13.0	-41.1	
1.66	-67.3	V	3.0	-23.9	33.7	1.0	-56.6	-13.0	-43.6	
2.49	-69.0	V	3.0	-24.2	34.1	1.0	-57.3	-13.0	-44.3	
3.32	-69.1	V	3.0	-20.6	34.6	1.0	-54.2	-13.0	-41.2	
Mid Channel (836.5MHz)										
1.67	-66.9	H	3.0	-15.5	33.7	1.0	-48.2	-13.0	-35.2	
2.51	-68.2	H	3.0	-23.9	34.1	1.0	-57.0	-13.0	-44.0	
3.35	-68.6	H	3.0	-20.2	34.6	1.0	-53.8	-13.0	-40.8	
1.67	-49.6	V	3.0	-6.2	33.7	1.0	-38.9	-13.0	-25.9	
2.51	-68.2	V	3.0	-23.4	34.1	1.0	-56.5	-13.0	-43.5	
3.35	-68.0	V	3.0	-19.3	34.6	1.0	-52.9	-13.0	-39.9	
High Channel (844MHz)										
1.69	-67.9	H	3.0	-26.5	33.7	1.0	-59.2	-13.0	-46.2	
2.53	-67.9	H	3.0	-23.6	34.1	1.0	-56.7	-13.0	-43.7	
3.38	-68.8	H	3.0	-20.3	34.6	1.0	-53.9	-13.0	-40.9	
1.69	-64.4	V	3.0	-21.0	33.7	1.0	-53.7	-13.0	-40.7	
2.53	-68.9	V	3.0	-23.9	34.1	1.0	-57.1	-13.0	-44.1	
3.38	-67.9	V	3.0	-19.1	34.6	1.0	-52.7	-13.0	-39.7	

Rev. 05.21.15

LTE B5 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/11/18
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 5, 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber F | Pre-amplifer: 3m Chamber F | Filter: Filter | Limit: EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (829MHz)										
1.66	-67.4	H	3.0	-25.9	33.7	1.0	-58.6	-13.0	-45.6	
2.49	-68.0	H	3.0	-24.8	34.1	1.0	-57.9	-13.0	-44.9	
3.32	-69.1	H	3.0	-23.1	34.6	1.0	-56.8	-13.0	-43.8	
1.66	-65.4	V	3.0	-23.6	33.7	1.0	-56.3	-13.0	-43.3	
2.49	-68.2	V	3.0	-24.1	34.1	1.0	-57.2	-13.0	-44.2	
3.32	-68.7	V	3.0	-22.7	34.6	1.0	-56.4	-13.0	-43.4	
Mid Channel (836.5MHz)										
1.67	-66.4	H	3.0	-14.9	33.7	1.0	-47.6	-13.0	-34.6	
2.51	-68.2	H	3.0	-25.0	34.1	1.0	-58.1	-13.0	-45.1	
3.35	-68.5	H	3.0	-22.5	34.6	1.0	-56.1	-13.0	-43.1	
1.67	-66.7	V	3.0	-24.0	33.7	1.0	-56.6	-13.0	-43.6	
2.51	-68.0	V	3.0	-23.7	34.1	1.0	-56.8	-13.0	-43.8	
3.35	-68.5	V	3.0	-22.6	34.6	1.0	-56.1	-13.0	-43.1	
High Channel (844MHz)										
1.69	-65.8	H	3.0	-24.3	33.7	1.0	-57.0	-13.0	-44.0	
2.53	-67.9	H	3.0	-24.6	34.1	1.0	-57.7	-13.0	-44.7	
3.38	-68.8	H	3.0	-22.7	34.6	1.0	-56.3	-13.0	-43.3	
1.69	-66.7	V	3.0	-24.9	33.7	1.0	-57.6	-13.0	-44.6	
2.53	-66.7	V	3.0	-22.4	34.1	1.0	-55.6	-13.0	-42.6	
3.38	-67.7	V	3.0	-21.5	34.6	1.0	-55.1	-13.0	-42.1	

Rev. 05.21.15

LTE B5 10MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.2.3. LTE BAND 7

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 7, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)										
5.02	-65.9	H	3.0	-13.3	34.2	1.0	-46.5	-25.0	-21.5	
7.53	-68.4	H	3.0	-11.9	33.5	1.0	-44.4	-25.0	-19.4	
10.04	-70.8	H	3.0	-11.0	31.7	1.0	-41.6	-25.0	-16.6	
5.02	-65.3	V	3.0	-12.5	34.2	1.0	-45.7	-25.0	-20.7	
7.53	-68.2	V	3.0	-11.9	33.5	1.0	-44.4	-25.0	-19.4	
10.04	-68.5	V	3.0	-8.7	31.7	1.0	-39.4	-25.0	-14.4	
Mid Channel (2535MHz)										
5.07	-65.3	H	3.0	-12.6	34.2	1.0	-45.8	-25.0	-20.8	
7.61	-68.2	H	3.0	-11.6	33.5	1.0	-44.1	-25.0	-19.1	
10.14	-70.4	H	3.0	-10.5	31.7	1.0	-41.2	-25.0	-16.2	
5.07	-66.0	V	3.0	-13.1	34.2	1.0	-46.3	-25.0	-21.3	
7.61	-67.9	V	3.0	-11.5	33.5	1.0	-43.9	-25.0	-18.9	
10.14	-68.3	V	3.0	-8.5	31.7	1.0	-39.2	-25.0	-14.2	
High Channel (2560MHz)										
5.12	-64.9	H	3.0	-12.2	34.2	1.0	-46.3	-25.0	-20.3	
7.68	-68.3	H	3.0	-11.6	33.4	1.0	-44.0	-25.0	-19.0	
10.24	-69.0	H	3.0	-9.0	31.8	1.0	-39.9	-25.0	-14.9	
5.12	-66.1	V	3.0	-12.1	34.2	1.0	-46.3	-25.0	-20.3	
7.68	-66.3	V	3.0	-9.8	33.4	1.0	-42.2	-25.0	-17.2	
10.24	-68.2	V	3.0	-8.3	31.8	1.0	-39.1	-25.0	-14.1	

Rev. 05.21.15

LTE B7 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 7, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)										
5.02	-65.3	H	3.0	-12.7	34.2	1.0	-45.9	-25.0	-20.9	
7.53	-66.7	H	3.0	-10.2	33.5	1.0	-42.7	-25.0	-17.7	
10.04	-68.2	H	3.0	-8.4	31.7	1.0	-39.0	-25.0	-14.0	
5.02	-65.2	V	3.0	-12.4	34.2	1.0	-45.6	-25.0	-20.6	
7.53	-67.0	V	3.0	-10.7	33.5	1.0	-43.2	-25.0	-18.2	
10.04	-66.8	V	3.0	-7.0	31.7	1.0	-37.7	-25.0	-12.7	
Mid Channel (2535MHz)										
5.07	-65.8	H	3.0	-13.1	34.2	1.0	-46.3	-25.0	-21.3	
7.61	-67.7	H	3.0	-11.1	33.5	1.0	-43.6	-25.0	-18.6	
10.14	-66.4	H	3.0	-6.5	31.7	1.0	-37.2	-25.0	-12.2	
5.07	-65.6	V	3.0	-12.7	34.2	1.0	-45.9	-25.0	-20.9	
7.61	-65.5	V	3.0	-9.1	33.5	1.0	-41.5	-25.0	-16.5	
10.14	-67.9	V	3.0	-8.1	31.7	1.0	-38.8	-25.0	-13.8	
High Channel (2560MHz)										
5.12	-66.2	H	3.0	-13.5	34.2	1.0	-46.6	-25.0	-21.6	
7.68	-67.4	H	3.0	-10.7	33.4	1.0	-43.1	-25.0	-18.1	
10.24	-67.6	H	3.0	-7.6	31.8	1.0	-38.5	-25.0	-13.5	
5.12	-65.3	V	3.0	-12.3	34.2	1.0	-45.5	-25.0	-20.5	
7.68	-67.3	V	3.0	-10.8	33.4	1.0	-43.2	-25.0	-18.2	
10.24	-68.0	V	3.0	-8.1	31.8	1.0	-38.9	-25.0	-13.9	

Rev. 05.21.15

LTE B7 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.2.4. LTE BAND 12

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 12, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (704MHz)										
1.41	-67.6	H	3.0	-27.9	34.0	1.0	-60.9	-13.0	-47.9	
2.11	-67.2	H	3.0	-23.6	33.7	1.0	-56.2	-13.0	-43.2	
2.82	-66.8	H	3.0	-20.8	34.5	1.0	-54.3	-13.0	-41.3	
1.41	-66.2	V	3.0	-23.7	34.0	1.0	-56.8	-13.0	-43.8	
2.11	-66.7	V	3.0	-22.8	33.7	1.0	-55.5	-13.0	-42.5	
2.82	-67.0	V	3.0	-20.5	34.5	1.0	-54.1	-13.0	-41.1	
Mid Channel (707.5MHz)										
1.42	-67.7	H	3.0	-27.9	34.0	1.0	-60.9	-13.0	-47.9	
2.12	-66.4	H	3.0	-22.7	33.7	1.0	-55.4	-13.0	-42.4	
2.83	-66.9	H	3.0	-20.8	34.6	1.0	-54.4	-13.0	-41.4	
1.42	-67.6	V	3.0	-25.1	34.0	1.0	-58.1	-13.0	-45.1	
2.12	-67.2	V	3.0	-23.3	33.7	1.0	-56.0	-13.0	-43.0	
2.83	-66.5	V	3.0	-20.0	34.6	1.0	-53.5	-13.0	-40.5	
High Channel (711MHz)										
1.42	-65.2	H	3.0	-25.4	34.0	1.0	-58.4	-13.0	-45.4	
2.13	-66.4	H	3.0	-22.7	33.7	1.0	-55.4	-13.0	-42.4	
2.84	-66.5	H	3.0	-20.3	34.6	1.0	-53.9	-13.0	-40.9	
1.42	-64.0	V	3.0	-21.4	34.0	1.0	-54.4	-13.0	-41.4	
2.13	-66.6	V	3.0	-22.7	33.7	1.0	-55.4	-13.0	-42.4	
2.84	-65.3	V	3.0	-18.7	34.6	1.0	-52.3	-13.0	-39.3	

Rev. 05.21.15

LTE B12 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 12, 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (704MHz)										
1.41	-61.8	H	3.0	-22.1	34.0	1.0	-55.1	-13.0	-42.1	
2.11	-61.9	H	3.0	-18.3	33.7	1.0	-50.9	-13.0	-37.9	
2.82	-61.9	H	3.0	-15.9	34.5	1.0	-49.4	-13.0	-36.4	
1.41	-62.7	V	3.0	-20.2	34.0	1.0	-53.3	-13.0	-40.3	
2.11	-62.4	V	3.0	-18.5	33.7	1.0	-51.2	-13.0	-38.2	
2.82	-61.6	V	3.0	-15.1	34.5	1.0	-48.7	-13.0	-35.7	
Mid Channel (707.5MHz)										
1.42	-63.1	H	3.0	-23.3	34.0	1.0	-56.4	-13.0	-43.4	
2.12	-62.6	H	3.0	-18.9	33.7	1.0	-51.6	-13.0	-38.6	
2.83	-61.8	H	3.0	-15.7	34.6	1.0	-49.3	-13.0	-36.3	
1.42	-62.9	V	3.0	-20.4	34.0	1.0	-53.4	-13.0	-40.4	
2.12	-61.6	V	3.0	-17.7	33.7	1.0	-50.4	-13.0	-37.4	
2.83	-61.9	V	3.0	-15.4	34.6	1.0	-48.9	-13.0	-35.9	
High Channel (711MHz)										
1.42	-62.8	H	3.0	-23.0	34.0	1.0	-56.0	-13.0	-43.0	
2.13	-61.7	H	3.0	-18.0	33.7	1.0	-50.7	-13.0	-37.7	
2.84	-61.2	H	3.0	-15.0	34.6	1.0	-48.6	-13.0	-35.6	
1.42	-60.1	V	3.0	-17.5	34.0	1.0	-50.5	-13.0	-37.5	
2.13	-61.3	V	3.0	-17.4	33.7	1.0	-50.1	-13.0	-37.1	
2.84	-61.9	V	3.0	-15.3	34.6	1.0	-48.9	-13.0	-35.9	

Rev. 05.21.15

LTE B12 10MHz 16QAM

9.2.5. LTE BAND 13

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 13, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	LTE B13

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (782MHz)										
1.56	-66.9	H	3.0	-26.3	33.8	1.0	-59.1	-40.0	-19.1	
2.35	-66.3	H	3.0	-22.4	34.1	1.0	-55.5	-13.0	-42.5	
3.13	-65.4	H	3.0	-17.8	34.8	1.0	-51.6	-13.0	-38.6	
1.56	-65.8	V	3.0	-22.4	33.8	1.0	-55.2	-40.0	-15.2	
2.35	-66.0	V	3.0	-21.5	34.1	1.0	-54.6	-13.0	-41.6	
3.13	-65.5	V	3.0	-17.6	34.8	1.0	-51.4	-13.0	-38.4	

Rev. 05.21.15

LTE B13 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 13, 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	LTE B13

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (782MHz)										
1.56	-66.3	H	3.0	-25.7	33.8	1.0	-58.5	-40.0	-18.5	
2.35	-61.3	H	3.0	-17.4	34.1	1.0	-50.5	-13.0	-37.5	
3.13	-60.7	H	3.0	-13.1	34.8	1.0	-46.9	-13.0	-33.9	
1.56	-66.8	V	3.0	-23.4	33.8	1.0	-56.2	-40.0	-16.2	
2.35	-67.2	V	3.0	-22.6	34.1	1.0	-55.7	-13.0	-42.7	
3.13	-66.0	V	3.0	-18.1	34.8	1.0	-51.9	-13.0	-38.9	

Rev. 05.21.15

LTE B13 10MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.2.6. LTE BAND 14

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 14, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber F | Pre-amplifer: 3m Chamber F | Filter: Filter | Limit: EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (793MHz) [BW 10MHz]										
1.59	-69.2	H	3.0	-28.5	33.8	1.0	-61.2	-40.0	-21.2	
2.38	-70.6	H	3.0	-26.7	34.2	1.0	-59.8	-13.0	-46.8	
3.17	-70.9	H	3.0	-23.1	34.7	1.0	-56.9	-13.0	-43.9	
1.59	-70.0	V	3.0	-26.6	33.8	1.0	-59.4	-40.0	-19.4	
2.38	-70.3	V	3.0	-25.7	34.2	1.0	-58.8	-13.0	-45.8	
3.17	-70.8	V	3.0	-22.8	34.7	1.0	-56.5	-13.0	-43.5	

Rev. 05.21.15

LTE B14 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 14, 5MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber F | Pre-amplifer: 3m Chamber F | Filter: Filter | Limit: EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (793MHz) [BW 10MHz]										
1.59	-68.5	H	3.0	-27.8	33.8	1.0	-60.5	-40.0	-20.5	
2.38	-70.8	H	3.0	-26.9	34.2	1.0	-60.0	-13.0	-47.0	
3.17	-70.8	H	3.0	-23.0	34.7	1.0	-56.8	-13.0	-43.8	
1.59	-69.2	V	3.0	-25.8	33.8	1.0	-58.6	-40.0	-18.6	
2.38	-70.5	V	3.0	-25.9	34.2	1.0	-59.0	-13.0	-46.0	
3.17	-70.3	V	3.0	-22.3	34.7	1.0	-56.0	-13.0	-43.0	

Rev. 05.21.15

LTE B14 10MHz 16QAM

9.2.7. LTE BAND 17

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 17, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber F | Pre-amplifer: 3m Chamber F | Filter: Filter | Limit: EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (710MHz)										
1.42	-67.1	H	3.0	-27.4	34.0	1.0	-60.4	-13.0	-47.4	
2.13	-66.4	H	3.0	-22.7	33.7	1.0	-55.4	-13.0	-42.4	
2.84	-66.7	H	3.0	-20.5	34.6	1.0	-54.1	-13.0	-41.1	
1.42	-67.0	V	3.0	-24.4	34.0	1.0	-57.4	-13.0	-44.4	
2.13	-67.0	V	3.0	-23.1	33.7	1.0	-55.8	-13.0	-42.8	
2.84	-66.6	V	3.0	-20.0	34.6	1.0	-53.6	-13.0	-40.6	

Rev. 05.21.15

LTE B17 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 17, 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber F | Pre-amplifer: 3m Chamber F | Filter: Filter | Limit: EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (710MHz)										
1.42	-67.7	H	3.0	-27.9	34.0	1.0	-60.9	-13.0	-47.9	
2.13	-66.5	H	3.0	-22.8	33.7	1.0	-55.5	-13.0	-42.5	
2.84	-66.7	H	3.0	-20.5	34.6	1.0	-54.1	-13.0	-41.1	
1.42	-67.4	V	3.0	-24.8	34.0	1.0	-57.8	-13.0	-44.8	
2.13	-66.0	V	3.0	-22.1	33.7	1.0	-54.8	-13.0	-41.8	
2.84	-65.4	V	3.0	-18.8	34.6	1.0	-52.4	-13.0	-39.4	

Rev. 05.21.15

LTE B17 10MHz 16QAM

UL VERIFICATION SERVICES INC. FORM NO: CCSUP4031B
47173 BENICIA STREET, FREMONT, CA 94538, USA TEL: (510) 771-1000 FAX: (510) 661-0888
This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.2.8. LTE BAND 25

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 25, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.70	-65.5	H	3.0	-15.7	34.4	1.0	-49.1	-13.0	-36.1	
5.56	-62.5	H	3.0	-9.1	34.1	1.0	-42.2	-13.0	-29.2	
7.44	-68.9	H	3.0	-12.5	33.6	1.0	-45.1	-13.0	-32.1	
3.70	-64.0	V	3.0	-14.1	34.4	1.0	-47.6	-13.0	-34.6	
5.56	-61.5	V	3.0	-7.9	34.1	1.0	-41.0	-13.0	-28.0	
7.44	-68.9	V	3.0	-12.7	33.6	1.0	-45.3	-13.0	-32.3	
Mid Channel (1882.5MHz)										
3.74	-62.1	H	3.0	-12.2	34.4	1.0	-45.6	-13.0	-32.6	
5.62	-64.2	H	3.0	-10.7	34.1	1.0	-43.8	-13.0	-30.8	
7.53	-68.1	H	3.0	-11.6	33.5	1.0	-44.1	-13.0	-31.1	
3.74	-61.1	V	3.0	-11.0	34.4	1.0	-44.5	-13.0	-31.5	
5.62	-63.4	V	3.0	-9.6	34.1	1.0	-42.7	-13.0	-29.7	
7.53	-67.6	V	3.0	-11.3	33.5	1.0	-43.8	-13.0	-30.8	
High Channel (1905MHz)										
3.79	-63.6	H	3.0	-13.5	34.4	1.0	-46.9	-13.0	-33.9	
5.69	-65.4	H	3.0	-11.8	34.1	1.0	-44.9	-13.0	-31.9	
7.62	-69.1	H	3.0	-12.5	33.4	1.0	-45.0	-13.0	-32.0	
3.79	-62.5	V	3.0	-12.3	34.4	1.0	-45.7	-13.0	-32.7	
5.69	-65.0	V	3.0	-11.2	34.1	1.0	-44.3	-13.0	-31.3	
7.62	-68.3	V	3.0	-11.9	33.4	1.0	-44.3	-13.0	-31.3	

Rev. 05.21.15

LTE B25 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 25, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.70	-64.3	H	3.0	-14.5	34.4	1.0	-48.0	-13.0	-35.0	
5.58	-67.1	H	3.0	-13.6	34.1	1.0	-46.8	-13.0	-33.8	
7.44	-68.1	H	3.0	-11.7	33.6	1.0	-44.3	-13.0	-31.3	
3.70	-63.0	V	3.0	-13.2	34.4	1.0	-46.6	-13.0	-33.6	
5.58	-66.5	V	3.0	-12.9	34.1	1.0	-46.0	-13.0	-33.0	
7.44	-69.4	V	3.0	-13.2	33.6	1.0	-45.8	-13.0	-32.8	
Mid Channel (1882.5MHz)										
3.74	-62.8	H	3.0	-12.8	34.4	1.0	-46.3	-13.0	-33.3	
5.65	-67.4	H	3.0	-13.8	34.1	1.0	-46.9	-13.0	-33.9	
7.53	-68.0	H	3.0	-11.5	33.5	1.0	-44.0	-13.0	-31.0	
3.74	-63.3	V	3.0	-13.3	34.4	1.0	-46.7	-13.0	-33.7	
5.65	-67.7	V	3.0	-14.0	34.1	1.0	-47.1	-13.0	-34.1	
7.53	-67.9	V	3.0	-11.5	33.5	1.0	-44.1	-13.0	-31.1	
High Channel (1905MHz)										
3.79	-62.5	H	3.0	-12.4	34.4	1.0	-45.8	-13.0	-32.8	
5.69	-66.1	H	3.0	-12.4	34.1	1.0	-45.5	-13.0	-32.5	
7.62	-69.5	H	3.0	-12.9	33.4	1.0	-45.3	-13.0	-32.3	
3.79	-64.0	V	3.0	-13.8	34.4	1.0	-47.2	-13.0	-34.2	
5.69	-62.9	V	3.0	-9.1	34.1	1.0	-42.2	-13.0	-29.2	
7.62	-69.7	V	3.0	-13.3	33.4	1.0	-45.7	-13.0	-32.7	

Rev. 05.21.15

LTE B25 20MHz 16QAM

9.2.9. LTE BAND 26 (PART 90S)

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 26 (90S), 15MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (831.5MHz)										
1.66	-41.9	H	3.0	-0.6	33.7	1.0	-33.3	-13.0	-20.3	
2.49	-66.3	H	3.0	-22.1	34.1	1.0	-55.2	-13.0	-42.2	
3.33	-66.7	H	3.0	-18.4	34.6	1.0	-52.0	-13.0	-39.0	
1.66	-47.0	V	3.0	-3.5	33.7	1.0	-36.2	-13.0	-23.2	
2.49	-66.7	V	3.0	-21.9	34.1	1.0	-55.0	-13.0	-42.0	
3.33	-67.3	V	3.0	-18.7	34.6	1.0	-52.4	-13.0	-39.4	

Rev. 05.21.15

LTE B26 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 26 (90S), 15MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (831.5MHz)										
1.66	-41.7	H	3.0	-0.4	33.7	1.0	-33.1	-13.0	-20.1	
2.49	-66.8	H	3.0	-22.6	34.1	1.0	-55.7	-13.0	-42.7	
3.33	-66.6	H	3.0	-18.3	34.6	1.0	-51.9	-13.0	-38.9	
1.66	-49.6	V	3.0	-6.2	33.7	1.0	-38.9	-13.0	-25.9	
2.49	-66.4	V	3.0	-21.6	34.1	1.0	-54.7	-13.0	-41.7	
3.33	-67.8	V	3.0	-19.2	34.6	1.0	-52.9	-13.0	-39.9	

Rev. 05.21.15

LTE B26 10MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.2.10. LTE BAND 30

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 10643
Configuration: EUT only
Mode: LTE Band 30, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	LTE B30

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (2310MHz)										
4.62	-71.4	H	3.0	-17.6	37.9	1.0	-54.5	-40.0	-14.5	
6.93	-69.7	H	3.0	-11.1	36.5	1.0	-46.5	-40.0	-6.5	
9.24	-73.6	H	3.0	-12.1	34.9	1.0	-45.9	-40.0	-5.9	
4.62	-70.8	V	3.0	-17.1	37.9	1.0	-54.0	-40.0	-14.0	
6.93	-69.7	V	3.0	-10.2	36.5	1.0	-45.7	-40.0	-5.7	
9.24	-73.8	V	3.0	-12.0	34.9	1.0	-45.9	-40.0	-5.9	

Rev. 05.21.15

LTE B30 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 10643
Configuration: EUT only
Mode: LTE Band 30, 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	LTE B30

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (2310MHz)										
4.62	-70.7	H	3.0	-16.9	37.9	1.0	-53.8	-40.0	-13.8	
6.93	-68.7	H	3.0	-10.1	36.5	1.0	-45.5	-40.0	-5.5	
9.24	-73.8	H	3.0	-12.3	34.9	1.0	-46.1	-40.0	-6.1	
4.62	-71.6	V	3.0	-17.9	37.9	1.0	-54.8	-40.0	-14.8	
6.93	-69.5	V	3.0	-10.0	36.5	1.0	-45.5	-40.0	-5.5	
9.24	-73.6	V	3.0	-11.8	34.9	1.0	-45.7	-40.0	-5.7	

Rev. 05.21.15

LTE B30 10MHz 16QAM

9.2.11. LTE BAND 41

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 4/13/2018
Test Enginee 12500
Configuration EUT only
Mode: LTE Band 41, 20MHz QPSK (IC)

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)										
5.02	-66.2	H	3.0	-13.7	34.2	1.0	-46.9	-25.0	-21.9	
7.53	-67.0	H	3.0	-10.5	33.5	1.0	-43.0	-25.0	-18.0	
10.04	-67.9	H	3.0	-8.1	31.7	1.0	-38.7	-25.0	-13.7	
5.02	-66.3	V	3.0	-13.5	34.2	1.0	-46.7	-25.0	-21.7	
7.53	-65.3	V	3.0	-9.0	33.5	1.0	-41.5	-25.0	-16.5	
10.04	-67.8	V	3.0	-8.1	31.7	1.0	-38.7	-25.0	-13.7	
Mid Channel (2595MHz)										
5.19	-66.5	H	3.0	-13.7	34.2	1.0	-46.8	-25.0	-21.8	
7.79	-66.9	H	3.0	-10.1	33.3	1.0	-42.4	-25.0	-17.4	
10.38	-67.8	H	3.0	-7.8	31.9	1.0	-38.7	-25.0	-13.7	
5.19	-65.3	V	3.0	-12.2	34.2	1.0	-45.4	-25.0	-20.4	
7.79	-66.6	V	3.0	-10.0	33.3	1.0	-42.3	-25.0	-17.3	
10.38	-67.1	V	3.0	-7.1	31.9	1.0	-38.0	-25.0	-13.0	
High Channel (2680MHz)										
5.36	-66.5	H	3.0	-13.4	34.2	1.0	-46.6	-25.0	-21.6	
8.04	-67.0	H	3.0	-9.8	33.1	1.0	-42.0	-25.0	-17.0	
10.72	-67.4	H	3.0	-7.2	32.2	1.0	-38.4	-25.0	-13.4	
5.36	-66.8	V	3.0	-13.5	34.2	1.0	-46.6	-25.0	-21.6	
8.04	-66.3	V	3.0	-9.3	33.1	1.0	-41.4	-25.0	-16.4	
10.72	-68.0	V	3.0	-7.7	32.2	1.0	-38.9	-25.0	-13.9	

Rev. 05.21.15

LTE B41 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/13/18
Test Engineer: 12500
Configuration: EUT Only
Mode: LTE Band 41, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz)										
5.01	-66.8	H	3.0	-14.2	34.2	1.0	-47.4	-25.0	-22.4	
7.52	-67.9	H	3.0	-11.4	33.5	1.0	-43.9	-25.0	-18.9	
10.02	-68.7	H	3.0	-8.9	31.6	1.0	-39.5	-25.0	-14.5	
5.01	-66.9	V	3.0	-14.1	34.2	1.0	-47.3	-25.0	-22.3	
7.52	-65.9	V	3.0	-9.6	33.5	1.0	-42.1	-25.0	-17.1	
10.02	-68.4	V	3.0	-8.7	31.6	1.0	-39.3	-25.0	-14.3	
Mid Channel (2593MHz)										
5.19	-66.8	H	3.0	-14.0	34.2	1.0	-47.1	-25.0	-22.1	
7.78	-67.5	H	3.0	-10.7	33.3	1.0	-43.0	-25.0	-18.0	
10.37	-68.4	H	3.0	-8.4	31.9	1.0	-39.3	-25.0	-14.3	
5.19	-65.9	V	3.0	-12.8	34.2	1.0	-45.9	-25.0	-20.9	
7.78	-67.2	V	3.0	-10.6	33.3	1.0	-42.9	-25.0	-17.9	
10.37	-67.7	V	3.0	-7.6	31.9	1.0	-38.5	-25.0	-13.6	
High Channel (2680MHz)										
5.36	-67.1	H	3.0	-14.0	34.2	1.0	-47.1	-25.0	-22.1	
8.04	-66.9	H	3.0	-9.7	33.1	1.0	-41.9	-25.0	-16.9	
10.72	-68.0	H	3.0	-7.7	32.2	1.0	-38.9	-25.0	-13.9	
5.36	-67.4	V	3.0	-14.0	34.2	1.0	-47.2	-25.0	-22.2	
8.04	-66.7	V	3.0	-9.7	33.1	1.0	-41.8	-25.0	-16.8	
10.72	-68.6	V	3.0	-8.2	32.2	1.0	-39.4	-25.0	-14.4	

Rev. 05.21.15

LTE B41 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.2.12. LTE BAND 66

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 12500
Configuration: EUT Only
Mode: LTE Band 66, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1720.0MHz)										
3.44	-66.9	H	3.0	-18.1	34.6	1.0	-51.7	-13.0	-38.7	
5.16	-66.4	H	3.0	-13.6	34.2	1.0	-46.8	-13.0	-33.8	
6.88	-68.0	H	3.0	-12.4	33.9	1.0	-45.3	-13.0	-32.3	
3.44	-65.7	V	3.0	-16.7	34.6	1.0	-50.3	-13.0	-37.3	
5.16	-66.0	V	3.0	-12.9	34.2	1.0	-46.1	-13.0	-33.1	
6.88	-67.5	V	3.0	-12.1	33.9	1.0	-45.0	-13.0	-32.0	
Mid Channel (1745.0MHz)										
3.49	-66.7	H	3.0	-17.8	34.6	1.0	-51.3	-13.0	-38.3	
5.24	-68.2	H	3.0	-15.3	34.2	1.0	-48.4	-13.0	-35.4	
6.98	-68.1	H	3.0	-12.3	33.9	1.0	-45.3	-13.0	-32.3	
3.49	-66.2	V	3.0	-17.0	34.6	1.0	-50.6	-13.0	-37.6	
5.24	-67.4	V	3.0	-14.2	34.2	1.0	-47.4	-13.0	-34.4	
6.98	-68.2	V	3.0	-12.7	33.9	1.0	-45.6	-13.0	-32.6	
High Channel (1770.0MHz)										
3.54	-67.2	H	3.0	-18.0	34.5	1.0	-51.5	-13.0	-38.5	
5.31	-67.4	H	3.0	-14.4	34.2	1.0	-47.6	-13.0	-34.6	
7.08	-68.3	H	3.0	-12.4	33.9	1.0	-45.3	-13.0	-32.3	
3.54	-66.9	V	3.0	-17.6	34.5	1.0	-51.1	-13.0	-38.1	
5.31	-63.2	V	3.0	-9.9	34.2	1.0	-43.1	-13.0	-30.1	
7.08	-67.8	V	3.0	-12.1	33.9	1.0	-44.9	-13.0	-31.9	

Rev. 02.24.17

LTE B66 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 12500
Configuration: EUT Only
Mode: LTE Band 66, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1720.0MHz)										
3.44	-65.2	H	3.0	-16.4	34.6	1.0	-50.0	-13.0	-37.0	
5.13	-64.1	H	3.0	-11.4	34.2	1.0	-44.6	-13.0	-31.6	
6.88	-66.0	H	3.0	-10.4	33.9	1.0	-43.3	-13.0	-30.3	
3.44	-66.4	V	3.0	-17.4	34.6	1.0	-51.0	-13.0	-38.0	
5.13	-65.6	V	3.0	-12.6	34.2	1.0	-45.8	-13.0	-32.8	
6.88	-67.9	V	3.0	-12.5	33.9	1.0	-45.4	-13.0	-32.4	
Mid Channel (1745.0MHz)										
3.49	-66.3	H	3.0	-17.4	34.6	1.0	-50.9	-13.0	-37.9	
5.23	-63.1	H	3.0	-10.2	34.2	1.0	-43.4	-13.0	-30.4	
6.98	-68.7	H	3.0	-13.0	33.9	1.0	-45.9	-13.0	-32.9	
3.49	-67.0	V	3.0	-17.8	34.6	1.0	-51.4	-13.0	-38.4	
5.23	-60.8	V	3.0	-7.6	34.2	1.0	-40.8	-13.0	-27.8	
6.98	-67.9	V	3.0	-12.4	33.9	1.0	-45.3	-13.0	-32.3	
High Channel (1770.0MHz)										
3.54	-67.3	H	3.0	-18.1	34.5	1.0	-51.7	-13.0	-38.7	
5.31	-67.4	H	3.0	-14.4	34.2	1.0	-47.6	-13.0	-34.6	
7.08	-69.0	H	3.0	-13.1	33.9	1.0	-46.0	-13.0	-33.0	
3.54	-65.4	V	3.0	-16.1	34.5	1.0	-49.6	-13.0	-36.6	
5.31	-63.6	V	3.0	-10.3	34.2	1.0	-43.4	-13.0	-30.4	
7.08	-67.0	V	3.0	-11.4	33.9	1.0	-44.2	-13.0	-31.2	

Rev. 02.24.17

LTE B66 20MHz 16QAM

9.2.13. LTE BAND 71

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 71, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (673MHz)										
1.35	-69.6	H	3.0	-38.1	34.2	1.0	-63.3	-13.0	-50.3	
2.02	-68.5	H	3.0	-25.0	33.5	1.0	-57.5	-13.0	-44.5	
2.69	-71.6	H	3.0	-26.3	34.4	1.0	-59.7	-13.0	-46.7	
1.35	-70.3	V	3.0	-28.4	34.2	1.0	-61.6	-13.0	-48.6	
2.02	-68.6	V	3.0	-25.0	33.5	1.0	-57.5	-13.0	-44.5	
2.69	-71.1	V	3.0	-25.3	34.4	1.0	-58.6	-13.0	-45.6	
Mid Channel (680.5MHz)										
1.36	-70.1	H	3.0	-30.6	34.1	1.0	-63.8	-13.0	-50.8	
2.04	-69.0	H	3.0	-25.5	33.5	1.0	-58.0	-13.0	-45.0	
2.72	-70.9	H	3.0	-25.5	34.4	1.0	-58.9	-13.0	-45.9	
1.36	-70.1	V	3.0	-28.1	34.1	1.0	-61.2	-13.0	-48.2	
2.04	-69.0	V	3.0	-25.3	33.5	1.0	-57.9	-13.0	-44.9	
2.72	-71.4	V	3.0	-25.4	34.4	1.0	-58.8	-13.0	-45.8	
High Channel (688MHz)										
1.38	-70.1	H	3.0	-30.6	34.1	1.0	-63.7	-13.0	-50.7	
2.06	-69.4	H	3.0	-25.8	33.6	1.0	-58.4	-13.0	-45.4	
2.75	-70.7	H	3.0	-25.0	34.5	1.0	-58.5	-13.0	-45.5	
1.38	-70.4	V	3.0	-28.3	34.1	1.0	-61.3	-13.0	-48.3	
2.06	-68.9	V	3.0	-25.2	33.6	1.0	-57.8	-13.0	-44.8	
2.75	-71.2	V	3.0	-25.1	34.5	1.0	-58.5	-13.0	-45.5	

Rev. 12.18.15

LTE B71 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/12/18
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 71, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (673MHz)										
1.35	-69.8	H	3.0	-38.4	34.2	1.0	-63.6	-13.0	-50.6	
2.02	-68.3	H	3.0	-24.7	33.5	1.0	-57.2	-13.0	-44.2	
2.69	-71.4	H	3.0	-26.1	34.4	1.0	-59.5	-13.0	-46.5	
1.35	-70.2	V	3.0	-28.4	34.2	1.0	-61.5	-13.0	-48.5	
2.02	-68.4	V	3.0	-24.8	33.5	1.0	-57.3	-13.0	-44.3	
2.69	-70.6	V	3.0	-24.8	34.4	1.0	-58.2	-13.0	-45.2	
Mid Channel (680.5MHz)										
1.36	-69.9	H	3.0	-30.4	34.1	1.0	-63.5	-13.0	-50.5	
2.04	-68.4	H	3.0	-24.8	33.5	1.0	-57.3	-13.0	-44.3	
2.72	-71.1	H	3.0	-25.6	34.4	1.0	-59.0	-13.0	-46.0	
1.36	-69.2	V	3.0	-27.2	34.1	1.0	-60.4	-13.0	-47.4	
2.04	-68.1	V	3.0	-24.4	33.5	1.0	-56.9	-13.0	-43.9	
2.72	-74.5	V	3.0	-28.5	34.4	1.0	-61.9	-13.0	-48.9	
High Channel (688MHz)										
1.38	-68.3	H	3.0	-28.7	34.1	1.0	-61.8	-13.0	-48.8	
2.06	-69.5	H	3.0	-26.0	33.6	1.0	-58.5	-13.0	-45.5	
2.75	-71.3	H	3.0	-25.7	34.5	1.0	-59.1	-13.0	-46.1	
1.38	-69.7	V	3.0	-27.6	34.1	1.0	-60.7	-13.0	-47.7	
2.06	-68.9	V	3.0	-25.2	33.6	1.0	-57.8	-13.0	-44.8	
2.75	-71.7	V	3.0	-25.5	34.5	1.0	-59.0	-13.0	-46.0	

Rev. 12.18.15

LTE B71 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.3. FIELD STRENGTH OF SPURIOUS RADIATION (ANT3)

9.3.1. LTE BAND 2

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/13/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 2, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-65.4	H	3.0	-15.6	34.4	1.0	-49.0	-13.0	-36.0	
5.58	-66.0	H	3.0	-12.5	34.1	1.0	-45.6	-13.0	-32.6	
7.44	-68.2	H	3.0	-11.8	33.6	1.0	-44.4	-13.0	-31.4	
3.72	-63.1	V	3.0	-13.2	34.4	1.0	-46.6	-13.0	-33.6	
5.58	-66.4	V	3.0	-12.7	34.1	1.0	-45.9	-13.0	-32.9	
7.44	-66.9	V	3.0	-10.7	33.6	1.0	-43.3	-13.0	-30.3	
Mid Channel (1880MHz)										
3.76	-64.9	H	3.0	-14.9	34.4	1.0	-48.3	-13.0	-35.3	
5.64	-67.4	H	3.0	-13.8	34.1	1.0	-46.9	-13.0	-33.9	
7.52	-67.9	H	3.0	-11.4	33.5	1.0	-43.9	-13.0	-30.9	
3.76	-65.1	V	3.0	-15.0	34.4	1.0	-48.4	-13.0	-35.4	
5.64	-66.2	V	3.0	-12.5	34.1	1.0	-45.6	-13.0	-32.6	
7.52	-68.0	V	3.0	-11.7	33.5	1.0	-44.2	-13.0	-31.2	
High Channel (1900MHz)										
3.80	-67.7	H	3.0	-17.6	34.4	1.0	-51.0	-13.0	-38.0	
5.70	-67.3	H	3.0	-13.6	34.1	1.0	-46.7	-13.0	-33.7	
7.60	-67.3	H	3.0	-10.7	33.5	1.0	-43.2	-13.0	-30.2	
3.80	-67.3	V	3.0	-17.1	34.4	1.0	-50.5	-13.0	-37.5	
5.70	-67.4	V	3.0	-13.6	34.1	1.0	-46.7	-13.0	-33.7	
7.60	-67.2	V	3.0	-10.8	33.5	1.0	-43.3	-13.0	-30.3	

Rev. 05.21.15

LTE B2 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/13/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 2, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-65.1	H	3.0	-15.3	34.4	1.0	-48.7	-13.0	-35.7	
5.58	-65.6	H	3.0	-12.1	34.1	1.0	-45.2	-13.0	-32.2	
7.44	-67.6	H	3.0	-11.2	33.6	1.0	-43.8	-13.0	-30.8	
3.72	-64.4	V	3.0	-14.5	34.4	1.0	-47.9	-13.0	-34.9	
5.58	-66.6	V	3.0	-12.9	34.1	1.0	-46.1	-13.0	-33.1	
7.44	-67.9	V	3.0	-11.7	33.6	1.0	-44.3	-13.0	-31.3	
Mid Channel (1880MHz)										
3.76	-64.6	H	3.0	-14.6	34.4	1.0	-48.0	-13.0	-35.0	
5.64	-65.7	H	3.0	-12.1	34.1	1.0	-45.2	-13.0	-32.2	
7.52	-67.9	H	3.0	-11.4	33.5	1.0	-43.9	-13.0	-30.9	
3.76	-65.3	V	3.0	-15.2	34.4	1.0	-48.6	-13.0	-35.6	
5.64	-66.2	V	3.0	-12.5	34.1	1.0	-45.6	-13.0	-32.6	
7.52	-67.8	V	3.0	-11.5	33.5	1.0	-44.0	-13.0	-31.0	
High Channel (1900MHz)										
3.80	-66.6	H	3.0	-16.5	34.4	1.0	-49.9	-13.0	-36.9	
5.70	-67.4	H	3.0	-13.7	34.1	1.0	-46.8	-13.0	-33.8	
7.60	-67.2	H	3.0	-10.6	33.5	1.0	-43.1	-13.0	-30.1	
3.80	-66.8	V	3.0	-16.6	34.4	1.0	-50.0	-13.0	-37.0	
5.70	-67.3	V	3.0	-13.5	34.1	1.0	-46.6	-13.0	-33.6	
7.60	-66.6	V	3.0	-10.2	33.5	1.0	-42.7	-13.0	-29.7	

Rev. 05.21.15

LTE B2 20MHz 16QAM

9.3.2. LTE BAND 7

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/13/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 7, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)										
5.02	-65.5	H	3.0	-12.9	34.2	1.0	-46.1	-25.0	-21.1	
7.53	-66.9	H	3.0	-10.4	33.5	1.0	-42.9	-25.0	-17.9	
10.04	-67.6	H	3.0	-7.8	31.7	1.0	-38.4	-25.0	-13.4	
5.02	-64.4	V	3.0	-11.6	34.2	1.0	-44.8	-25.0	-19.8	
7.53	-67.7	V	3.0	-11.4	33.5	1.0	-43.9	-25.0	-18.9	
10.04	-67.3	V	3.0	-7.5	31.7	1.0	-38.2	-25.0	-13.2	
Mid Channel (2535MHz)										
5.07	-65.9	H	3.0	-13.2	34.2	1.0	-46.4	-25.0	-21.4	
7.61	-67.6	H	3.0	-11.0	33.5	1.0	-43.5	-25.0	-18.5	
10.14	-68.1	H	3.0	-8.2	31.7	1.0	-38.9	-25.0	-13.9	
5.07	-66.7	V	3.0	-13.8	34.2	1.0	-47.0	-25.0	-22.0	
7.61	-66.1	V	3.0	-9.7	33.5	1.0	-42.1	-25.0	-17.1	
10.14	-67.8	V	3.0	-8.0	31.7	1.0	-38.7	-25.0	-13.7	
High Channel (2560MHz)										
5.12	-65.1	H	3.0	-12.4	34.2	1.0	-45.5	-25.0	-20.5	
7.68	-66.9	H	3.0	-10.2	33.4	1.0	-42.6	-25.0	-17.6	
10.24	-67.2	H	3.0	-7.2	31.8	1.0	-38.1	-25.0	-13.1	
5.12	-66.2	V	3.0	-13.2	34.2	1.0	-46.4	-25.0	-21.4	
7.68	-67.5	V	3.0	-11.0	33.4	1.0	-43.4	-25.0	-18.4	
10.24	-68.3	V	3.0	-8.4	31.8	1.0	-39.2	-25.0	-14.2	

Rev. 05.21.15

LTE B7 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/13/18
Test Engineer: 12500
Configuration: EUT only
Mode: LTE Band 7, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)										
5.02	-66.4	H	3.0	-13.8	34.2	1.0	-47.0	-25.0	-22.0	
7.53	-68.6	H	3.0	-12.1	33.5	1.0	-44.6	-25.0	-19.6	
10.04	-67.8	H	3.0	-8.8	31.7	1.0	-38.6	-25.0	-13.6	
5.02	-65.8	V	3.0	-13.0	34.2	1.0	-46.2	-25.0	-21.2	
7.53	-67.3	V	3.0	-11.0	33.5	1.0	-43.5	-25.0	-18.5	
10.04	-67.6	V	3.0	-7.8	31.7	1.0	-38.5	-25.0	-13.5	
Mid Channel (2535MHz)										
5.07	-65.3	H	3.0	-12.6	34.2	1.0	-45.8	-25.0	-20.8	
7.61	-67.2	H	3.0	-10.6	33.5	1.0	-43.1	-25.0	-18.1	
10.14	-67.5	H	3.0	-7.6	31.7	1.0	-38.3	-25.0	-13.3	
5.07	-65.5	V	3.0	-12.6	34.2	1.0	-45.8	-25.0	-20.8	
7.61	-67.1	V	3.0	-10.7	33.5	1.0	-43.1	-25.0	-18.1	
10.14	-66.7	V	3.0	-6.9	31.7	1.0	-37.6	-25.0	-12.6	
High Channel (2560MHz)										
5.12	-65.7	H	3.0	-13.0	34.2	1.0	-46.1	-25.0	-21.1	
7.68	-66.8	H	3.0	-10.1	33.4	1.0	-42.5	-25.0	-17.5	
10.24	-67.1	H	3.0	-7.1	31.8	1.0	-38.0	-25.0	-13.0	
5.12	-65.7	V	3.0	-12.7	34.2	1.0	-45.9	-25.0	-20.9	
7.68	-67.0	V	3.0	-10.5	33.4	1.0	-42.9	-25.0	-17.9	
10.24	-66.2	V	3.0	-6.3	31.8	1.0	-37.1	-25.0	-12.1	

Rev. 05.21.15

LTE B7 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.3.3. LTE BAND 25

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/13/18
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 25, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-64.6	H	3.0	-14.7	34.4	1.0	-48.2	-13.0	-35.2	
5.58	-66.7	H	3.0	-13.2	34.1	1.0	-46.4	-13.0	-33.4	
7.44	-67.1	H	3.0	-10.8	33.6	1.0	-43.4	-13.0	-30.4	
3.72	-64.3	V	3.0	-14.3	34.4	1.0	-47.7	-13.0	-34.7	
5.58	-65.1	V	3.0	-11.5	34.1	1.0	-44.6	-13.0	-31.6	
7.44	-66.6	V	3.0	-10.4	33.6	1.0	-43.0	-13.0	-30.0	
Mid Channel (1882.5MHz)										
3.77	-63.9	H	3.0	-13.9	34.4	1.0	-47.3	-13.0	-34.3	
5.65	-66.9	H	3.0	-13.3	34.1	1.0	-46.4	-13.0	-33.4	
7.53	-66.4	H	3.0	-9.9	33.5	1.0	-42.4	-13.0	-29.4	
3.77	-65.4	V	3.0	-15.3	34.4	1.0	-48.8	-13.0	-35.8	
5.65	-67.5	V	3.0	-13.8	34.1	1.0	-46.9	-13.0	-33.9	
7.53	-68.3	V	3.0	-12.0	33.5	1.0	-44.5	-13.0	-31.5	
High Channel (1905MHz)										
3.81	-64.9	H	3.0	-14.7	34.4	1.0	-48.1	-13.0	-35.1	
5.72	-68.1	H	3.0	-14.4	34.1	1.0	-47.5	-13.0	-34.5	
7.62	-66.6	H	3.0	-10.0	33.4	1.0	-42.5	-13.0	-29.5	
3.81	-64.9	V	3.0	-14.7	34.4	1.0	-48.1	-13.0	-35.1	
5.72	-67.6	V	3.0	-13.8	34.1	1.0	-46.9	-13.0	-33.9	
7.62	-66.6	V	3.0	-10.2	33.4	1.0	-42.6	-13.0	-29.6	

Rev. 05.21.15

LTE B25 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/13/18
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 25, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-64.4	H	3.0	-14.6	34.4	1.0	-48.0	-13.0	-35.0	
5.58	-68.2	H	3.0	-14.7	34.1	1.0	-47.8	-13.0	-34.8	
7.44	-66.9	H	3.0	-10.5	33.6	1.0	-43.1	-13.0	-30.1	
3.72	-65.7	V	3.0	-15.7	34.4	1.0	-49.2	-13.0	-36.2	
5.58	-67.2	V	3.0	-13.5	34.1	1.0	-46.6	-13.0	-33.6	
7.44	-67.2	V	3.0	-11.0	33.6	1.0	-43.6	-13.0	-30.6	
Mid Channel (1882.5MHz)										
3.77	-64.6	H	3.0	-14.6	34.4	1.0	-48.0	-13.0	-35.0	
5.65	-66.9	H	3.0	-13.3	34.1	1.0	-46.4	-13.0	-33.4	
7.53	-66.2	H	3.0	-9.7	33.5	1.0	-42.2	-13.0	-29.2	
3.77	-65.3	V	3.0	-15.2	34.4	1.0	-48.7	-13.0	-35.7	
5.65	-67.6	V	3.0	-13.8	34.1	1.0	-46.9	-13.0	-33.9	
7.53	-68.2	V	3.0	-11.9	33.5	1.0	-44.4	-13.0	-31.4	
High Channel (1905MHz)										
3.81	-64.1	H	3.0	-14.0	34.4	1.0	-47.3	-13.0	-34.3	
5.72	-67.5	H	3.0	-13.8	34.1	1.0	-46.9	-13.0	-33.9	
7.62	-67.0	H	3.0	-10.4	33.4	1.0	-42.8	-13.0	-29.8	
3.81	-64.2	V	3.0	-13.9	34.4	1.0	-47.3	-13.0	-34.3	
5.72	-67.3	V	3.0	-13.5	34.1	1.0	-46.6	-13.0	-33.6	
7.62	-67.7	V	3.0	-11.3	33.4	1.0	-43.7	-13.0	-30.7	

Rev. 05.21.15

LTE B25 20MHz 16QAM

9.3.4. LTE BAND 30

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/13/18
Test Engineer: 10643
Configuration: EUT only
Mode: LTE Band 30, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B30

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (2310MHz)										
4.62	-67.5	H	3.0	-13.7	37.9	1.0	-50.6	-40.0	-10.6	
6.93	-67.3	H	3.0	-8.7	36.5	1.0	-44.1	-40.0	-4.1	
8.50	-69.5	H	3.0	-8.9	35.4	1.0	-43.2	-40.0	-3.2	
4.62	-66.9	V	3.0	-13.2	37.9	1.0	-50.1	-40.0	-10.1	
6.93	-68.5	V	3.0	-9.0	36.5	1.0	-44.5	-40.0	-4.5	
8.50	-70.2	V	3.0	-9.1	35.4	1.0	-43.5	-40.0	-3.5	

Rev. 05.21.15

LTE B30 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/13/18
Test Engineer: 10643
Configuration: EUT only
Mode: LTE Band 30, 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	LTE B30

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (2310MHz)										
4.62	-66.6	H	3.0	-12.7	37.9	1.0	-49.7	-40.0	-9.7	
6.93	-69.6	H	3.0	-10.9	36.5	1.0	-46.4	-40.0	-6.4	
8.50	-69.7	H	3.0	-8.4	34.9	1.0	-42.3	-40.0	-2.3	
4.62	-66.9	V	3.0	-12.2	37.9	1.0	-49.1	-40.0	-9.1	
6.93	-68.0	V	3.0	-8.5	36.5	1.0	-44.0	-40.0	-4.0	
8.50	-70.5	V	3.0	-9.0	34.9	1.0	-42.9	-40.0	-2.9	

Rev. 05.21.15

LTE B30 10MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.3.5. LTE BAND 41

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/14/18
Test Engineer: 12491
Configuration: EUT Only
Mode: LTE Band 41, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber G	3m Chamber G	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz)										
5.01	-68.0	H	3.0	-18.6	36.2	1.0	-53.9	-25.0	-28.9	
7.52	-69.0	H	3.0	-15.8	35.1	1.0	-50.0	-25.0	-25.0	
10.02	-70.7	H	3.0	-15.2	33.3	1.0	-47.5	-25.0	-22.5	
5.01	-67.1	V	3.0	-17.8	36.2	1.0	-53.1	-25.0	-28.1	
7.52	-69.7	V	3.0	-16.6	35.1	1.0	-50.7	-25.0	-25.7	
10.02	-71.3	V	3.0	-16.0	33.3	1.0	-48.3	-25.0	-23.3	
Mid Channel (2593MHz)										
5.19	-68.2	H	3.0	-18.5	36.3	1.0	-53.8	-25.0	-28.8	
7.78	-69.2	H	3.0	-15.8	34.9	1.0	-49.7	-25.0	-24.7	
10.37	-71.9	H	3.0	-16.2	33.1	1.0	-48.3	-25.0	-23.3	
5.19	-68.6	V	3.0	-19.1	36.3	1.0	-54.4	-25.0	-29.4	
7.78	-69.6	V	3.0	-16.2	34.9	1.0	-50.2	-25.0	-25.2	
10.37	-72.0	V	3.0	-16.5	33.1	1.0	-48.6	-25.0	-23.6	
High Channel (2680MHz)										
5.36	-68.4	H	3.0	-18.4	36.2	1.0	-53.6	-25.0	-28.6	
8.04	-69.1	H	3.0	-15.5	34.8	1.0	-49.2	-25.0	-24.2	
10.72	-72.0	H	3.0	-16.2	32.9	1.0	-48.1	-25.0	-23.1	
5.36	-68.2	V	3.0	-18.5	36.2	1.0	-53.7	-25.0	-28.7	
8.04	-68.7	V	3.0	-15.1	34.8	1.0	-48.9	-25.0	-23.9	
10.72	-71.7	V	3.0	-16.2	32.9	1.0	-48.1	-25.0	-23.1	

Rev. 05.21.15

LTE B41 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/14/18
Test Engineer: 12491
Configuration: EUT Only
Mode: LTE Band 41, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber G	3m Chamber G	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz)										
5.01	-67.8	H	3.0	-18.4	36.2	1.0	-53.6	-25.0	-28.6	
7.52	-69.5	H	3.0	-16.3	35.1	1.0	-50.5	-25.0	-25.5	
10.02	-71.2	H	3.0	-15.6	33.3	1.0	-48.0	-25.0	-23.0	
5.01	-68.9	V	3.0	-19.7	36.2	1.0	-54.9	-25.0	-29.9	
7.52	-69.7	V	3.0	-16.6	35.1	1.0	-50.7	-25.0	-25.7	
10.02	-71.8	V	3.0	-16.4	33.3	1.0	-48.7	-25.0	-23.7	
Mid Channel (2593MHz)										
5.19	-66.9	H	3.0	-17.2	36.3	1.0	-52.5	-25.0	-27.5	
7.78	-70.2	H	3.0	-16.7	34.9	1.0	-50.7	-25.0	-25.7	
10.37	-71.5	H	3.0	-15.9	33.1	1.0	-48.0	-25.0	-23.0	
5.19	-68.1	V	3.0	-18.6	36.3	1.0	-53.8	-25.0	-28.8	
7.78	-69.9	V	3.0	-16.5	34.9	1.0	-50.4	-25.0	-25.4	
10.37	-71.9	V	3.0	-16.4	33.1	1.0	-48.6	-25.0	-23.6	
High Channel (2680MHz)										
5.36	-68.1	H	3.0	-18.1	36.2	1.0	-53.3	-25.0	-28.3	
8.04	-69.6	H	3.0	-16.0	34.8	1.0	-49.7	-25.0	-24.7	
10.72	-71.7	H	3.0	-15.9	32.9	1.0	-47.9	-25.0	-22.9	
5.36	-68.3	V	3.0	-18.6	36.2	1.0	-53.8	-25.0	-28.8	
8.04	-69.8	V	3.0	-16.2	34.8	1.0	-49.9	-25.0	24.9	
10.72	-71.8	V	3.0	-16.3	32.9	1.0	-48.2	-25.0	-23.2	

Rev. 05.21.15

LTE B41 20MHz 16QAM

9.3.6. LTE BAND 66

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 50893
Configuration: EUT
Mode: LTE Band 66, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1720.0MHz)										
3.44	-68.4	H	3.0	-19.6	34.6	1.0	-53.2	-13.0	-40.2	
5.16	-69.7	H	3.0	-16.9	34.2	1.0	-50.1	-13.0	-37.1	
6.88	-71.2	H	3.0	-15.6	33.9	1.0	-48.5	-13.0	-35.5	
3.44	-70.6	V	3.0	-21.6	34.6	1.0	-55.2	-13.0	-42.2	
5.16	-70.7	V	3.0	-17.6	34.2	1.0	-50.8	-13.0	-37.8	
6.88	-71.7	V	3.0	-16.3	33.9	1.0	-49.3	-13.0	-36.3	
Mid Channel (1745.0MHz)										
3.49	-68.1	H	3.0	-19.1	34.6	1.0	-52.7	-13.0	-39.7	
5.24	-70.1	H	3.0	-17.2	34.2	1.0	-50.3	-13.0	-37.3	
6.98	-71.8	H	3.0	-16.0	33.9	1.0	-48.9	-13.0	-35.9	
3.49	-68.1	V	3.0	-19.0	34.6	1.0	-52.6	-13.0	-39.6	
5.24	-70.5	V	3.0	-17.3	34.2	1.0	-50.5	-13.0	-37.5	
6.98	-71.1	V	3.0	-16.6	33.9	1.0	-48.5	-13.0	-35.5	
High Channel (1770.0MHz)										
3.54	-69.6	H	3.0	-20.4	34.5	1.0	-54.0	-13.0	-41.0	
5.31	-70.9	H	3.0	-17.8	34.2	1.0	-51.0	-13.0	-38.0	
7.08	-71.4	H	3.0	-15.5	33.9	1.0	-48.3	-13.0	-35.3	
3.54	-70.2	V	3.0	-20.9	34.5	1.0	-54.4	-13.0	-41.4	
5.31	-70.9	V	3.0	-17.6	34.2	1.0	-50.8	-13.0	-37.8	
7.08	-71.9	V	3.0	-16.2	33.9	1.0	-49.1	-13.0	-36.1	

Rev. 02.24.17

LTE B66 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 50893
Configuration: EUT
Mode: LTE Band 66, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1720.0MHz)										
3.44	-69.8	H	3.0	-21.0	34.6	1.0	-54.6	-13.0	-41.6	
5.16	-70.5	H	3.0	-17.7	34.2	1.0	-50.9	-13.0	-37.9	
6.88	-71.6	H	3.0	-16.0	33.9	1.0	-48.9	-13.0	-35.9	
3.44	-69.1	V	3.0	-20.2	34.6	1.0	-53.8	-13.0	-40.8	
5.16	-70.6	V	3.0	-17.5	34.2	1.0	-50.7	-13.0	-37.7	
6.88	-71.0	V	3.0	-15.6	33.9	1.0	-48.6	-13.0	-35.6	
Mid Channel (1745.0MHz)										
3.49	-70.2	H	3.0	-21.3	34.6	1.0	-54.8	-13.0	-41.8	
5.24	-70.7	H	3.0	-17.8	34.2	1.0	-50.9	-13.0	-37.9	
6.98	-70.4	H	3.0	-14.6	33.9	1.0	-47.5	-13.0	-34.5	
3.49	-69.4	V	3.0	-20.3	34.6	1.0	-53.8	-13.0	-40.8	
5.24	-70.7	V	3.0	-17.5	34.2	1.0	-50.7	-13.0	-37.7	
6.98	-70.1	V	3.0	-14.5	33.9	1.0	-47.4	-13.0	-34.4	
High Channel (1770.0MHz)										
3.54	-69.6	H	3.0	-20.5	34.5	1.0	-54.0	-13.0	-41.0	
5.31	-69.5	H	3.0	-16.4	34.2	1.0	-49.6	-13.0	-36.6	
7.08	-70.8	H	3.0	-14.9	33.9	1.0	-47.8	-13.0	-34.8	
3.54	-68.6	V	3.0	-19.3	34.5	1.0	-52.8	-13.0	-39.8	
5.31	-70.6	V	3.0	-17.3	34.2	1.0	-50.5	-13.0	-37.5	
7.08	-71.0	V	3.0	-15.3	33.9	1.0	-48.2	-13.0	-35.2	

Rev. 02.24.17

LTE B66 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.4. FIELD STRENGTH OF SPURIOUS RADIATION (ANT4)

9.4.1. LTE BAND 2

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/14/18
Test Engineer: 12491
Configuration: EUT Only
Mode: LTE Band 2, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber G	3m Chamber G	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-67.4	H	3.0	-20.7	36.2	1.0	-55.9	-13.0	-42.9	
5.58	-66.8	H	3.0	-16.4	36.1	1.0	-51.5	-13.0	-38.5	
7.44	-69.0	H	3.0	-15.9	35.2	1.0	-50.0	-13.0	-37.0	
3.72	-67.4	V	3.0	-20.2	36.2	1.0	-55.4	-13.0	-42.4	
5.58	-67.1	V	3.0	-16.9	36.1	1.0	-52.0	-13.0	-39.0	
7.44	-69.7	V	3.0	-16.6	35.2	1.0	-50.8	-13.0	-37.8	
Mid Channel (1880MHz)										
3.76	-66.4	H	3.0	-19.5	36.2	1.0	-54.7	-13.0	-41.7	
5.64	-67.8	H	3.0	-17.3	36.1	1.0	-52.4	-13.0	-39.4	
7.52	-68.6	H	3.0	-15.4	35.1	1.0	-49.5	-13.0	-36.5	
3.76	-66.5	V	3.0	-19.2	36.2	1.0	-54.4	-13.0	-41.4	
5.64	-67.4	V	3.0	-17.1	36.1	1.0	-52.2	-13.0	-39.2	
7.52	-69.1	V	3.0	-16.0	35.1	1.0	-50.1	-13.0	-37.1	
High Channel (1900MHz)										
3.80	-67.6	H	3.0	-20.6	36.2	1.0	-55.8	-13.0	-42.8	
5.70	-68.3	H	3.0	-17.7	36.1	1.0	-52.8	-13.0	-39.8	
7.60	-69.6	H	3.0	-16.4	35.1	1.0	-50.4	-13.0	-37.4	
3.80	-67.9	V	3.0	-20.5	36.2	1.0	-55.6	-13.0	-42.6	
5.70	-67.8	V	3.0	-17.4	36.1	1.0	-52.5	-13.0	-39.5	
7.60	-69.9	V	3.0	-16.7	35.1	1.0	-50.8	-13.0	-37.8	

Rev. 05.21.15

LTE B2 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/14/18
Test Engineer: 12491
Configuration: EUT Only
Mode: LTE Band 2, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber G	3m Chamber G	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-69.3	H	3.0	-22.5	36.2	1.0	-57.7	-13.0	-44.7	
5.58	-70.0	H	3.0	-19.6	36.1	1.0	-54.7	-13.0	-41.7	
7.44	-71.2	H	3.0	-18.1	35.2	1.0	-52.2	-13.0	-39.2	
3.72	-69.4	V	3.0	-22.2	36.2	1.0	-57.4	-13.0	-44.4	
5.58	-69.7	V	3.0	-19.5	36.1	1.0	-54.6	-13.0	-41.6	
7.44	-71.7	V	3.0	-18.6	35.2	1.0	-52.8	-13.0	-39.8	
Mid Channel (1880MHz)										
3.76	-67.9	H	3.0	-21.0	36.2	1.0	-56.2	-13.0	-43.2	
5.64	-68.2	H	3.0	-17.8	36.1	1.0	-52.9	-13.0	-39.9	
7.52	-68.5	H	3.0	-15.3	35.1	1.0	-49.4	-13.0	-36.4	
3.76	-67.2	V	3.0	-19.8	36.2	1.0	-55.0	-13.0	-42.0	
5.64	-67.0	V	3.0	-16.7	36.1	1.0	-51.8	-13.0	-38.8	
7.52	-69.2	V	3.0	-16.1	35.1	1.0	-50.2	-13.0	-37.2	
High Channel (1900MHz)										
3.80	-67.7	H	3.0	-20.7	36.2	1.0	-55.9	-13.0	-42.9	
5.70	-68.0	H	3.0	-17.4	36.1	1.0	-52.5	-13.0	-39.5	
7.60	-69.2	H	3.0	-16.0	35.1	1.0	-50.1	-13.0	-37.1	
3.80	-68.0	V	3.0	-20.6	36.2	1.0	-55.7	-13.0	-42.7	
5.70	-68.3	V	3.0	-17.9	36.1	1.0	-52.9	-13.0	-39.9	
7.60	-69.2	V	3.0	-16.0	35.1	1.0	-50.1	-13.0	-37.1	

Rev. 05.21.15

LTE B2 20MHz 16QAM

9.4.2. LTE BAND 7

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/14/18
Test Engineer: 12491
Configuration: EUT Only
Mode: LTE Band 7, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber G	3m Chamber G	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)										
5.02	-67.8	H	3.0	-18.4	36.2	1.0	-53.6	-25.0	-28.6	
7.53	-69.2	H	3.0	-16.0	35.1	1.0	-50.1	-25.0	-25.1	
10.04	-71.1	H	3.0	-15.6	33.3	1.0	-47.9	-25.0	-22.9	
5.02	-68.7	V	3.0	-19.4	36.2	1.0	-54.6	-25.0	-29.6	
7.53	-69.5	V	3.0	-16.4	35.1	1.0	-50.5	-25.0	-25.5	
10.04	-71.7	V	3.0	-16.4	33.3	1.0	-48.7	-25.0	-23.7	
Mid Channel (2535MHz)										
5.07	-68.3	H	3.0	-18.8	36.3	1.0	-54.0	-25.0	-29.0	
7.61	-69.2	H	3.0	-16.0	35.1	1.0	-50.0	-25.0	-25.0	
10.14	-70.4	H	3.0	-14.8	33.3	1.0	-47.0	-25.0	-22.0	
5.07	-67.6	V	3.0	-18.3	36.3	1.0	-53.5	-25.0	-28.5	
7.61	-69.2	V	3.0	-16.0	35.1	1.0	-50.0	-25.0	-25.0	
10.14	-70.6	V	3.0	-15.2	33.3	1.0	-47.5	-25.0	-22.5	
High Channel (2560MHz)										
5.12	-68.5	H	3.0	-18.9	36.3	1.0	-54.2	-25.0	-29.2	
7.68	-69.7	H	3.0	-16.3	35.0	1.0	-50.3	-25.0	-25.3	
10.24	-70.5	H	3.0	-14.9	33.2	1.0	-47.1	-25.0	-22.1	
5.12	-69.1	V	3.0	-19.7	36.3	1.0	-54.9	-25.0	-29.9	
7.68	-69.8	V	3.0	-16.6	35.0	1.0	-50.6	-25.0	-25.6	
10.24	-71.0	V	3.0	-15.6	33.2	1.0	-47.8	-25.0	-22.8	

Rev. 05.21.15

LTE B7 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/14/18
Test Engineer: 12491
Configuration: EUT Only
Mode: LTE Band 7, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber G	3m Chamber G	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)										
5.02	-67.9	H	3.0	-18.5	36.2	1.0	-53.8	-25.0	-28.8	
7.53	-69.7	H	3.0	-16.5	35.1	1.0	-50.7	-25.0	-25.7	
10.04	-71.8	H	3.0	-16.3	33.3	1.0	-48.6	-25.0	-23.6	
5.02	-68.0	V	3.0	-18.7	36.2	1.0	-54.0	-25.0	-29.0	
7.53	-69.8	V	3.0	-16.7	35.1	1.0	-50.8	-25.0	-25.8	
10.04	-71.5	V	3.0	-16.1	33.3	1.0	-48.4	-25.0	-23.4	
Mid Channel (2535MHz)										
5.07	-67.9	H	3.0	-18.4	36.3	1.0	-53.7	-25.0	-28.7	
7.61	-69.7	H	3.0	-16.4	35.1	1.0	-50.5	-25.0	-25.5	
10.14	-69.9	H	3.0	-14.3	33.3	1.0	-46.6	-25.0	-21.6	
5.07	-67.7	V	3.0	-18.4	36.3	1.0	-53.6	-25.0	-28.6	
7.61	-70.3	V	3.0	-17.1	35.1	1.0	-51.2	-25.0	-26.2	
10.14	-70.7	V	3.0	-15.3	33.3	1.0	-47.5	-25.0	-22.5	
High Channel (2560MHz)										
5.12	-68.2	H	3.0	-18.6	36.3	1.0	-53.8	-25.0	-28.8	
7.68	-69.0	H	3.0	-15.6	35.0	1.0	-49.6	-25.0	-24.6	
10.24	-70.9	H	3.0	-15.3	33.2	1.0	-47.5	-25.0	-22.5	
5.12	-69.2	V	3.0	-19.8	36.3	1.0	-55.0	-25.0	-30.0	
7.68	-69.0	V	3.0	-15.8	35.0	1.0	-49.8	-25.0	-24.8	
10.24	-71.7	V	3.0	-16.3	33.2	1.0	-48.5	-25.0	-23.5	

Rev. 05.21.15

LTE B7 20MHz 16QAM

UL VERIFICATION SERVICES INC. FORM NO: CCSUP4031B
47173 BENICIA STREET, FREMONT, CA 94538, USA TEL: (510) 771-1000 FAX: (510) 661-0888
This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.4.3. LTE BAND 25

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/14/18
Test Engineer: 12491
Configuration: EUT Only
Mode: LTE Band 25, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber G	3m Chamber G	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-67.3	H	3.0	-20.5	36.2	1.0	-55.8	-13.0	-42.8	
5.58	-67.4	H	3.0	-17.0	36.1	1.0	-52.1	-13.0	-39.1	
7.44	-69.3	H	3.0	-16.2	35.2	1.0	-50.4	-13.0	-37.4	
3.72	-68.6	V	3.0	-21.4	36.2	1.0	-56.6	-13.0	-43.6	
5.58	-67.9	V	3.0	-17.8	36.1	1.0	-52.9	-13.0	-39.9	
7.44	-69.1	V	3.0	-16.0	35.2	1.0	-50.2	-13.0	-37.2	
Mid Channel (1882.5MHz)										
3.77	-67.7	H	3.0	-20.8	36.2	1.0	-56.0	-13.0	-43.0	
5.65	-67.7	H	3.0	-17.2	36.1	1.0	-52.3	-13.0	-39.3	
7.53	-69.0	H	3.0	-15.8	35.1	1.0	-49.9	-13.0	-36.9	
3.77	-66.7	V	3.0	-19.3	36.2	1.0	-54.5	-13.0	-41.5	
5.65	-67.5	V	3.0	-17.2	36.1	1.0	-52.3	-13.0	-39.3	
7.53	-68.7	V	3.0	-15.5	35.1	1.0	-49.7	-13.0	-36.7	
High Channel (1905MHz)										
3.81	-67.5	H	3.0	-20.5	36.1	1.0	-55.7	-13.0	-42.7	
5.72	-67.2	H	3.0	-16.6	36.1	1.0	-51.6	-13.0	-38.6	
7.62	-69.9	H	3.0	-16.6	35.1	1.0	-50.7	-13.0	-37.7	
3.81	-67.5	V	3.0	-20.0	36.1	1.0	-55.1	-13.0	-42.1	
5.72	-68.3	V	3.0	-17.9	36.1	1.0	-53.0	-13.0	-40.0	
7.62	-69.6	V	3.0	-16.4	35.1	1.0	-50.5	-13.0	-37.5	

Rev. 05.21.15

LTE B25 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/14/18
Test Engineer: 12491
Configuration: EUT Only
Mode: LTE Band 25, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber G	3m Chamber G	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-67.9	H	3.0	-21.1	36.2	1.0	-56.3	-13.0	-43.3	
5.58	-67.6	H	3.0	-17.2	36.1	1.0	-52.3	-13.0	-39.3	
7.44	-70.2	H	3.0	-17.1	35.2	1.0	-51.3	-13.0	-38.3	
3.72	-69.0	V	3.0	-21.8	36.2	1.0	-57.0	-13.0	-44.0	
5.58	-68.1	V	3.0	-18.0	36.1	1.0	-53.1	-13.0	-40.1	
7.44	-69.3	V	3.0	-16.2	35.2	1.0	-50.4	-13.0	-37.4	
Mid Channel (1882.5MHz)										
3.77	-67.3	H	3.0	-20.4	36.2	1.0	-55.6	-13.0	-42.6	
5.65	-68.3	H	3.0	-17.9	36.1	1.0	-53.0	-13.0	-40.0	
7.53	-69.3	H	3.0	-16.1	35.1	1.0	-50.2	-13.0	-37.2	
3.77	-68.1	V	3.0	-20.8	36.2	1.0	-55.9	-13.0	-42.9	
5.65	-67.4	V	3.0	-17.1	36.1	1.0	-52.2	-13.0	-39.2	
7.53	-67.9	V	3.0	-14.8	35.1	1.0	-48.9	-13.0	-35.9	
High Channel (1905MHz)										
3.81	-67.7	H	3.0	-20.7	36.1	1.0	-55.9	-13.0	-42.9	
5.72	-66.8	H	3.0	-16.2	36.1	1.0	-51.3	-13.0	-38.3	
7.62	-69.6	H	3.0	-16.4	35.1	1.0	-50.4	-13.0	-37.4	
3.81	-67.9	V	3.0	-20.4	36.1	1.0	-55.5	-13.0	-42.5	
5.72	-67.8	V	3.0	-17.4	36.1	1.0	-52.4	-13.0	-39.4	
7.62	-69.5	V	3.0	-16.3	35.1	1.0	-50.4	-13.0	-37.4	

Rev. 05.21.15

LTE B25 20MHz 16QAM

9.4.4. LTE BAND 30

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 12491
Configuration: EUT only
Mode: LTE Band 30, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber G	3m Chamber G	Filter	LTE B30

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (2310MHz)										
4.62	-69.6	H	3.0	-15.8	37.9	1.0	-52.7	-40.0	-12.7	
6.93	-69.8	H	3.0	-11.2	36.5	1.0	-46.6	-40.0	-6.6	
9.24	-71.7	H	3.0	-10.1	34.9	1.0	-44.0	-40.0	-4.0	
4.62	-69.1	V	3.0	-15.4	37.9	1.0	-52.3	-40.0	-12.3	
6.93	-69.8	V	3.0	-10.3	36.5	1.0	-45.8	-40.0	-5.8	
9.24	-70.9	V	3.0	-9.1	34.9	1.0	-43.0	-40.0	-3.0	

Rev. 05.21.15

LTE B30 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/22/18
Test Engineer: 12491
Configuration: EUT only
Mode: LTE Band 30, 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber G	3m Chamber G	Filter	LTE B30

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (2310MHz)										
4.62	-68.0	H	3.0	-14.2	37.9	1.0	-51.1	-40.0	-11.1	
6.93	-69.6	H	3.0	-11.0	36.5	1.0	-46.4	-40.0	-6.4	
9.24	-70.9	H	3.0	-9.4	34.9	1.0	-43.2	-40.0	-3.2	
4.62	-68.7	V	3.0	-15.0	37.9	1.0	-51.9	-40.0	-11.9	
6.93	-69.7	V	3.0	-10.2	36.5	1.0	-45.6	-40.0	-5.6	
9.24	-72.3	V	3.0	-10.5	34.9	1.0	-44.3	-40.0	-4.3	

Rev. 05.21.15

LTE B30 10MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.4.5. LTE BAND 41

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/14/18
Test Engineer: 12491
Configuration: EUT Only
Mode: LTE Band 41, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber G	3m Chamber G	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz)										
5.01	-68.3	H	3.0	-19.0	36.2	1.0	-54.2	-25.0	-29.2	
7.52	-69.3	H	3.0	-16.1	35.1	1.0	-50.2	-25.0	-25.2	
10.02	-71.6	H	3.0	-16.0	33.3	1.0	-48.4	-25.0	-23.4	
5.01	-67.9	V	3.0	-18.6	36.2	1.0	-53.9	-25.0	-28.9	
7.52	-69.3	V	3.0	-16.2	35.1	1.0	-50.3	-25.0	-25.3	
10.02	-71.5	V	3.0	-16.1	33.3	1.0	-48.5	-25.0	-23.5	
Mid Channel (2593MHz)										
5.19	-67.7	H	3.0	-18.0	36.3	1.0	-53.3	-25.0	-28.3	
7.78	-69.6	H	3.0	-16.1	34.9	1.0	-50.1	-25.0	-25.1	
10.37	-71.9	H	3.0	-16.3	33.1	1.0	-48.4	-25.0	-23.4	
5.19	-68.0	V	3.0	-18.6	36.3	1.0	-53.8	-25.0	-28.8	
7.78	-69.8	V	3.0	-16.5	34.9	1.0	-50.4	-25.0	-25.4	
10.37	-70.9	V	3.0	-15.5	33.1	1.0	-47.6	-25.0	-22.6	
High Channel (2680MHz)										
5.36	-68.2	H	3.0	-18.2	36.2	1.0	-53.4	-25.0	-28.4	
8.04	-69.3	H	3.0	-15.6	34.8	1.0	-49.4	-25.0	-24.4	
10.72	-71.8	H	3.0	-16.0	32.9	1.0	-47.9	-25.0	-22.9	
5.36	-68.2	V	3.0	-18.4	36.2	1.0	-53.7	-25.0	-28.7	
8.04	-69.8	V	3.0	-16.2	34.8	1.0	-50.0	-25.0	-25.0	
10.72	-72.3	V	3.0	-16.8	32.9	1.0	-48.7	-25.0	-23.7	

Rev. 05.21.15

LTE B41 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/14/18
Test Engineer: 12491
Configuration: EUT Only
Mode: LTE Band 41, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber G	3m Chamber G	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz)										
5.01	-68.0	H	3.0	-18.6	36.2	1.0	-53.9	-25.0	-28.9	
7.52	-69.6	H	3.0	-16.4	35.1	1.0	-50.5	-25.0	-25.5	
10.02	-71.7	H	3.0	-16.2	33.3	1.0	-48.5	-25.0	-23.5	
5.01	-67.3	V	3.0	-18.0	36.2	1.0	-53.2	-25.0	-28.2	
7.52	-68.2	V	3.0	-15.1	35.1	1.0	-49.2	-25.0	-24.2	
10.02	-71.4	V	3.0	-16.1	33.3	1.0	-48.4	-25.0	-23.4	
Mid Channel (2593MHz)										
5.19	-68.5	H	3.0	-18.8	36.3	1.0	-54.1	-25.0	-29.1	
7.78	-70.2	H	3.0	-16.7	34.9	1.0	-50.7	-25.0	-25.7	
10.37	-71.2	H	3.0	-15.5	33.1	1.0	-47.7	-25.0	-22.7	
5.19	-68.4	V	3.0	-18.9	36.3	1.0	-54.2	-25.0	-29.2	
7.78	-69.6	V	3.0	-16.2	34.9	1.0	-50.2	-25.0	-25.2	
10.37	-70.5	V	3.0	-15.0	33.1	1.0	-47.1	-25.0	-22.1	
High Channel (2680MHz)										
5.36	-67.5	H	3.0	-17.5	36.2	1.0	-52.7	-25.0	-27.7	
8.04	-69.8	H	3.0	-16.1	34.8	1.0	-49.9	-25.0	-24.9	
10.72	-71.3	H	3.0	-15.5	32.9	1.0	-47.4	-25.0	-22.4	
5.36	-67.2	V	3.0	-17.4	36.2	1.0	-52.6	-25.0	-27.6	
8.04	-70.1	V	3.0	-16.5	34.8	1.0	-50.3	-25.0	-25.3	
10.72	-72.0	V	3.0	-16.4	32.9	1.0	-48.3	-25.0	-23.3	

Rev. 05.21.15

LTE B41 20MHz 16QAM

9.4.6. LTE BAND 66

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 50893
Configuration: EUT
Mode: LTE Band 66, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1720.0MHz)										
3.44	-69.3	H	3.0	-20.5	34.6	1.0	-54.1	-13.0	-41.1	
5.16	-70.2	H	3.0	-17.4	34.2	1.0	-50.6	-13.0	-37.6	
6.88	-71.7	H	3.0	-16.2	33.9	1.0	-49.1	-13.0	-36.1	
3.44	-69.8	V	3.0	-20.8	34.6	1.0	-54.4	-13.0	-41.4	
5.16	-70.8	V	3.0	-17.7	34.2	1.0	-50.9	-13.0	-37.9	
6.88	-71.5	V	3.0	-16.1	33.9	1.0	-49.0	-13.0	-36.0	
Mid Channel (1745.0MHz)										
3.49	-69.8	H	3.0	-20.9	34.6	1.0	-54.4	-13.0	-41.4	
5.24	-69.5	H	3.0	-16.6	34.2	1.0	-49.8	-13.0	-36.8	
6.98	-70.9	H	3.0	-15.1	33.9	1.0	-48.0	-13.0	-35.0	
3.49	-69.3	V	3.0	-20.2	34.6	1.0	-53.8	-13.0	-40.8	
5.24	-70.4	V	3.0	-17.2	34.2	1.0	-50.3	-13.0	-37.3	
6.98	-71.7	V	3.0	-16.2	33.9	1.0	-49.1	-13.0	-36.1	
High Channel (1770.0MHz)										
3.54	-70.0	H	3.0	-20.9	34.5	1.0	-54.4	-13.0	-41.4	
5.31	-70.2	H	3.0	-17.2	34.2	1.0	-50.4	-13.0	-37.4	
7.08	-72.0	H	3.0	-16.2	33.9	1.0	-49.0	-13.0	-36.0	
3.54	-69.8	V	3.0	-20.5	34.5	1.0	-54.0	-13.0	-41.0	
5.31	-70.8	V	3.0	-17.5	34.2	1.0	-50.7	-13.0	-37.7	
7.08	-71.8	V	3.0	-16.1	33.9	1.0	-49.0	-13.0	-36.0	

Rev. 02.24.17

LTE B66 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 50893
Configuration: EUT
Mode: LTE Band 66, 20MHz 16-QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1720.0MHz)										
3.44	-68.9	H	3.0	-20.1	34.6	1.0	-53.7	-13.0	-40.7	
5.16	-70.0	H	3.0	-17.2	34.2	1.0	-50.4	-13.0	-37.4	
6.88	-71.2	H	3.0	-15.6	33.9	1.0	-48.5	-13.0	-35.5	
3.44	-69.0	V	3.0	-20.0	34.6	1.0	-53.6	-13.0	-40.6	
5.16	-69.9	V	3.0	-16.8	34.2	1.0	-50.0	-13.0	-37.0	
6.88	-70.7	V	3.0	-15.3	33.9	1.0	-48.2	-13.0	-35.2	
Mid Channel (1745.0MHz)										
3.49	-69.0	H	3.0	-20.1	34.6	1.0	-53.6	-13.0	-40.6	
5.24	-69.3	H	3.0	-16.3	34.2	1.0	-49.5	-13.0	-36.5	
6.98	-70.2	H	3.0	-70.2	33.9	1.0	-103.1	-13.0	-90.1	
3.49	-70.2	V	3.0	-70.2	34.6	1.0	-103.8	-13.0	-90.8	
5.24	-70.5	V	3.0	-17.3	34.2	1.0	-50.5	-13.0	-37.5	
6.98	-72.0	V	3.0	-16.5	33.9	1.0	-49.4	-13.0	-36.4	
High Channel (1770.0MHz)										
3.54	-68.1	H	3.0	-18.9	34.5	1.0	-52.5	-13.0	-39.5	
5.31	-70.0	H	3.0	-16.9	34.2	1.0	-50.1	-13.0	-37.1	
7.08	-70.4	H	3.0	-14.6	33.9	1.0	-47.4	-13.0	-34.4	
3.54	-68.8	V	3.0	-19.5	34.5	1.0	-53.0	-13.0	-40.0	
5.31	-69.6	V	3.0	-16.3	34.2	1.0	-49.5	-13.0	-36.5	
7.08	-71.1	V	3.0	-16.4	33.9	1.0	-48.3	-13.0	-35.3	

Rev. 02.24.17

LTE B66 20MHz 16QAM

10. SETUP PHOTOS

Please refer to 12124122-EP1V1

UL VERIFICATION SERVICES INC. FORM NO: CCSUP4031B
47173 BENICIA STREET, FREMONT, CA 94538, USA TEL: (510) 771-1000 FAX: (510) 661-0888
This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.