8.5. PEAK-TO-AVERAGE POWER RATIO

LIMIT

In addition, the peak-to-average power ratio (PAPR) of the transmitter shall not exceed 13 dB for more than 0.1% of the time and shall use a signal corresponding to the highest PAPR during periods of continuous transmission.

RESULT

Test was performed on Port 1 antenna; full resource block (FRB) for each bandwidth was used to measure as the worst case. The results from all CCDF measurements are passed with 13dB peak-to-average ratio criteria.

8.5.1. LTE BAND 7

ID:	10643	Date:	5/11/18

Band	Bandwidth (MHz)	PCC f (MHz)	SCC1 f (MHz)	Modulation	Conducted Power (dBm)		Peak-to-Average Power Ratio (dB)
					Peak	Average	
Band 7	10MHz / 20MHz	2525.6	2540.0	QPSK	30.81	23.08	7.73
				16QAM	30.91	22.10	8.81
	15 MHz / 15MHz	2527.5	2542.5	QPSK	30.45	23.04	7.41
				16QAM	30.55	22.07	8.48
	15MHz / 20MHz	2525.3	2542.4	QPSK	30.47	22.99	7.48
				16QAM	30.47	22.02	8.45
	20MHz / 10MHz	2530.1	2544.5	QPSK	30.85	23.01	7.84
				16QAM	30.66	22.02	8.64
	20MHz / 15MHz	2527.6	2544.7	QPSK	30.50	23.04	7.46
				16QAM	30.45	22.09	8.36
	20MHz / 20MHz	2525.1	2544.9	QPSK	30.78	23.11	7.67
				16QAM	30.13	22.1	8.03
Duty Cycle Correction Factor (dB) =			0.00				
Peak-to-Average Power Ratio= Peak Reading - Average Reading - Duty Cycle Correction Factor							

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

8.5.2. LTE BAND 41

ID:	10643	Date:	5/11/18

Band	Bandwidth (MHz)	PCC f (MHz)	SCC1 f (MHz)	Modulation	Conducted Power (dBm)		Peak-to-Average Power Ratio (dB)
					Peak	Average	
Band 41 (FCC)	5MHz / 20MHz	2583.8	2595.5	QPSK	31.22	16.14	8.09
				16QAM	31.39	15.18	9.22
	10MHz / 20MHz	2583.6	2598.0	QPSK	31.04	16.02	8.03
				16QAM	31.27	15.06	9.22
	15MHz / 15MHz	2585.5	2600.5	QPSK	30.76	16.00	7.77
				16QAM	30.93	15.04	8.90
	15MHz / 20MHz	2583.3	2600.4	QPSK	30.65	16.04	7.62
				16QAM	30.78	15.08	8.71
	20MHz / 5MHz	2590.5	2602.2	QPSK	30.92	16.11	7.82
				16QAM	31.07	15.18	8.90
	20MHz / 10MHz	2588.1	2602.5	QPSK	38.11	23.33	7.79
				16QAM	30.84	15.02	8.83
	20MHz / 15MHz	2585.6	2602.7	QPSK	30.48	16.00	7.49
				16QAM	30.64	15.06	8.59
	20MHz / 20MHz	2583.1	2602.9	QPSK	30.47	16.02	7.46
				16QAM	30.42	15.05	8.38
Duty Cycle Correction Factor (dB) =			6.99				
Peak-to-Average Power Ratio= Peak Reading - Average Reading - Duty Cycle Correction Factor							

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9. RADIATED TEST RESULTS

RULE PART(S)

FCC: §2.1053, §27.53

LIMIT

FCC: §27.53 (m)
At least 55 + 10 log (P) dB on all frequencies more than X megahertz from the channel edge, where X is the greater of 6 megahertz or the actual emission bandwidth as defined in paragraph (m)(6) of this section.

TEST PROCEDURE

KDB 971168 D01 v03r01/ D02 v02r01

MODES TESTED

- LTE Band 7
- LTE Band 41

RESULTS

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.1. FIELD STRENGTH OF SPURIOUS RADIATION, ANT 1

9.1.1. LTE BAND 7

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/28/18
Test Engineer: 10649
Configuration: EUT Only
Mode: LTE Band 7, QPSK UL CA 20/10

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+2524.4MHz 1-99 1-0										
5.03	-63.8	H	3.0	-10.9	38.7	1.0	-48.6	-25.0	-23.6	
7.55	-66.6	H	3.0	-8.7	37.7	1.0	-45.4	-25.0	-20.4	
10.15	-67.8	H	3.0	-6.9	36.2	1.0	-42.1	-25.0	-17.1	
5.03	-63.7	V	3.0	-11.1	38.7	1.0	-48.8	-25.0	-23.8	
7.55	-65.8	V	3.0	-8.2	37.7	1.0	-44.9	-25.0	-19.9	
10.15	-67.8	V	3.0	-6.9	36.2	1.0	-42.1	-25.0	-17.1	
Mid Channel (2530.1MHz)+2544.5MHz 1-99 1-0										
5.07	-63.5	H	3.0	-10.5	38.7	1.0	-48.2	-25.0	-23.2	
7.61	-66.6	H	3.0	-8.7	37.7	1.0	-45.4	-25.0	-20.4	
10.15	-67.0	H	3.0	-6.0	36.2	1.0	-41.3	-25.0	-16.3	
5.07	-63.5	V	3.0	-10.7	38.7	1.0	-48.4	-25.0	-23.4	
7.61	-66.9	V	3.0	-9.2	37.7	1.0	-45.8	-25.0	-20.8	
10.15	-67.3	V	3.0	-6.4	36.2	1.0	-41.6	-25.0	-16.6	
High Channel (2550.1MHz)+2564.5MHz 1-99 1-0										
5.11	-64.7	H	3.0	-11.6	38.7	1.0	-49.3	-25.0	-24.3	
7.67	-66.8	H	3.0	-8.8	37.6	1.0	-45.4	-25.0	-20.4	
10.23	-66.1	H	3.0	-5.2	36.3	1.0	-40.4	-25.0	-15.4	
5.11	-63.8	V	3.0	-11.0	38.7	1.0	-48.7	-25.0	-23.7	
7.67	-65.2	V	3.0	-7.4	37.6	1.0	-44.1	-25.0	-19.1	
10.23	-67.0	V	3.0	-5.9	36.3	1.0	-41.2	-25.0	-16.2	

Rev. 05.21.15

LTE B7 20MHz + 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/28/18
Test Engineer: 10649
Configuration: EUT Only
Mode: LTE Band 7, 16QAM UL CA 20/10

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+2524.4MHz 1-99 1-0										
5.03	-64.4	H	3.0	-11.5	38.7	1.0	-49.2	-25.0	-24.2	
7.55	-65.6	H	3.0	-7.9	37.7	1.0	-44.5	-25.0	-19.5	
10.15	-68.1	H	3.0	-7.2	36.2	1.0	-42.4	-25.0	-17.4	
5.03	-63.1	V	3.0	-10.5	38.7	1.0	-48.2	-25.0	-23.2	
7.55	-66.7	V	3.0	-9.1	37.7	1.0	-45.8	-25.0	-20.8	
10.15	-68.3	V	3.0	-7.4	36.2	1.0	-42.6	-25.0	-17.6	
Mid Channel (2530.1MHz)+2544.5MHz 1-99 1-0										
5.07	-63.5	H	3.0	-10.5	38.7	1.0	-48.2	-25.0	-23.2	
7.61	-66.5	H	3.0	-8.6	37.7	1.0	-45.2	-25.0	-20.2	
10.15	-67.8	H	3.0	-6.8	36.2	1.0	-42.1	-25.0	-17.1	
5.07	-64.4	V	3.0	-11.7	38.7	1.0	-49.3	-25.0	-24.3	
7.61	-67.0	V	3.0	-9.2	37.7	1.0	-45.9	-25.0	-20.9	
10.15	-67.4	V	3.0	-6.4	36.2	1.0	-41.7	-25.0	-16.7	
High Channel (2550.1MHz)+2564.5MHz 1-99 1-0										
5.11	-63.5	H	3.0	-10.4	38.7	1.0	-48.1	-25.0	-23.1	
7.67	-65.8	H	3.0	-7.8	37.6	1.0	-44.4	-25.0	-19.4	
10.23	-66.8	H	3.0	-5.8	36.3	1.0	-41.1	-25.0	-16.1	
5.11	-64.7	V	3.0	-11.9	38.7	1.0	-49.6	-25.0	-24.6	
7.67	-65.7	V	3.0	-7.9	37.6	1.0	-44.6	-25.0	-19.6	
10.23	-67.8	V	3.0	-6.7	36.3	1.0	-42.0	-25.0	-17.0	

Rev. 05.21.15

LTE B7 20MHz + 10MHz 16QAM

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 4/282018
Test Engineer: 10649
Configuration: EUT Only
Mode: LTE Band 7, QPSK UL CA 20/20

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+ 2529.8MHz 1-99 1-0										
5.04	-64.0	H	3.0	-15.9	36.1	1.0	-51.0	-25.0	-26.0	
7.56	-66.7	H	3.0	-17.0	36.3	1.0	-52.3	-25.0	-27.3	
10.08	-67.1	H	3.0	-11.7	33.4	1.0	-44.1	-25.0	-19.1	
5.04	-64.2	V	3.0	-14.6	36.3	1.0	-49.8	-25.0	-24.8	
7.56	-66.9	V	3.0	-13.4	34.8	1.0	-47.1	-25.0	-22.1	
10.08	-67.1	V	3.0	-11.1	32.1	1.0	-42.1	-25.0	-17.1	
Mid Channel (2525.1MHz)+2544.9MHz 1-99 1-0										
5.07	-65.2	H	3.0	-14.2	36.0	1.0	-49.2	-25.0	-24.2	
7.61	-65.4	H	3.0	-12.3	35.2	1.0	-46.6	-25.0	-21.6	
10.14	-68.1	H	3.0	-11.8	32.0	1.0	-42.8	-25.0	-17.8	
5.07	-63.8	V	3.0	-16.1	36.1	1.0	-51.2	-25.0	-26.2	
7.61	-66.9	V	3.0	-9.2	37.7	1.0	-45.9	-25.0	-20.9	
10.14	-67.3	V	3.0	-6.4	36.2	1.0	-41.6	-25.0	-16.6	
High Channel (2540.2MHz)+2560Mhz 1-99 1-0										
5.10	-64.7	H	3.0	-15.6	36.2	1.0	-50.8	-25.0	-25.8	
7.65	-66.8	H	3.0	-16.1	36.0	1.0	-51.1	-25.0	-26.1	
10.20	-66.1	H	3.0	-9.9	32.0	1.0	-40.9	-25.0	-15.9	
5.10	-65.3	V	3.0	-18.3	36.3	1.0	-53.6	-25.0	-28.6	
7.65	-66.2	V	3.0	-14.9	35.8	1.0	-49.8	-25.0	-24.8	
10.20	-68.1	V	3.0	-7.1	36.3	1.0	-42.3	-25.0	-17.3	

Rev. 05.21.15

LTE B7 20MHz + 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/28/18
Test Engineer: 10649
Configuration: EUT Only
Mode: LTE Band 7, 16QAM UL CA 20/20

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+ 2529.8MHz 1-99 1-0										
5.04	-64.7	H	3.0	-11.8	38.7	1.0	-49.5	-25.0	-24.5	
7.56	-66.1	H	3.0	-8.2	37.7	1.0	-44.9	-25.0	-19.9	
10.08	-67.4	H	3.0	-6.5	36.2	1.0	-41.7	-25.0	-16.7	
5.04	-61.7	V	3.0	-9.0	38.7	1.0	-46.7	-25.0	-21.7	
7.56	-65.9	V	3.0	-8.2	37.7	1.0	-45.0	-25.0	-20.0	
10.08	-67.6	V	3.0	-6.7	36.2	1.0	-41.9	-25.0	-16.9	
Mid Channel (2525.1MHz)+2544.9MHz 1-99 1-0										
5.07	-64.5	H	3.0	-11.5	38.7	1.0	-49.2	-25.0	-24.2	
7.61	-67.5	H	3.0	-9.6	37.7	1.0	-46.3	-25.0	-21.3	
10.14	-67.9	H	3.0	-7.0	36.2	1.0	-42.2	-25.0	-17.2	
5.07	-64.1	V	3.0	-11.4	38.7	1.0	-49.1	-25.0	-24.1	
7.61	-66.8	V	3.0	-9.1	37.7	1.0	-45.8	-25.0	-20.8	
10.14	-66.6	V	3.0	-5.7	36.2	1.0	-40.9	-25.0	-15.9	
High Channel (2540.2MHz)+2560Mhz 1-99 1-0										
5.10	-64.3	H	3.0	-11.3	38.7	1.0	-49.0	-25.0	-24.0	
7.65	-66.3	H	3.0	-8.3	37.7	1.0	-45.0	-25.0	-20.0	
10.20	-67.0	H	3.0	-6.0	36.3	1.0	-41.3	-25.0	-16.3	
5.10	-63.9	V	3.0	-11.1	38.7	1.0	-48.8	-25.0	-23.8	
7.65	-66.4	V	3.0	-8.7	37.7	1.0	-45.3	-25.0	-20.3	
10.20	-67.4	V	3.0	-6.4	36.3	1.0	-41.7	-25.0	-16.7	

Rev. 05.21.15

LTE B7 20MHz + 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.1.2. LTE BAND 41

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/28/18
Test Engineer: 52275
Configuration: EUT
Mode: LTE Band 41, QPSK UL CA 20/5

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) +2517.7MHz 1-99, 1-0										
5.02	-64.3	H	3.0	-11.4	38.7	1.0	-49.1	-25.0	-24.1	
7.54	-66.0	H	3.0	-8.2	37.7	1.0	-44.9	-25.0	-19.9	
10.05	-68.1	H	3.0	-7.3	36.2	1.0	-42.4	-25.0	-17.4	
5.02	-64.2	V	3.0	-11.6	38.7	1.0	-49.3	-25.0	-24.3	
7.54	-67.0	V	3.0	-9.4	37.7	1.0	-46.1	-25.0	-21.1	
10.05	-68.1	V	3.0	-7.3	36.2	1.0	-42.5	-25.0	-17.5	
Mid Channel (2590.5MHz)+2602.2MHz 1-99, 1-0										
5.19	-65.1	H	3.0	-11.8	38.7	1.0	-49.5	-25.0	-24.5	
7.79	-66.6	H	3.0	-8.4	37.6	1.0	-45.0	-25.0	-20.0	
10.39	-66.4	H	3.0	-5.3	36.4	1.0	-40.6	-25.0	-15.6	
5.19	-64.8	V	3.0	-11.8	38.7	1.0	-49.5	-25.0	-24.5	
7.79	-65.8	V	3.0	-7.8	37.6	1.0	-44.4	-25.0	-19.4	
10.39	-68.0	V	3.0	-6.8	36.4	1.0	-42.2	-25.0	-17.2	
High Channel (2675MHz)+2686.7MHz 1-99, 1-0										
5.36	-66.5	H	3.0	-12.9	38.6	1.0	-50.5	-25.0	-25.5	
8.05	-67.4	H	3.0	-8.9	37.4	1.0	-45.3	-25.0	-20.3	
10.73	-67.3	H	3.0	-5.9	36.6	1.0	-41.5	-25.0	-16.5	
5.36	-65.8	V	3.0	-12.5	38.6	1.0	-50.1	-25.0	-25.1	
8.05	-66.6	V	3.0	-8.3	37.4	1.0	-44.7	-25.0	-19.7	
10.73	-67.0	V	3.0	-5.5	36.6	1.0	-41.1	-25.0	-16.1	

Rev. 05.21.15

LTE B41 20MHz + 5MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/28/18
Test Engineer: 52275
Configuration: EUT
Mode: LTE Band 41, 16QAM UL CA 20/5

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) +2517.7MHz 1-99, 1-0										
5.02	-63.9	H	3.0	-11.0	38.7	1.0	-48.7	-25.0	-23.7	
7.54	-66.0	H	3.0	-8.1	37.7	1.0	-44.9	-25.0	-19.9	
10.05	-67.7	H	3.0	-6.8	36.2	1.0	-42.0	-25.0	-17.0	
5.02	-64.8	V	3.0	-12.2	38.7	1.0	-49.9	-25.0	-24.9	
7.54	-67.0	V	3.0	-9.4	37.7	1.0	-46.1	-25.0	-21.1	
10.05	-67.4	V	3.0	-6.6	36.2	1.0	-41.8	-25.0	-16.8	
Mid Channel (2590.5MHz)+2602.2MHz 1-99, 1-0										
5.19	-64.5	H	3.0	-11.3	38.7	1.0	-49.0	-25.0	-24.0	
7.79	-66.4	H	3.0	-8.2	37.6	1.0	-44.8	-25.0	-19.8	
10.39	-66.8	H	3.0	-5.7	36.4	1.0	-41.0	-25.0	-16.0	
5.19	-64.1	V	3.0	-11.2	38.7	1.0	-48.9	-25.0	-23.9	
7.79	-66.1	V	3.0	-8.1	37.6	1.0	-44.7	-25.0	-19.7	
10.39	-67.3	V	3.0	-6.1	36.4	1.0	-41.5	-25.0	-16.5	
High Channel (2675MHz)+2686.7MHz 1-99, 1-0										
5.36	-67.2	H	3.0	-13.6	38.6	1.0	-51.2	-25.0	-26.2	
8.05	-67.0	H	3.0	-8.5	37.4	1.0	-44.9	-25.0	-19.9	
10.73	-67.8	H	3.0	-6.4	36.6	1.0	-42.0	-25.0	-17.0	
5.36	-66.6	V	3.0	-13.3	38.6	1.0	-50.9	-25.0	-25.9	
8.05	-66.3	V	3.0	-8.0	37.4	1.0	-44.4	-25.0	-19.4	
10.73	-67.1	V	3.0	-5.5	36.6	1.0	-41.1	-25.0	-16.1	

Rev. 05.21.15

LTE B41 20MHz + 5MHz 16QAM

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/28/18
Test Engineer: 52275
Configuration: EUT
Mode: LTE Band 41, QPSK UL CA 20/20

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) + 2525.8MHz 1-99 1-0										
5.03	-64.7	H	3.0	-11.7	38.7	1.0	-49.4	-25.0	-24.4	
7.55	-66.7	H	3.0	-8.9	37.7	1.0	-45.6	-25.0	-20.6	
10.06	-67.9	H	3.0	-7.1	36.2	1.0	-42.2	-25.0	-17.2	
5.03	-65.6	V	3.0	-12.9	38.7	1.0	-50.6	-25.0	-25.6	
7.55	-66.0	V	3.0	-8.3	37.7	1.0	-45.1	-25.0	-20.1	
10.06	-69.3	V	3.0	-8.4	36.2	1.0	-43.6	-25.0	-18.6	
Mid Channel (2583.1MHz) + 2602.9MHz 1-99 1-0										
5.19	-65.9	H	3.0	-12.7	38.7	1.0	-50.4	-25.0	-25.4	
7.78	-66.9	H	3.0	-8.8	37.6	1.0	-45.4	-25.0	-20.4	
10.37	-68.3	H	3.0	-7.2	36.4	1.0	-42.6	-25.0	-17.6	
5.19	-64.6	V	3.0	-11.7	38.7	1.0	-49.4	-25.0	-24.4	
7.78	-66.7	V	3.0	-8.7	37.6	1.0	-45.3	-25.0	-20.3	
10.37	-66.9	V	3.0	-5.7	36.4	1.0	-41.0	-25.0	-16.0	
High Channel (2660.2MHz) + 2680MHz 1-99 1-0										
5.34	-67.0	H	3.0	-13.4	38.6	1.0	-51.0	-25.0	-26.0	
8.01	-67.6	H	3.0	-9.2	37.4	1.0	-45.6	-25.0	-20.6	
10.68	-66.6	H	3.0	-5.2	36.6	1.0	-40.8	-25.0	-15.8	
5.34	-66.0	V	3.0	-12.7	38.6	1.0	-50.3	-25.0	-25.3	
8.01	-66.8	V	3.0	-8.6	37.4	1.0	-45.0	-25.0	-20.0	
10.68	-68.0	V	3.0	-6.5	36.6	1.0	-42.1	-25.0	-17.1	

Rev. 05.21.15

LTE B41 20MHz + 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/28/18
Test Engineer: 52275
Configuration: EUT
Mode: LTE Band 41, 16QAM UL CA 20/20

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) + 2525.8MHz 1-99 1-0										
5.03	-64.9	H	3.0	-12.0	38.7	1.0	-49.6	-25.0	-24.6	
7.55	-65.2	H	3.0	-7.4	37.7	1.0	-44.1	-25.0	-19.1	
10.06	-67.3	H	3.0	-6.4	36.2	1.0	-41.6	-25.0	-16.6	
5.03	-65.0	V	3.0	-12.4	38.7	1.0	-50.1	-25.0	-25.1	
7.55	-67.4	V	3.0	-9.7	37.7	1.0	-46.5	-25.0	-21.5	
10.06	-67.7	V	3.0	-6.9	36.2	1.0	-42.0	-25.0	-17.0	
Mid Channel (2583.1MHz) + 2602.9MHz 1-99 1-0										
5.19	-65.1	H	3.0	-11.8	38.7	1.0	-49.5	-25.0	-24.5	
7.78	-65.7	H	3.0	-7.6	37.6	1.0	-44.2	-25.0	-19.2	
10.37	-67.0	H	3.0	-5.8	36.4	1.0	-41.2	-25.0	-16.2	
5.19	-64.3	V	3.0	-11.4	38.7	1.0	-49.0	-25.0	-24.0	
7.78	-66.2	V	3.0	-8.2	37.6	1.0	-44.8	-25.0	-19.8	
10.37	-67.3	V	3.0	-6.1	36.4	1.0	-41.5	-25.0	-16.5	
High Channel (2660.2MHz) + 2680MHz 1-99 1-0										
5.34	-67.6	H	3.0	-14.0	38.6	1.0	-51.7	-25.0	-26.7	
8.01	-65.9	H	3.0	-7.5	37.4	1.0	-43.9	-25.0	-18.9	
10.68	-67.2	H	3.0	-5.9	36.6	1.0	-41.4	-25.0	-16.4	
5.34	-68.4	V	3.0	-15.1	38.6	1.0	-52.8	-25.0	-27.8	
8.01	-67.0	V	3.0	-8.8	37.4	1.0	-45.2	-25.0	-20.2	
10.68	-67.7	V	3.0	-6.2	36.6	1.0	-41.7	-25.0	-16.7	

Rev. 05.21.15

LTE B41 20MHz + 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.2. FIELD STRENGTH OF SPURIOUS RADIATION, ANT 2

9.2.1. LTE BAND 7

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/29/18
Test Engineer: 52275
Configuration: EUT Only
Mode: LTE Band 7, QPSK UL CA 20/10

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+2524.4MHz 1-99 1-0										
5.03	-64.2	H	3.0	-11.3	38.7	1.0	-49.0	-25.0	-24.0	
7.55	-66.5	H	3.0	-8.6	37.7	1.0	-45.3	-25.0	-20.3	
10.07	-67.9	H	3.0	-7.0	36.2	1.0	-42.2	-25.0	-17.2	
5.03	-65.1	V	3.0	-12.4	38.7	1.0	-50.1	-25.0	-25.1	
7.55	-66.6	V	3.0	-9.0	37.7	1.0	-45.7	-25.0	-20.7	
10.07	-68.3	V	3.0	-7.5	36.2	1.0	-42.7	-25.0	-17.7	
Mid Channel (2530.1MHz)+2544.5MHz 1-99 1-0										
5.07	-64.7	H	3.0	-11.7	38.7	1.0	-49.4	-25.0	-24.4	
7.61	-66.8	H	3.0	-8.8	37.7	1.0	-45.5	-25.0	-20.5	
10.15	-67.2	H	3.0	-6.2	36.2	1.0	-41.4	-25.0	-16.4	
5.07	-63.7	V	3.0	-10.9	38.7	1.0	-48.6	-25.0	-23.6	
7.61	-68.2	V	3.0	-10.5	37.7	1.0	-47.1	-25.0	-22.1	
10.15	-67.7	V	3.0	-6.8	36.2	1.0	-42.0	-25.0	-17.0	
High Channel (2550.1MHz)+2564.5MHz 1-99 1-0										
5.11	-64.7	H	3.0	-11.6	38.7	1.0	-49.3	-25.0	-24.3	
7.67	-66.7	H	3.0	-8.7	37.6	1.0	-45.3	-25.0	-20.3	
10.23	-66.5	H	3.0	-5.5	36.3	1.0	-40.8	-25.0	-15.8	
5.11	-64.1	V	3.0	-11.3	38.7	1.0	-49.0	-25.0	-24.0	
7.67	-67.1	V	3.0	-9.3	37.6	1.0	-46.0	-25.0	-21.0	
10.23	-67.2	V	3.0	-6.2	36.3	1.0	-41.4	-25.0	-16.4	

Rev. 05.21.15

LTE B7 20MHz + 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/29/18
Test Engineer: 52275
Configuration: EUT Only
Mode: LTE Band 7, 16QAM UL CA 20/10

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+2524.4MHz 1-99 1-0										
5.03	-64.1	H	3.0	-11.2	38.7	1.0	-48.9	-25.0	-23.9	
7.55	-66.6	H	3.0	-8.7	37.7	1.0	-45.5	-25.0	-20.5	
10.07	-67.1	H	3.0	-6.2	36.2	1.0	-41.4	-25.0	-16.4	
5.03	-63.8	V	3.0	-11.2	38.7	1.0	-48.9	-25.0	-23.9	
7.55	-67.1	V	3.0	-9.5	37.7	1.0	-46.2	-25.0	-21.2	
10.07	-68.3	V	3.0	-7.5	36.2	1.0	-42.6	-25.0	-17.6	
Mid Channel (2530.1MHz)+2544.5MHz 1-99 1-0										
5.07	-63.7	H	3.0	-10.7	38.7	1.0	-48.4	-25.0	-23.4	
7.61	-67.2	H	3.0	-9.2	37.7	1.0	-45.9	-25.0	-20.9	
10.15	-67.9	H	3.0	-6.9	36.2	1.0	-42.1	-25.0	-17.1	
5.07	-64.9	V	3.0	-12.2	38.7	1.0	-49.9	-25.0	-24.9	
7.61	-67.4	V	3.0	-9.6	37.7	1.0	-46.3	-25.0	-21.3	
10.15	-68.8	V	3.0	-7.9	36.2	1.0	-43.1	-25.0	-18.1	
High Channel (2550.1MHz)+2564.5MHz 1-99 1-0										
5.11	-64.1	H	3.0	-11.0	38.7	1.0	-48.7	-25.0	-23.7	
7.67	-66.5	H	3.0	-8.5	37.6	1.0	-45.1	-25.0	-20.1	
10.23	-66.7	H	3.0	-5.7	36.3	1.0	-41.0	-25.0	-16.0	
5.11	-63.7	V	3.0	-10.9	38.7	1.0	-48.6	-25.0	-23.6	
7.67	-65.5	V	3.0	-7.7	37.6	1.0	-44.4	-25.0	-19.4	
10.23	-68.1	V	3.0	-7.1	36.3	1.0	-42.3	-25.0	-17.3	

Rev. 05.21.15

LTE B7 20MHz + 10MHz 16QAM

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/29/18
Test Engineer: 52275
Configuration: EUT Only
Mode: LTE Band 7, QPSK UL CA 20/20

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+ 2529.8MHz 1-99 1-0										
5.04	-63.5	H	3.0	-15.4	36.1	1.0	-50.5	-25.0	-25.5	
7.56	-67.1	H	3.0	-17.4	36.3	1.0	-52.7	-25.0	-27.7	
10.08	-66.5	H	3.0	-11.1	33.4	1.0	-43.5	-25.0	-18.5	
5.04	-64.8	V	3.0	-15.3	36.3	1.0	-50.5	-25.0	-25.5	
7.56	-67.3	V	3.0	-13.7	34.8	1.0	-47.5	-25.0	-22.5	
10.08	-67.6	V	3.0	-11.7	32.1	1.0	-42.7	-25.0	-17.7	
Mid Channel (2525.1MHz)+2544.9MHz 1-99 1-0										
5.07	-65.8	H	3.0	-14.6	36.0	1.0	-49.6	-25.0	-24.6	
7.61	-66.8	H	3.0	-13.8	35.2	1.0	-48.0	-25.0	-23.0	
10.14	-66.7	H	3.0	-10.4	32.0	1.0	-41.4	-25.0	-16.4	
5.07	-64.9	V	3.0	-17.2	36.1	1.0	-52.3	-25.0	-27.3	
7.61	-67.2	V	3.0	-9.4	37.7	1.0	-46.1	-25.0	-21.1	
10.14	-66.7	V	3.0	-5.8	36.2	1.0	-41.0	-25.0	-16.0	
High Channel (2540.2MHz)+2560Mhz 1-99 1-0										
5.10	-63.8	H	3.0	-14.7	36.2	1.0	-49.9	-25.0	-24.9	
7.65	-66.6	H	3.0	-15.9	36.0	1.0	-50.9	-25.0	-25.9	
10.20	-67.2	H	3.0	-10.9	32.0	1.0	-41.9	-25.0	-16.9	
5.10	-65.0	V	3.0	-18.0	36.3	1.0	-53.2	-25.0	-28.2	
7.65	-66.5	V	3.0	-15.3	35.8	1.0	-50.1	-25.0	-25.1	
10.20	-68.3	V	3.0	-7.3	36.3	1.0	-42.5	-25.0	-17.5	

Rev. 05.21.15

LTE B7 20MHz + 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/29/18
Test Engineer: 52275
Configuration: EUT Only
Mode: LTE Band 7, 16QAM UL CA 20/20

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+ 2529.8MHz 1-99 1-0										
5.04	-64.0	H	3.0	-11.1	38.7	1.0	-48.8	-25.0	-23.8	
7.56	-65.9	H	3.0	-8.1	37.7	1.0	-44.8	-25.0	-19.8	
10.08	-67.6	H	3.0	-6.8	36.2	1.0	-41.9	-25.0	-16.9	
5.04	-64.7	V	3.0	-12.1	38.7	1.0	-49.8	-25.0	-24.8	
7.56	-67.9	V	3.0	-10.3	37.7	1.0	-47.0	-25.0	-22.0	
10.08	-67.3	V	3.0	-6.5	36.2	1.0	-41.6	-25.0	-16.6	
Mid Channel (2525.1MHz)+2544.9MHz 1-99 1-0										
5.07	-64.5	H	3.0	-11.5	38.7	1.0	-49.2	-25.0	-24.2	
7.61	-66.0	H	3.0	-8.1	37.7	1.0	-44.8	-25.0	-19.8	
10.14	-67.2	H	3.0	-6.3	36.2	1.0	-41.5	-25.0	-16.5	
5.07	-63.6	V	3.0	-10.9	38.7	1.0	-48.6	-25.0	-23.6	
7.61	-67.2	V	3.0	-9.5	37.7	1.0	-46.2	-25.0	-21.2	
10.14	-67.3	V	3.0	-6.4	36.2	1.0	-41.6	-25.0	-16.6	
High Channel (2540.2MHz)+2560Mhz 1-99 1-0										
5.10	-63.8	H	3.0	-10.7	38.7	1.0	-48.4	-25.0	-23.4	
7.65	-67.1	H	3.0	-9.1	37.7	1.0	-45.8	-25.0	-20.8	
10.20	-66.7	H	3.0	-5.8	36.3	1.0	-41.0	-25.0	-16.0	
5.10	-64.9	V	3.0	-12.2	38.7	1.0	-49.8	-25.0	-24.8	
7.65	-66.9	V	3.0	-9.1	37.7	1.0	-45.8	-25.0	-20.8	
10.20	-67.8	V	3.0	-6.8	36.3	1.0	-42.1	-25.0	-17.1	

Rev. 05.21.15

LTE B7 20MHz + 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.2.2. LTE BAND 41

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/29/18
Test Engineer: 52275
Configuration: EUT Only
Mode: LTE Band 41, QPSK UL CA 20/5

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) +2517.7MHz 1-99, 1-0										
5.02	-63.4	H	3.0	-10.5	38.7	1.0	-48.2	-25.0	-23.2	
7.54	-66.0	H	3.0	-8.2	37.7	1.0	-44.9	-25.0	-19.9	
10.05	-67.9	H	3.0	-7.1	36.2	1.0	-42.2	-25.0	-17.2	
5.02	-64.0	V	3.0	-11.4	38.7	1.0	-49.1	-25.0	-24.1	
7.54	-66.5	V	3.0	-8.9	37.7	1.0	-45.6	-25.0	-20.6	
10.05	-67.9	V	3.0	-7.1	36.2	1.0	-42.2	-25.0	-17.2	
Mid Channel (2590.5MHz)+2602.2MHz 1-99, 1-0										
5.19	-63.5	H	3.0	-10.2	38.7	1.0	-47.9	-25.0	-22.9	
7.79	-65.8	H	3.0	-7.6	37.6	1.0	-44.2	-25.0	-19.2	
10.39	-67.2	H	3.0	-6.1	36.4	1.0	-41.4	-25.0	-16.4	
5.19	-65.7	V	3.0	-12.7	38.7	1.0	-50.4	-25.0	-25.4	
7.79	-65.3	V	3.0	-7.3	37.6	1.0	-43.9	-25.0	-18.9	
10.39	-67.5	V	3.0	-6.3	36.4	1.0	-41.6	-25.0	-16.6	
High Channel (2675MHz)+2686.7MHz 1-99, 1-0										
5.36	-65.4	H	3.0	-11.8	38.6	1.0	-49.4	-25.0	-24.4	
8.04	-66.3	H	3.0	-7.8	37.4	1.0	-44.2	-25.0	-19.2	
10.72	-67.9	H	3.0	-6.4	36.6	1.0	-42.0	-25.0	-17.0	
5.36	-66.5	V	3.0	-13.2	38.6	1.0	-50.8	-25.0	-25.8	
8.04	-66.0	V	3.0	-7.8	37.4	1.0	-44.2	-25.0	-19.2	
10.72	-67.4	V	3.0	-5.8	36.6	1.0	-41.4	-25.0	-16.4	

Rev. 05.21.15

LTE B41 20MHz + 5MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/29/18
Test Engineer: 52275
Configuration: EUT Only
Mode: LTE Band 41, 16QAM UL CA 20/5

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) +2517.7MHz 1-99, 1-0										
5.02	-64.4	H	3.0	-11.4	38.7	1.0	-49.1	-25.0	-24.1	
7.54	-66.0	H	3.0	-8.1	37.7	1.0	-44.9	-25.0	-19.9	
10.05	-68.4	H	3.0	-7.6	36.2	1.0	-42.7	-25.0	-17.7	
5.02	-63.9	V	3.0	-11.2	38.7	1.0	-48.9	-25.0	-23.9	
7.54	-67.2	V	3.0	-9.5	37.7	1.0	-46.3	-25.0	-21.3	
10.05	-67.8	V	3.0	-7.0	36.2	1.0	-42.2	-25.0	-17.2	
Mid Channel (2590.5MHz)+2602.2MHz 1-99, 1-0										
5.19	-64.0	H	3.0	-10.7	38.7	1.0	-48.4	-25.0	-23.4	
7.79	-66.2	H	3.0	-8.0	37.6	1.0	-44.6	-25.0	-19.6	
10.39	-67.2	H	3.0	-6.1	36.4	1.0	-41.5	-25.0	-16.5	
5.19	-65.3	V	3.0	-12.4	38.7	1.0	-50.0	-25.0	-25.0	
7.79	-66.2	V	3.0	-8.3	37.6	1.0	-44.9	-25.0	-19.9	
10.39	-68.5	V	3.0	-7.3	36.4	1.0	-42.7	-25.0	-17.7	
High Channel (2675MHz)+2686.7MHz 1-99, 1-0										
5.36	-66.7	H	3.0	-13.0	38.6	1.0	-50.7	-25.0	-25.7	
8.04	-66.8	H	3.0	-8.4	37.4	1.0	-44.8	-25.0	-19.8	
10.72	-68.0	H	3.0	-6.6	36.6	1.0	-42.2	-25.0	-17.2	
5.36	-66.3	V	3.0	-13.0	38.6	1.0	-50.6	-25.0	-25.6	
8.04	-66.6	V	3.0	-8.4	37.4	1.0	-44.8	-25.0	-19.8	
10.72	-67.8	V	3.0	-6.3	36.6	1.0	-41.9	-25.0	-16.9	

Rev. 05.21.15

LTE B41 20MHz + 5MHz 16QAM

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/29/18
Test Engineer: 38806
Configuration: EUT Only
Mode: LTE Band 41, QPSK UL CA 20/20

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) + 2525.8MHz 1-99 1-0										
5.03	-65.6	H	3.0	-12.7	38.7	1.0	-50.4	-25.0	-25.4	
7.55	-66.8	H	3.0	-8.9	37.7	1.0	-45.7	-25.0	-20.7	
10.06	-67.1	H	3.0	-6.2	36.2	1.0	-41.4	-25.0	-16.4	
5.03	-64.5	V	3.0	-11.9	38.7	1.0	-49.5	-25.0	-24.5	
7.55	-65.7	V	3.0	-8.1	37.7	1.0	-44.8	-25.0	-19.8	
10.06	-66.3	V	3.0	-5.5	36.2	1.0	-40.7	-25.0	-15.7	
Mid Channel (2583.1MHz) + 2602.9MHz 1-99 1-0										
5.19	-64.9	H	3.0	-11.6	38.7	1.0	-49.3	-25.0	-24.3	
7.78	-65.5	H	3.0	-7.4	37.6	1.0	-44.0	-25.0	-19.0	
10.37	-66.7	H	3.0	-5.6	36.4	1.0	-40.9	-25.0	-15.9	
5.19	-65.1	V	3.0	-12.2	38.7	1.0	-49.9	-25.0	-24.9	
7.78	-66.8	V	3.0	-8.9	37.6	1.0	-45.4	-25.0	-20.4	
10.37	-67.9	V	3.0	-6.7	36.4	1.0	-42.1	-25.0	-17.1	
High Channel (2660.2MHz) + 2680MHz 1-99 1-0										
5.34	-63.8	H	3.0	-10.2	38.6	1.0	-47.8	-25.0	-22.8	
8.01	-64.5	H	3.0	-6.1	37.4	1.0	-42.5	-25.0	-17.5	
10.68	-66.0	H	3.0	-4.6	36.6	1.0	-40.2	-25.0	-15.2	
5.34	-64.2	V	3.0	-10.9	38.6	1.0	-48.6	-25.0	-23.6	
8.01	-65.3	V	3.0	-7.1	37.4	1.0	-43.5	-25.0	-18.5	
10.68	-66.7	V	3.0	-5.2	36.6	1.0	-40.7	-25.0	-15.7	

Rev. 05.21.15

LTE B41 20MHz + 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/29/18
Test Engineer: 38806
Configuration: EUT Only
Mode: LTE Band 41, 16QAM UL CA 20/20

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) + 2525.8MHz 1-99 1-0										
5.03	-65.8	H	3.0	-12.9	38.7	1.0	-50.6	-25.0	-25.6	
7.55	-67.0	H	3.0	-9.1	37.7	1.0	-45.9	-25.0	-20.9	
10.06	-67.6	H	3.0	-6.7	36.2	1.0	-41.9	-25.0	-16.9	
5.03	-65.0	V	3.0	-12.4	38.7	1.0	-50.0	-25.0	-25.0	
7.55	-66.1	V	3.0	-8.5	37.7	1.0	-45.2	-25.0	-20.2	
10.06	-67.3	V	3.0	-6.5	36.2	1.0	-41.6	-25.0	-16.6	
Mid Channel (2583.1MHz) + 2602.9MHz 1-99 1-0										
5.19	-65.2	H	3.0	-11.9	38.7	1.0	-49.6	-25.0	-24.6	
7.78	-66.1	H	3.0	-8.0	37.6	1.0	-44.5	-25.0	-19.5	
10.37	-67.4	H	3.0	-6.3	36.4	1.0	-41.6	-25.0	-16.6	
5.19	-65.8	V	3.0	-12.9	38.7	1.0	-50.6	-25.0	-25.6	
7.78	-67.2	V	3.0	-9.3	37.6	1.0	-45.8	-25.0	-20.8	
10.37	-68.1	V	3.0	-6.9	36.4	1.0	-42.3	-25.0	-17.3	
High Channel (2660.2MHz) + 2680MHz 1-99 1-0										
5.34	-64.3	H	3.0	-10.7	38.6	1.0	-48.3	-25.0	-23.3	
8.01	-65.1	H	3.0	-6.7	37.4	1.0	-43.1	-25.0	-18.1	
10.68	-66.9	H	3.0	-5.5	36.6	1.0	-41.1	-25.0	-16.1	
5.34	-65.1	V	3.0	-11.8	38.6	1.0	-49.5	-25.0	-24.5	
8.01	-66.0	V	3.0	-7.8	37.4	1.0	-44.2	-25.0	-19.2	
10.68	-67.3	V	3.0	-5.8	36.6	1.0	-41.3	-25.0	-16.3	

Rev. 05.21.15

LTE B41 20MHz + 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.3. FIELD STRENGTH OF SPURIOUS RADIATION, ANT 3

9.3.1. LTE BAND 7

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/30/18
Test Engineer: 10649
Configuration: EUT Only
Mode: LTE Band 7, QPSK UL CA 20/10

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber E | Pre-amplifer: 3m Chamber E | Filter: Filter | Limit: LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+2524.4MHz 1-99 1-0										
5.03	-65.1	H	3.0	-12.2	38.7	1.0	-49.9	-25.0	-24.9	
7.55	-65.8	H	3.0	-8.0	37.7	1.0	-44.7	-25.0	-19.7	
10.07	-67.8	H	3.0	-6.9	36.2	1.0	-42.1	-25.0	-17.1	
5.03	-63.9	V	3.0	-11.3	38.7	1.0	-49.0	-25.0	-24.0	
7.55	-65.7	V	3.0	-8.1	37.7	1.0	-44.8	-25.0	-19.8	
10.07	-67.5	V	3.0	-6.7	36.2	1.0	-41.9	-25.0	-16.9	
Mid Channel (2530.1MHz)+2544.5MHz 1-99 1-0										
5.07	-64.8	H	3.0	-11.8	38.7	1.0	-49.5	-25.0	-24.5	
7.61	-66.7	H	3.0	-8.8	37.7	1.0	-45.5	-25.0	-20.5	
10.15	-67.3	H	3.0	-6.3	36.2	1.0	-41.6	-25.0	-16.6	
5.07	-64.4	V	3.0	-11.7	38.7	1.0	-49.4	-25.0	-24.4	
7.61	-66.3	V	3.0	-8.5	37.7	1.0	-45.2	-25.0	-20.2	
10.15	-67.8	V	3.0	-6.9	36.2	1.0	-42.1	-25.0	-17.1	
High Channel (2550.1MHz)+2564.5MHz 1-99 1-0										
5.11	-64.0	H	3.0	-10.9	38.7	1.0	-48.6	-25.0	-23.6	
7.67	-65.0	H	3.0	-7.0	37.6	1.0	-43.6	-25.0	-18.6	
10.23	-67.3	H	3.0	-6.3	36.3	1.0	-41.6	-25.0	-16.6	
5.11	-64.8	V	3.0	-12.0	38.7	1.0	-49.7	-25.0	-24.7	
7.67	-65.8	V	3.0	-8.0	37.6	1.0	-44.6	-25.0	-19.6	
10.23	-65.7	V	3.0	-4.7	36.3	1.0	-40.0	-25.0	-15.0	

Rev. 05.21.15

LTE B7 20MHz + 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/30/18
Test Engineer: 10649
Configuration: EUT Only
Mode: LTE Band 7, 16QAM UL CA 20/10

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber E | Pre-amplifer: 3m Chamber E | Filter: Filter | Limit: LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+2524.4MHz 1-99 1-0										
5.03	-63.1	H	3.0	-10.2	38.7	1.0	-47.9	-25.0	-22.9	
7.55	-66.5	H	3.0	-8.7	37.7	1.0	-45.4	-25.0	-20.4	
10.07	-68.1	H	3.0	-7.2	36.2	1.0	-42.4	-25.0	-17.4	
5.03	-63.7	V	3.0	-11.1	38.7	1.0	-48.8	-25.0	-23.8	
7.55	-65.1	V	3.0	-7.4	37.7	1.0	-44.2	-25.0	-19.2	
10.07	-68.1	V	3.0	-7.2	36.2	1.0	-42.4	-25.0	-17.4	
Mid Channel (2530.1MHz)+2544.5MHz 1-99 1-0										
5.07	-64.2	H	3.0	-11.2	38.7	1.0	-48.9	-25.0	-23.9	
7.61	-67.1	H	3.0	-9.2	37.7	1.0	-45.9	-25.0	-20.9	
10.15	-67.6	H	3.0	-6.6	36.2	1.0	-41.9	-25.0	-16.9	
5.07	-63.1	V	3.0	-10.4	38.7	1.0	-48.1	-25.0	-23.1	
7.61	-65.6	V	3.0	-7.9	37.7	1.0	-44.6	-25.0	-19.6	
10.15	-67.8	V	3.0	-6.9	36.2	1.0	-42.1	-25.0	-17.1	
High Channel (2550.1MHz)+2564.5MHz 1-99 1-0										
5.11	-65.3	H	3.0	-12.2	38.7	1.0	-49.9	-25.0	-24.9	
7.67	-66.6	H	3.0	-8.6	37.6	1.0	-45.3	-25.0	-20.3	
10.23	-67.5	H	3.0	-6.5	36.3	1.0	-41.8	-25.0	-16.8	
5.11	-64.6	V	3.0	-11.9	38.7	1.0	-49.5	-25.0	-24.5	
7.67	-66.5	V	3.0	-8.7	37.6	1.0	-45.3	-25.0	-20.3	
10.23	-68.1	V	3.0	-7.1	36.3	1.0	-42.3	-25.0	-17.3	

Rev. 05.21.15

LTE B7 20MHz + 10MHz 16QAM

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/30/18
Test Engineer: 10641
Configuration: EUT Only
Mode: LTE Band 7, QPSK UL CA 20/20

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber E | Pre-amplifer: 3m Chamber E | Filter: Filter | Limit: LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+ 2529.8MHz 1-99 1-0										
5.04	-64.5	H	3.0	-16.4	36.1	1.0	-51.5	-25.0	-26.5	
7.56	-66.2	H	3.0	-16.5	36.3	1.0	-51.8	-25.0	-26.8	
10.08	-68.1	H	3.0	-12.6	33.4	1.0	-45.1	-25.0	-20.1	
5.04	-63.2	V	3.0	-13.7	36.3	1.0	-48.9	-25.0	-23.9	
7.56	-66.2	V	3.0	-12.6	34.8	1.0	-46.4	-25.0	-21.4	
10.08	-67.6	V	3.0	-11.6	32.1	1.0	-42.7	-25.0	-17.7	
Mid Channel (2525.1MHz)+2544.9MHz 1-99 1-0										
5.07	-63.7	H	3.0	-12.7	36.0	1.0	-47.7	-25.0	-22.7	
7.61	-66.9	H	3.0	-13.8	35.2	1.0	-48.0	-25.0	-23.0	
10.14	-66.9	H	3.0	-10.6	32.0	1.0	-41.6	-25.0	-16.6	
5.07	-64.3	V	3.0	-16.6	36.1	1.0	-51.7	-25.0	-26.7	
7.61	-64.6	V	3.0	-6.9	37.7	1.0	-43.6	-25.0	-18.6	
10.14	-68.1	V	3.0	-7.2	36.2	1.0	-42.4	-25.0	-17.4	
High Channel (2540.2MHz)+2560Mhz 1-99 1-0										
5.10	-63.7	H	3.0	-14.5	36.2	1.0	-49.8	-25.0	-24.8	
7.65	-66.5	H	3.0	-15.8	36.0	1.0	-50.8	-25.0	-25.8	
10.20	-65.4	H	3.0	-9.2	32.0	1.0	-40.2	-25.0	-15.2	
5.10	-63.4	V	3.0	-16.4	36.3	1.0	-51.6	-25.0	-26.6	
7.65	-66.0	V	3.0	-14.8	35.8	1.0	-49.6	-25.0	-24.6	
10.20	-66.7	V	3.0	-5.7	36.3	1.0	-41.0	-25.0	-16.0	

Rev. 05.21.15

LTE B7 20MHz + 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/30/18
Test Engineer: 10641
Configuration: EUT Only
Mode: LTE Band 7, 16QAM UL CA 20/20

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber E | Pre-amplifer: 3m Chamber E | Filter: Filter | Limit: LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+ 2529.8MHz 1-99 1-0										
5.04	-65.2	H	3.0	-12.3	38.7	1.0	-50.0	-25.0	-25.0	
7.56	-67.2	H	3.0	-9.3	37.7	1.0	-46.0	-25.0	-21.0	
10.08	-68.5	H	3.0	-7.7	36.2	1.0	-42.8	-25.0	-17.8	
5.04	-64.8	V	3.0	-12.1	38.7	1.0	-49.8	-25.0	-24.8	
7.56	-67.3	V	3.0	-9.6	37.7	1.0	-46.3	-25.0	-21.3	
10.08	-67.3	V	3.0	-6.5	36.2	1.0	-41.7	-25.0	-16.7	
Mid Channel (2525.1MHz)+2544.9MHz 1-99 1-0										
5.07	-65.0	H	3.0	-11.9	38.7	1.0	-49.6	-25.0	-24.6	
7.61	-67.4	H	3.0	-9.4	37.7	1.0	-46.1	-25.0	-21.1	
10.14	-68.7	H	3.0	-7.7	36.2	1.0	-43.0	-25.0	-18.0	
5.07	-63.6	V	3.0	-10.9	38.7	1.0	-48.6	-25.0	-23.6	
7.61	-67.1	V	3.0	-9.4	37.7	1.0	-46.1	-25.0	-21.1	
10.14	-67.6	V	3.0	-6.6	36.2	1.0	-41.8	-25.0	-16.8	
High Channel (2540.2MHz)+2560MHz 1-99 1-0										
5.10	-64.2	H	3.0	-11.1	38.7	1.0	-48.8	-25.0	-23.8	
7.61	-66.1	H	3.0	-8.2	37.7	1.0	-44.9	-25.0	-19.9	
10.20	-67.5	H	3.0	-6.5	36.3	1.0	-41.8	-25.0	-16.8	
5.10	-63.7	V	3.0	-10.9	38.7	1.0	-48.6	-25.0	-23.6	
7.61	-65.2	V	3.0	-7.4	37.7	1.0	-44.1	-25.0	-19.1	
10.20	-66.2	V	3.0	-5.2	36.3	1.0	-40.5	-25.0	-15.5	

Rev. 05.21.15

LTE B7 20MHz + 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.3.2. LTE BAND 41

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/30/18
Test Engineer: 10641
Configuration: EUT Only
Mode: LTE Band 41, QPSK UL CA 20/5

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) +2517.7MHz 1-99, 1-0										
5.02	-62.9	H	3.0	-10.0	38.7	1.0	-47.7	-25.0	-22.7	
7.54	-66.1	H	3.0	-8.3	37.7	1.0	-45.0	-25.0	-20.0	
10.05	-67.2	H	3.0	-6.3	36.2	1.0	-41.5	-25.0	-16.5	
5.02	-64.7	V	3.0	-12.1	38.7	1.0	-49.8	-25.0	-24.8	
7.54	-66.7	V	3.0	-9.0	37.7	1.0	-45.8	-25.0	-20.8	
10.05	-68.2	V	3.0	-7.4	36.2	1.0	-42.6	-25.0	-17.6	
Mid Channel (2590.5MHz)+2602.2MHz 1-99, 1-0										
5.19	-65.1	H	3.0	-11.9	38.7	1.0	-49.6	-25.0	-24.6	
7.79	-66.0	H	3.0	-7.8	37.6	1.0	-44.4	-25.0	-19.4	
10.19	-65.6	H	3.0	-4.6	36.2	1.0	-38.8	-25.0	-14.8	
5.19	-64.0	V	3.0	-11.0	38.7	1.0	-48.7	-25.0	-23.7	
7.79	-66.1	V	3.0	-8.2	37.6	1.0	-44.7	-25.0	-19.7	
10.19	-68.0	V	3.0	-7.0	36.2	1.0	-42.2	-25.0	-17.2	
High Channel (2675MHz)+2686.7MHz 1-99, 1-0										
5.36	-66.1	H	3.0	-12.4	38.6	1.0	-50.1	-25.0	-25.1	
8.05	-66.8	H	3.0	-8.4	37.4	1.0	-44.8	-25.0	-19.8	
10.73	-66.3	H	3.0	-4.9	36.6	1.0	-40.5	-25.0	-15.5	
5.36	-67.4	V	3.0	-14.1	38.6	1.0	-51.7	-25.0	-26.7	
8.05	-67.0	V	3.0	-8.7	37.4	1.0	-45.1	-25.0	-20.1	
10.73	-68.3	V	3.0	-6.7	36.6	1.0	-42.3	-25.0	-17.3	

Rev. 05.21.15

LTE B41 20MHz + 5MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/30/18
Test Engineer: 10641
Configuration: EUT Only
Mode: LTE Band 41, 16QAM UL CA 20/5

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) +2517.7MHz 1-99, 1-0										
5.02	-65.5	H	3.0	-12.6	38.7	1.0	-50.3	-25.0	-25.3	
7.54	-65.8	H	3.0	-8.0	37.7	1.0	-44.7	-25.0	-19.7	
10.05	-68.7	H	3.0	-7.8	36.2	1.0	-43.0	-25.0	-18.0	
5.02	-63.9	V	3.0	-11.3	38.7	1.0	-49.0	-25.0	-24.0	
7.54	-66.9	V	3.0	-9.3	37.7	1.0	-46.0	-25.0	-21.0	
10.05	-68.3	V	3.0	-7.4	36.2	1.0	-42.6	-25.0	-17.6	
Mid Channel (2590.5MHz)+2602.2MHz 1-99, 1-0										
5.19	-63.9	H	3.0	-10.6	38.7	1.0	-48.3	-25.0	-23.3	
7.79	-64.8	H	3.0	-6.7	37.6	1.0	-43.3	-25.0	-18.3	
10.19	-66.3	H	3.0	-5.4	36.2	1.0	-40.6	-25.0	-15.6	
5.19	-65.5	V	3.0	-12.5	38.7	1.0	-50.2	-25.0	-25.2	
7.79	-67.5	V	3.0	-9.5	37.6	1.0	-46.1	-25.0	-21.1	
10.19	-67.1	V	3.0	-6.1	36.2	1.0	-41.4	-25.0	-16.4	
High Channel (2675MHz)+2686.7MHz 1-99, 1-0										
5.36	-66.7	H	3.0	-13.0	38.6	1.0	-50.7	-25.0	-25.7	
8.05	-66.7	H	3.0	-8.2	37.4	1.0	-44.6	-25.0	-19.6	
10.73	-67.2	H	3.0	-5.7	36.6	1.0	-41.3	-25.0	-16.3	
5.36	-66.5	V	3.0	-13.2	38.6	1.0	-50.9	-25.0	-25.9	
8.05	-65.7	V	3.0	-7.4	37.4	1.0	-43.8	-25.0	-18.8	
10.73	-67.7	V	3.0	-6.1	36.6	1.0	-41.7	-25.0	-16.7	

Rev. 05.21.15

LTE B41 20MHz + 5MHz 16QAM

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/30/18
Test Engineer: 10641
Configuration: EUT Only
Mode: LTE Band 41, QPSK UL CA 20/20

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) + 2525.8MHz 1-99 1-0										
5.03	-64.2	H	3.0	-11.2	38.7	1.0	-48.9	-25.0	-23.9	
7.55	-66.1	H	3.0	-8.2	37.7	1.0	-44.9	-25.0	-19.9	
10.06	-68.0	H	3.0	-7.2	36.2	1.0	-42.4	-25.0	-17.4	
5.03	-63.6	V	3.0	-11.0	38.7	1.0	-48.6	-25.0	-23.6	
7.55	-66.9	V	3.0	-9.3	37.7	1.0	-46.0	-25.0	-21.0	
10.06	-68.0	V	3.0	-7.2	36.2	1.0	-42.3	-25.0	-17.3	
Mid Channel (2583.1MHz) + 2602.9MHz 1-99 1-0										
5.19	-64.9	H	3.0	-11.7	38.7	1.0	-49.4	-25.0	-24.4	
7.78	-66.4	H	3.0	-8.3	37.6	1.0	-44.9	-25.0	-19.9	
10.37	-67.0	H	3.0	-5.9	36.4	1.0	-41.2	-25.0	-16.2	
5.19	-65.0	V	3.0	-12.1	38.7	1.0	-49.8	-25.0	-24.8	
7.78	-66.7	V	3.0	-8.7	37.6	1.0	-45.3	-25.0	-20.3	
10.37	-68.1	V	3.0	-7.0	36.4	1.0	-42.3	-25.0	-17.3	
High Channel (2660.2MHz) + 2680MHz 1-99 1-0										
5.34	-65.9	H	3.0	-12.4	38.6	1.0	-50.0	-25.0	-25.0	
8.01	-66.6	H	3.0	-8.2	37.4	1.0	-44.7	-25.0	-19.7	
10.68	-67.5	H	3.0	-6.1	36.6	1.0	-41.7	-25.0	-16.7	
5.34	-66.3	V	3.0	-13.0	38.6	1.0	-50.6	-25.0	-25.6	
8.01	-66.5	V	3.0	-8.3	37.4	1.0	-44.7	-25.0	-19.7	
10.68	-67.1	V	3.0	-5.6	36.6	1.0	-41.1	-25.0	-16.1	

Rev. 05.21.15

LTE B41 20MHz + 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/30/18
Test Engineer: 10641
Configuration: EUT Only
Mode: LTE Band 41, 16QAM UL CA 20/20

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) + 2525.8MHz 1-99 1-0										
5.03	-63.9	H	3.0	-11.0	38.7	1.0	-48.7	-25.0	-23.7	
7.55	-67.1	H	3.0	-9.2	37.7	1.0	-45.9	-25.0	-20.9	
10.06	-67.7	H	3.0	-6.8	36.2	1.0	-42.0	-25.0	-17.0	
5.03	-64.6	V	3.0	-11.9	38.7	1.0	-49.6	-25.0	-24.6	
7.55	-67.4	V	3.0	-9.7	37.7	1.0	-46.5	-25.0	-21.5	
10.06	-67.4	V	3.0	-6.6	36.2	1.0	-41.7	-25.0	-16.7	
Mid Channel (2583.1MHz) + 2602.9MHz 1-99 1-0										
5.19	-65.0	H	3.0	-11.7	38.7	1.0	-49.4	-25.0	-24.4	
7.78	-65.4	H	3.0	-7.2	37.6	1.0	-43.8	-25.0	-18.8	
10.37	-67.5	H	3.0	-6.4	36.4	1.0	-41.8	-25.0	-16.8	
5.19	-64.1	V	3.0	-11.2	38.7	1.0	-48.8	-25.0	-23.8	
7.78	-65.9	V	3.0	-8.0	37.6	1.0	-44.6	-25.0	-19.6	
10.37	-67.8	V	3.0	-6.6	36.4	1.0	-42.0	-25.0	-17.0	
High Channel (2660.2MHz) + 2680MHz 1-99 1-0										
5.34	-65.6	H	3.0	-12.0	38.6	1.0	-49.7	-25.0	-24.7	
8.01	-66.8	H	3.0	-8.4	37.4	1.0	-44.9	-25.0	-19.9	
10.68	-66.9	H	3.0	-5.5	36.6	1.0	-41.1	-25.0	-16.1	
5.34	-66.0	V	3.0	-12.8	38.6	1.0	-50.4	-25.0	-25.4	
8.01	-66.5	V	3.0	-8.2	37.4	1.0	-44.6	-25.0	-19.6	
10.68	-67.0	V	3.0	-5.4	36.6	1.0	-41.0	-25.0	-16.0	

Rev. 05.21.15

LTE B41 20MHz + 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.4. FIELD STRENGTH OF SPURIOUS RADIATION, ANT 4

9.4.1. LTE BAND 7

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/29/18
Test Engineer: 38806
Configuration: EUT Only
Mode: LTE Band 7, QPSK UL CA 20/10

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber E | Pre-amplifer: 3m Chamber E | Filter: Filter | Limit: LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+2524.4MHz 1-99 1-0										
5.03	-63.8	H	3.0	-10.9	38.7	1.0	-48.6	-25.0	-23.6	
7.55	-64.5	H	3.0	-6.6	37.7	1.0	-43.4	-25.0	-18.4	
10.15	-65.9	H	3.0	-5.0	36.2	1.0	-40.2	-25.0	-15.2	
5.03	-64.1	V	3.0	-11.5	38.7	1.0	-49.1	-25.0	-24.1	
7.55	-65.0	V	3.0	-7.4	37.7	1.0	-44.1	-25.0	-19.1	
10.15	-66.4	V	3.0	-5.4	36.2	1.0	-40.6	-25.0	-15.6	
Mid Channel (2530.1MHz)+2544.5MHz 1-99 1-0										
5.07	-64.1	H	3.0	-11.1	38.7	1.0	-48.8	-25.0	-23.8	
7.61	-65.3	H	3.0	-7.4	37.7	1.0	-44.1	-25.0	-19.1	
10.15	-66.2	H	3.0	-5.3	36.2	1.0	-40.5	-25.0	-15.5	
5.07	-64.5	V	3.0	-11.8	38.7	1.0	-49.5	-25.0	-24.5	
7.61	-65.5	V	3.0	-7.7	37.7	1.0	-44.4	-25.0	-19.4	
10.15	-66.7	V	3.0	-5.8	36.2	1.0	-41.0	-25.0	-16.0	
High Channel (2550.1MHz)+2564.5MHz 1-99 1-0										
5.11	-64.3	H	3.0	-11.2	38.7	1.0	-48.9	-25.0	-23.9	
7.67	-65.2	H	3.0	-7.2	37.6	1.0	-43.8	-25.0	-18.8	
10.23	-66.6	H	3.0	-5.6	36.3	1.0	-40.9	-25.0	-15.9	
5.11	-64.9	V	3.0	-12.1	38.7	1.0	-49.8	-25.0	-24.8	
7.67	-65.7	V	3.0	-7.9	37.6	1.0	-44.6	-25.0	-19.6	
10.23	-67.1	V	3.0	-6.1	36.3	1.0	-41.4	-25.0	-16.4	

Rev. 05.21.15

LTE B7 20MHz + 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/29/18
Test Engineer: 38806
Configuration: EUT Only
Mode: LTE Band 7, 16QAM UL CA 20/10

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber E | Pre-amplifer: 3m Chamber E | Filter: Filter | Limit: LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+2524.4MHz 1-99 1-0										
5.03	-64.1	H	3.0	-11.2	38.7	1.0	-48.9	-25.0	-23.9	
7.55	-65.2	H	3.0	-7.3	37.7	1.0	-44.0	-25.0	-19.0	
10.15	-66.3	H	3.0	-5.4	36.2	1.0	-40.6	-25.0	-15.6	
5.03	-64.6	V	3.0	-11.9	38.7	1.0	-49.6	-25.0	-24.6	
7.55	-65.5	V	3.0	-7.8	37.7	1.0	-44.6	-25.0	-19.6	
10.15	-66.9	V	3.0	-6.0	36.2	1.0	-41.2	-25.0	-16.2	
Mid Channel (2530.1MHz)+2544.5MHz 1-99 1-0										
5.07	-64.6	H	3.0	-11.6	38.7	1.0	-49.3	-25.0	-24.3	
7.61	-65.9	H	3.0	-7.9	37.7	1.0	-44.6	-25.0	-19.6	
10.15	-67.0	H	3.0	-6.1	36.2	1.0	-41.3	-25.0	-16.3	
5.07	-65.2	V	3.0	-12.5	38.7	1.0	-50.2	-25.0	-25.2	
7.61	-66.1	V	3.0	-8.4	37.7	1.0	-45.1	-25.0	-20.1	
10.15	-67.3	V	3.0	-6.4	36.2	1.0	-41.6	-25.0	-16.6	
High Channel (2550.1MHz)+2564.5MHz 1-99 1-0										
5.11	-64.9	H	3.0	-11.8	38.7	1.0	-49.5	-25.0	-24.5	
7.67	-65.8	H	3.0	-7.8	37.6	1.0	-44.4	-25.0	-19.4	
10.23	-67.2	H	3.0	-6.2	36.3	1.0	-41.5	-25.0	-16.5	
5.11	-65.3	V	3.0	-12.5	38.7	1.0	-50.2	-25.0	-25.2	
7.67	-66.2	V	3.0	-8.3	37.6	1.0	-45.0	-25.0	-20.0	
10.23	-67.5	V	3.0	-6.5	36.3	1.0	-41.7	-25.0	-16.7	

Rev. 05.21.15

LTE B7 20MHz + 10MHz 16QAM

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/29/18
Test Engineer: 38806
Configuration: EUT Only
Mode: LTE Band 7, QPSK UL CA 20/20

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber E | Pre-amplifer: 3m Chamber E | Filter: Filter | Limit: LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+ 2529.8MHz 1-99 1-0										
5.04	-63.8	H	3.0	-15.7	38.7	1.0	-53.3	-25.0	-28.3	
7.56	-64.6	H	3.0	-14.9	37.7	1.0	-51.6	-25.0	-26.6	
10.08	-66.1	H	3.0	-10.7	36.2	1.0	-45.9	-25.0	-20.9	
5.04	-64.1	V	3.0	-14.5	38.7	1.0	-52.2	-25.0	-27.2	
7.56	-65.6	V	3.0	-12.0	37.7	1.0	-48.7	-25.0	-23.7	
10.08	-66.8	V	3.0	-10.8	36.2	1.0	-46.0	-25.0	-21.0	
Mid Channel (2525.1MHz)+2544.9MHz 1-99 1-0										
5.07	-64.0	H	3.0	-13.0	38.7	1.0	-50.7	-25.0	-25.7	
7.61	-65.1	H	3.0	-12.0	37.7	1.0	-48.7	-25.0	-23.7	
10.14	-66.3	H	3.0	-10.0	36.2	1.0	-45.2	-25.0	-20.2	
5.07	-63.7	V	3.0	-16.0	38.7	1.0	-53.7	-25.0	-28.7	
7.61	-64.9	V	3.0	-7.2	37.7	1.0	-43.9	-25.0	-18.9	
10.14	-66.2	V	3.0	-5.3	36.2	1.0	-40.5	-25.0	-15.5	
High Channel (2540.2MHz)+2560MHz 1-99 1-0										
5.10	-64.3	H	3.0	-15.2	38.7	1.0	-52.9	-25.0	-27.9	
7.65	-65.7	H	3.0	-15.0	37.7	1.0	-51.7	-25.0	-26.7	
10.20	-66.9	H	3.0	-10.6	36.3	1.0	-45.9	-25.0	-20.9	
5.10	-64.5	V	3.0	-17.5	38.7	1.0	-55.2	-25.0	-30.2	
7.65	-65.8	V	3.0	-14.5	37.7	1.0	-51.2	-25.0	-26.2	
10.20	-67.1	V	3.0	-6.1	36.3	1.0	-41.4	-25.0	-16.4	

Rev. 05.21.15

LTE B7 20MHz + 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/29/18
Test Engineer: 38806
Configuration: EUT Only
Mode: LTE Band 7, 16QAM UL CA 20/20

Test Equipment:
Substitution: Horn T344 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber E | Pre-amplifer: 3m Chamber E | Filter: Filter | Limit: LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)+ 2529.8MHz 1-99 1-0										
5.04	-64.0	H	3.0	-11.1	38.7	1.0	-48.7	-25.0	-23.7	
7.56	-65.2	H	3.0	-7.3	37.7	1.0	-44.1	-25.0	-19.1	
10.08	-66.5	H	3.0	-5.6	36.2	1.0	-40.8	-25.0	-15.8	
5.04	-64.6	V	3.0	-12.0	38.7	1.0	-49.6	-25.0	-24.6	
7.56	-66.1	V	3.0	-8.4	37.7	1.0	-45.2	-25.0	-20.2	
10.08	-67.3	V	3.0	-6.4	36.2	1.0	-41.6	-25.0	-16.6	
Mid Channel (2525.1MHz)+2544.9MHz 1-99 1-0										
5.07	-64.6	H	3.0	-11.6	38.7	1.0	-49.2	-25.0	-24.2	
7.61	-65.7	H	3.0	-7.8	37.7	1.0	-44.5	-25.0	-19.5	
10.14	-66.9	H	3.0	-6.0	36.2	1.0	-41.2	-25.0	-16.2	
5.07	-64.1	V	3.0	-11.4	38.7	1.0	-49.1	-25.0	-24.1	
7.61	-65.3	V	3.0	-7.5	37.7	1.0	-44.2	-25.0	-19.2	
10.14	-66.8	V	3.0	-5.9	36.2	1.0	-41.1	-25.0	-16.1	
High Channel (2540.2MHz)+2560MHz 1-99 1-0										
5.10	-64.9	H	3.0	-11.9	38.7	1.0	-49.5	-25.0	-24.5	
7.65	-66.2	H	3.0	-8.2	37.7	1.0	-44.9	-25.0	-19.9	
10.20	-67.3	H	3.0	-6.3	36.3	1.0	-41.5	-25.0	-16.5	
5.10	-65.0	V	3.0	-12.2	38.7	1.0	-49.9	-25.0	-24.9	
7.65	-66.3	V	3.0	-8.5	37.7	1.0	-45.2	-25.0	-20.2	
10.20	-67.6	V	3.0	-6.6	36.3	1.0	-41.8	-25.0	-16.8	

Rev. 05.21.15

LTE B7 20MHz + 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.4.2. LTE BAND 41

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/30/18
Test Engineer: 10649
Configuration: EUT Only
Mode: LTE Band 41, QPSK UL CA 20/5

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) +2517.7MHz 1-99, 1-0										
5.02	-64.3	H	3.0	-11.4	38.7	1.0	-49.1	-25.0	-24.1	
7.54	-66.4	H	3.0	-8.6	37.7	1.0	-45.3	-25.0	-20.3	
10.05	-67.8	H	3.0	-7.0	36.2	1.0	-42.1	-25.0	-17.1	
5.02	-64.0	V	3.0	-11.3	38.7	1.0	-49.0	-25.0	-24.0	
7.54	-66.9	V	3.0	-8.3	37.7	1.0	-46.0	-25.0	-21.0	
10.05	-68.0	V	3.0	-7.2	36.2	1.0	-42.3	-25.0	-17.3	
Mid Channel (2590.5MHz)+2602.2MHz 1-99, 1-0										
5.19	-64.6	H	3.0	-11.3	38.7	1.0	-49.0	-25.0	-24.0	
7.79	-66.3	H	3.0	-8.2	37.6	1.0	-44.8	-25.0	-19.8	
10.39	-67.7	H	3.0	-6.6	36.4	1.0	-42.0	-25.0	-17.0	
5.19	-65.2	V	3.0	-12.3	38.7	1.0	-50.0	-25.0	-25.0	
7.79	-65.7	V	3.0	-7.8	37.6	1.0	-44.3	-25.0	-19.3	
10.39	-67.1	V	3.0	-5.9	36.4	1.0	-41.2	-25.0	-16.2	
High Channel (2675MHz)+2686.7MHz 1-99, 1-0										
5.36	-66.1	H	3.0	-12.5	38.6	1.0	-50.1	-25.0	-25.1	
8.04	-67.1	H	3.0	-8.6	37.4	1.0	-45.0	-25.0	-20.0	
10.72	-68.1	H	3.0	-6.7	36.6	1.0	-42.3	-25.0	-17.3	
5.36	-65.8	V	3.0	-12.5	38.6	1.0	-50.1	-25.0	-25.1	
8.04	-66.1	V	3.0	-7.9	37.4	1.0	-44.3	-25.0	-19.3	
10.72	-66.8	V	3.0	-5.2	36.6	1.0	-40.8	-25.0	-15.8	

Rev. 05.21.15

LTE B41 20MHz + 5MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/30/18
Test Engineer: 10649
Configuration: EUT Only
Mode: LTE Band 41, 16QAM UL CA 20/5

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) +2517.7MHz 1-99, 1-0										
5.02	-65.5	H	3.0	-12.6	38.7	1.0	-50.3	-25.0	-25.3	
7.54	-66.2	H	3.0	-8.4	37.7	1.0	-45.1	-25.0	-20.1	
10.05	-68.3	H	3.0	-7.4	36.2	1.0	-42.6	-25.0	-17.6	
5.02	-63.4	V	3.0	-10.8	38.7	1.0	-48.4	-25.0	-23.4	
7.54	-67.2	V	3.0	-9.6	37.7	1.0	-46.3	-25.0	-21.3	
10.05	-67.8	V	3.0	-7.0	36.2	1.0	-42.1	-25.0	-17.1	
Mid Channel (2590.5MHz)+2602.2MHz 1-99, 1-0										
5.19	-64.3	H	3.0	-11.0	38.7	1.0	-48.7	-25.0	-23.7	
7.79	-67.3	H	3.0	-9.2	37.6	1.0	-45.8	-25.0	-20.8	
10.39	-68.5	H	3.0	-7.3	36.4	1.0	-42.7	-25.0	-17.7	
5.19	-63.8	V	3.0	-10.9	38.7	1.0	-48.6	-25.0	-23.6	
7.79	-66.6	V	3.0	-8.7	37.6	1.0	-45.3	-25.0	-20.3	
10.39	-67.9	V	3.0	-6.7	36.4	1.0	-42.0	-25.0	-17.0	
High Channel (2675MHz)+2686.7MHz 1-99, 1-0										
5.36	-66.7	H	3.0	-13.1	38.6	1.0	-50.7	-25.0	-25.7	
8.04	-66.4	H	3.0	-8.0	37.4	1.0	-44.4	-25.0	-19.4	
10.72	-67.1	H	3.0	-5.7	36.6	1.0	-41.3	-25.0	-16.3	
5.36	-66.3	V	3.0	-13.0	38.6	1.0	-50.6	-25.0	-25.6	
8.04	-66.1	V	3.0	-7.8	37.4	1.0	-44.2	-25.0	-19.2	
10.72	-68.4	V	3.0	-6.9	36.6	1.0	-42.5	-25.0	-17.5	

Rev. 05.21.15

LTE B41 20MHz + 5MHz 16QAM

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/30/18
Test Engineer: 10649
Configuration: EUT Only
Mode: LTE Band 41, QPSK UL CA 20/20

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) + 2525.8MHz 1-99 1-0										
5.03	-63.9	H	3.0	-11.0	38.7	1.0	-48.7	-25.0	-23.7	
7.55	-67.0	H	3.0	-9.1	37.7	1.0	-45.9	-25.0	-20.9	
10.06	-67.4	H	3.0	-6.5	36.2	1.0	-41.7	-25.0	-16.7	
5.03	-64.0	V	3.0	-11.4	38.7	1.0	-49.1	-25.0	-24.1	
7.55	-66.6	V	3.0	-9.0	37.7	1.0	-45.7	-25.0	-20.7	
10.06	-67.7	V	3.0	-6.9	36.2	1.0	-42.1	-25.0	-17.1	
Mid Channel (2583.1MHz) + 2602.9MHz 1-99 1-0										
5.19	-64.9	H	3.0	-11.7	38.7	1.0	-49.4	-25.0	-24.4	
7.78	-65.8	H	3.0	-7.7	37.6	1.0	-44.3	-25.0	-19.3	
10.37	-67.0	H	3.0	-5.9	36.4	1.0	-41.2	-25.0	-16.2	
5.19	-63.8	V	3.0	-10.8	38.7	1.0	-48.5	-25.0	-23.5	
7.78	-65.8	V	3.0	-7.9	37.6	1.0	-44.4	-25.0	-19.4	
10.37	-66.2	V	3.0	-5.0	36.4	1.0	-40.4	-25.0	-15.4	
High Channel (2660.2MHz) + 2680MHz 1-99 1-0										
5.34	-66.6	H	3.0	-13.0	38.6	1.0	-50.6	-25.0	-25.6	
8.01	-67.0	H	3.0	-8.6	37.4	1.0	-45.0	-25.0	-20.0	
10.68	-67.6	H	3.0	-6.2	36.6	1.0	-41.8	-25.0	-16.8	
5.34	-66.9	V	3.0	-13.6	38.6	1.0	-51.2	-25.0	-26.2	
8.01	-67.0	V	3.0	-8.8	37.4	1.0	-45.2	-25.0	-20.2	
10.68	-67.7	V	3.0	-6.2	36.6	1.0	-41.7	-25.0	-16.7	

Rev. 05.21.15

LTE B41 20MHz + 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/30/18
Test Engineer: 10649
Configuration: EUT Only
Mode: LTE Band 41, 16QAM UL CA 20/20

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz) + 2525.8MHz 1-99 1-0										
5.03	-64.8	H	3.0	-11.7	38.7	1.0	-49.4	-25.0	-24.4	
7.55	-66.2	H	3.0	-8.3	37.7	1.0	-45.1	-25.0	-20.1	
10.06	-66.8	H	3.0	-5.9	36.2	1.0	-41.1	-25.0	-16.1	
5.03	-64.1	V	3.0	-11.5	38.7	1.0	-49.2	-25.0	-24.2	
7.55	-67.1	V	3.0	-9.4	37.7	1.0	-46.2	-25.0	-21.2	
10.06	-67.7	V	3.0	-6.9	36.2	1.0	-42.0	-25.0	-17.0	
Mid Channel (2583.1MHz) + 2602.9MHz 1-99 1-0										
5.19	-64.5	H	3.0	-11.2	38.7	1.0	-48.9	-25.0	-23.9	
7.78	-66.1	H	3.0	-8.0	37.6	1.0	-44.5	-25.0	-19.5	
10.37	-67.6	H	3.0	-6.5	36.4	1.0	-41.9	-25.0	-16.9	
5.19	-62.7	V	3.0	-9.8	38.7	1.0	-47.4	-25.0	-22.4	
7.78	-66.8	V	3.0	-8.8	37.6	1.0	-45.4	-25.0	-20.4	
10.37	-67.3	V	3.0	-6.1	36.4	1.0	-41.4	-25.0	-16.4	
High Channel (2660.2MHz) + 2680MHz 1-99 1-0										
5.34	-65.9	H	3.0	-12.3	38.6	1.0	-49.9	-25.0	-24.9	
8.01	-67.3	H	3.0	-8.9	37.4	1.0	-45.3	-25.0	-20.3	
10.68	-67.0	H	3.0	-5.6	36.6	1.0	-41.2	-25.0	-16.2	
5.34	-67.0	V	3.0	-13.7	38.6	1.0	-51.3	-25.0	-26.3	
8.01	-66.6	V	3.0	-8.4	37.4	1.0	-44.8	-25.0	-19.8	
10.68	-66.8	V	3.0	-5.3	36.6	1.0	-40.9	-25.0	-15.9	

Rev. 05.21.15

LTE B41 20MHz + 20MHz 16QAM

END OF REPORT

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

10. SETUP PHOTOS

Please refer to 12124122-EP1V1 for setup photos

UL VERIFICATION SERVICES INC. FORM NO: CCSUP4031B
47173 BENICIA STREET, FREMONT, CA 94538, USA TEL: (510) 771-1000 FAX: (510) 661-0888
This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.