9.2.3. LTE BAND 7

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 7, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)										
5.02	-67.7	H	3.0	-14.8	38.7	1.0	-52.5	-25.0	-27.5	
7.53	-69.5	H	3.0	-11.7	37.7	1.0	-48.4	-25.0	-23.4	
10.04	-72.4	H	3.0	-11.6	36.2	1.0	-46.7	-25.0	-21.7	
5.02	-67.0	V	3.0	-14.4	38.7	1.0	-52.1	-25.0	-27.1	
7.53	-69.8	V	3.0	-12.1	37.7	1.0	-48.9	-25.0	-23.9	
10.04	-73.1	V	3.0	-12.3	36.2	1.0	-47.4	-25.0	-22.4	
Mid Channel (2535MHz)										
5.07	-67.4	H	3.0	-14.4	38.7	1.0	-52.1	-25.0	-27.1	
7.61	-70.3	H	3.0	-12.4	37.7	1.0	-49.1	-25.0	-24.1	
10.14	-72.5	H	3.0	-11.6	36.2	1.0	-46.8	-25.0	-21.8	
5.07	-67.9	V	3.0	-15.2	38.7	1.0	-52.9	-25.0	-27.9	
7.61	-71.1	V	3.0	-13.4	37.7	1.0	-50.1	-25.0	-25.1	
10.14	-73.5	V	3.0	-12.6	36.2	1.0	-47.8	-25.0	-22.8	
High Channel (2560MHz)										
5.12	-67.9	H	3.0	-14.8	38.7	1.0	-52.4	-25.0	-27.4	
7.68	-70.1	H	3.0	-12.1	37.6	1.0	-48.8	-25.0	-23.8	
10.24	-72.4	H	3.0	-11.4	36.3	1.0	-46.7	-25.0	-21.7	
5.12	-66.3	V	3.0	-13.5	38.7	1.0	-51.2	-25.0	-26.2	
7.68	-69.0	V	3.0	-11.2	37.6	1.0	-47.8	-25.0	-22.8	
10.24	-72.9	V	3.0	-11.9	36.3	1.0	-47.2	-25.0	-22.2	

Rev. 05.21.15

LTE B7 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 7, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)										
5.02	-67.0	H	3.0	-14.1	38.7	1.0	-51.8	-25.0	-26.8	
7.53	-70.3	H	3.0	-12.5	37.7	1.0	-49.2	-25.0	-24.2	
10.04	-72.3	H	3.0	-11.5	36.2	1.0	-46.6	-25.0	-21.6	
5.02	-67.5	V	3.0	-14.9	38.7	1.0	-52.6	-25.0	-27.6	
7.53	-69.3	V	3.0	-11.7	37.7	1.0	-48.4	-25.0	-23.4	
10.04	-72.8	V	3.0	-12.0	36.2	1.0	-47.1	-25.0	-22.1	
Mid Channel (2535MHz)										
5.07	-67.8	H	3.0	-14.8	38.7	1.0	-52.4	-25.0	-27.4	
7.61	-71.0	H	3.0	-13.1	37.7	1.0	-49.8	-25.0	-24.8	
10.14	-71.9	H	3.0	-11.0	36.2	1.0	-46.2	-25.0	-21.2	
5.07	-66.4	V	3.0	-13.6	38.7	1.0	-51.3	-25.0	-26.3	
7.61	-70.1	V	3.0	-12.4	37.7	1.0	-49.1	-25.0	-24.1	
10.14	-72.7	V	3.0	-11.8	36.2	1.0	-47.0	-25.0	-22.0	
High Channel (2560MHz)										
5.12	-67.7	H	3.0	-14.5	38.7	1.0	-52.2	-25.0	-27.2	
7.68	-69.2	H	3.0	-11.2	37.6	1.0	-47.8	-25.0	-22.8	
10.24	-73.0	H	3.0	-12.0	36.3	1.0	-47.3	-25.0	-22.3	
5.12	-66.9	V	3.0	-14.1	38.7	1.0	-51.8	-25.0	-26.8	
7.68	-69.7	V	3.0	-11.9	37.6	1.0	-48.5	-25.0	-23.5	
10.24	-72.4	V	3.0	-11.4	36.3	1.0	-46.7	-25.0	-21.7	

Rev. 05.21.15

LTE B7 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.2.4. LTE BAND 12

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 12, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (704MHz)										
1.41	-65.3	H	3.0	-23.7	38.1	1.0	-60.8	-13.0	-47.8	
2.11	-65.9	H	3.0	-22.3	38.0	1.0	-59.3	-13.0	-46.3	
2.82	-67.5	H	3.0	-20.4	38.4	1.0	-57.8	-13.0	-44.8	
1.41	-63.9	V	3.0	-22.9	38.1	1.0	-60.0	-13.0	-47.0	
2.11	-65.3	V	3.0	-21.2	38.0	1.0	-58.1	-13.0	-45.1	
2.82	-66.9	V	3.0	-20.0	38.4	1.0	-57.5	-13.0	-44.5	
Mid Channel (707.5MHz)										
1.42	-65.6	H	3.0	-23.9	38.0	1.0	-61.0	-13.0	-48.0	
2.12	-66.3	H	3.0	-22.7	38.0	1.0	-59.6	-13.0	-46.6	
2.83	-66.8	H	3.0	-19.7	38.4	1.0	-57.1	-13.0	-44.1	
1.42	-64.8	V	3.0	-23.8	38.0	1.0	-60.9	-13.0	-47.9	
2.12	-66.1	V	3.0	-21.9	38.0	1.0	-58.9	-13.0	-45.9	
2.83	-68.2	V	3.0	-21.2	38.4	1.0	-58.6	-13.0	-45.6	
High Channel (711MHz)										
1.42	-64.8	H	3.0	-23.1	38.0	1.0	-60.2	-13.0	-47.2	
2.13	-66.7	H	3.0	-23.0	38.0	1.0	-60.0	-13.0	-47.0	
2.84	-67.1	H	3.0	-19.8	38.4	1.0	-57.2	-13.0	-44.2	
1.42	-66.0	V	3.0	-25.0	38.0	1.0	-62.0	-13.0	-49.0	
2.13	-66.8	V	3.0	-22.6	38.0	1.0	-59.6	-13.0	-46.6	
2.84	-67.4	V	3.0	-20.4	38.4	1.0	-57.8	-13.0	-44.8	

Rev. 05.21.15

LTE B12 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 12, 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (704MHz)										
1.41	-64.9	H	3.0	-23.3	38.1	1.0	-60.3	-13.0	-47.3	
2.11	-65.8	H	3.0	-22.3	38.0	1.0	-59.2	-13.0	-46.2	
2.82	-66.4	H	3.0	-19.3	38.4	1.0	-56.7	-13.0	-43.7	
1.41	-65.1	V	3.0	-24.1	38.1	1.0	-61.2	-13.0	-48.2	
2.11	-66.9	V	3.0	-22.7	38.0	1.0	-59.7	-13.0	-46.7	
2.82	-66.8	V	3.0	-19.9	38.4	1.0	-57.3	-13.0	-44.3	
Mid Channel (707.5MHz)										
1.42	-65.9	H	3.0	-24.3	38.0	1.0	-61.3	-13.0	-48.3	
2.12	-66.2	H	3.0	-22.6	38.0	1.0	-59.6	-13.0	-46.6	
2.83	-66.9	H	3.0	-19.8	38.4	1.0	-57.2	-13.0	-44.2	
1.42	-65.3	V	3.0	-24.4	38.0	1.0	-61.4	-13.0	-48.4	
2.12	-67.0	V	3.0	-22.9	38.0	1.0	-59.9	-13.0	-46.9	
2.83	-67.7	V	3.0	-20.7	38.4	1.0	-58.2	-13.0	-45.2	
High Channel (711MHz)										
1.42	-65.2	H	3.0	-23.6	38.0	1.0	-60.6	-13.0	-47.6	
2.13	-65.6	H	3.0	-22.0	38.0	1.0	-59.0	-13.0	-46.0	
2.84	-66.6	H	3.0	-19.3	38.4	1.0	-56.7	-13.0	-43.7	
1.42	-65.0	V	3.0	-24.0	38.0	1.0	-61.0	-13.0	-48.0	
2.13	-66.4	V	3.0	-22.3	38.0	1.0	-59.3	-13.0	-46.3	
2.84	-67.3	V	3.0	-20.3	38.4	1.0	-57.7	-13.0	-44.7	

Rev. 05.21.15

LTE B12 10MHz 16QAM

9.2.5. LTE BAND 13

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 13, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B13

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (782MHz)										
1.56	-59.4	H	3.0	-17.1	37.8	1.0	-53.9	-40.0	-13.9	
2.35	-65.6	H	3.0	-21.2	38.1	1.0	-58.3	-13.0	-45.3	
3.13	-67.3	H	3.0	-18.7	38.4	1.0	-56.2	-13.0	-43.2	
1.56	-52.8	V	3.0	-11.1	37.8	1.0	-47.9	-40.0	-7.9	
2.35	-67.7	V	3.0	-23.1	38.1	1.0	-60.2	-13.0	-47.2	
3.13	-67.8	V	3.0	-19.6	38.4	1.0	-57.0	-13.0	-44.0	

Rev. 05.21.15

LTE B13 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 13, 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B13

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (782MHz)										
1.56	-54.9	H	3.0	-11.7	37.8	1.0	-48.6	-40.0	-8.6	
2.35	-66.1	H	3.0	-21.7	38.1	1.0	-58.8	-13.0	-45.8	
3.13	-67.6	H	3.0	-19.1	38.4	1.0	-56.5	-13.0	-43.5	
1.56	-60.2	V	3.0	-18.5	37.8	1.0	-55.3	-40.0	-15.3	
2.35	-68.0	V	3.0	-23.3	38.1	1.0	-60.5	-13.0	-47.5	
3.13	-68.3	V	3.0	-20.2	38.4	1.0	-57.6	-13.0	-44.6	

Rev. 05.21.15

LTE B13 10MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.2.6. LTE BAND 14

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 14, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B14

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (793MHz) [BW 10MHz]										
1.59	-54.5	H	3.0	-12.1	37.8	1.0	-49.0	-40.0	-9.0	
2.38	-64.2	H	3.0	-19.7	38.2	1.0	-56.9	-13.0	-43.9	
3.17	-67.4	H	3.0	-18.7	38.4	1.0	-56.2	-13.0	-43.2	
1.59	-50.6	V	3.0	-8.8	37.8	1.0	-45.6	-40.0	-5.6	
2.38	-62.3	V	3.0	-17.6	38.2	1.0	-54.8	-13.0	-41.8	
3.17	-67.5	V	3.0	-19.2	38.4	1.0	-56.6	-13.0	-43.6	

Rev. 05.21.15

LTE B14 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 14, 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B14

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (793MHz) [BW 10MHz]										
1.59	-56.2	H	3.0	-13.8	37.8	1.0	-50.7	-40.0	-10.7	
2.38	-63.6	H	3.0	-19.1	38.2	1.0	-56.3	-13.0	-43.3	
3.17	-67.7	H	3.0	-19.0	38.4	1.0	-56.5	-13.0	-43.5	
1.59	-51.0	V	3.0	-9.2	37.8	1.0	-46.0	-40.0	-6.0	
2.38	-60.4	V	3.0	-15.7	38.2	1.0	-52.9	-13.0	-39.9	
3.17	-67.7	V	3.0	-19.4	38.4	1.0	-56.9	-13.0	-43.9	

Rev. 05.21.15

LTE B14 10MHz 16QAM

9.2.7. LTE BAND 17

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 05/08/18
Test Engineer: 10649
Configuration: EUT Only
Mode: LTE Band 17, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (710MHz)										
1.42	-56.1	H	3.0	-14.4	38.0	1.0	-51.4	-13.0	-38.4	
2.13	-59.5	H	3.0	-15.8	38.0	1.0	-52.8	-13.0	-39.8	
2.84	-65.2	H	3.0	-18.0	38.4	1.0	-55.4	-13.0	-42.4	
1.42	-67.7	V	3.0	-16.6	38.0	1.0	-53.7	-13.0	-40.7	
2.13	-65.4	V	3.0	-21.3	38.0	1.0	-58.3	-13.0	-45.3	
2.84	-65.6	V	3.0	-18.6	38.4	1.0	-56.1	-13.0	-43.1	

Rev. 05.21.15

LTE B17 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 05/08/18
Test Engineer: 10649
Configuration: EUT Only
Mode: LTE Band 17, 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (710MHz)										
1.42	-58.6	H	3.0	-16.9	38.0	1.0	-53.9	-13.0	-40.9	
2.13	-65.1	H	3.0	-21.5	38.0	1.0	-58.5	-13.0	-45.5	
2.84	-65.4	H	3.0	-18.2	38.4	1.0	-55.6	-13.0	-42.6	
1.42	-66.9	V	3.0	-15.9	38.0	1.0	-53.0	-13.0	-40.0	
2.13	-62.2	V	3.0	-18.0	38.0	1.0	-55.0	-13.0	-42.0	
2.84	-64.7	V	3.0	-17.7	38.4	1.0	-55.2	-13.0	-42.2	

Rev. 05.21.15

LTE B17 10MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.2.8. LTE BAND 25

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 25, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-56.7	H	3.0	-6.7	38.6	1.0	-44.3	-13.0	-31.3	
5.58	-67.8	H	3.0	-13.7	38.6	1.0	-51.2	-13.0	-38.2	
7.44	-70.9	H	3.0	-13.1	37.8	1.0	-49.9	-13.0	-36.9	
3.72	-55.8	V	3.0	-5.9	38.6	1.0	-43.5	-13.0	-30.5	
5.58	-67.0	V	3.0	-13.2	38.6	1.0	-50.8	-13.0	-37.8	
7.44	-70.0	V	3.0	-12.5	37.8	1.0	-49.3	-13.0	-36.3	
Mid Channel (1882.5MHz)										
3.77	-64.9	H	3.0	-14.8	38.6	1.0	-52.5	-13.0	-39.5	
5.65	-67.1	H	3.0	-12.8	38.5	1.0	-50.4	-13.0	-37.4	
7.53	-69.8	H	3.0	-12.0	37.7	1.0	-48.7	-13.0	-35.7	
3.77	-65.2	V	3.0	-15.1	38.6	1.0	-52.7	-13.0	-39.7	
5.65	-66.8	V	3.0	-12.8	38.5	1.0	-50.3	-13.0	-37.3	
7.53	-69.5	V	3.0	-11.8	37.7	1.0	-48.6	-13.0	-35.6	
High Channel (1905MHz)										
3.81	-52.9	H	3.0	-2.6	38.6	1.0	-40.3	-13.0	-27.3	
5.72	-67.8	H	3.0	-13.4	38.5	1.0	-50.9	-13.0	-37.9	
7.62	-70.4	H	3.0	-12.5	37.7	1.0	-49.2	-13.0	-36.2	
3.81	-60.1	V	3.0	-9.9	38.6	1.0	-47.5	-13.0	-34.5	
5.72	-68.5	V	3.0	-14.4	38.5	1.0	-52.0	-13.0	-39.0	
7.62	-71.9	V	3.0	-14.1	37.7	1.0	-50.8	-13.0	-37.8	

Rev. 05.21.15

LTE B25 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 25, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-49.9	H	3.0	0.1	38.6	1.0	-37.6	-13.0	-24.6	
5.58	-67.8	H	3.0	-13.7	38.6	1.0	-51.3	-13.0	-38.3	
7.44	-71.3	H	3.0	-13.5	37.8	1.0	-50.3	-13.0	-37.3	
3.72	-55.5	V	3.0	-5.6	38.6	1.0	-43.2	-13.0	-30.2	
5.58	-67.8	V	3.0	-14.0	38.6	1.0	-51.6	-13.0	-38.6	
7.44	-70.3	V	3.0	-12.8	37.8	1.0	-49.6	-13.0	-36.6	
Mid Channel (1882.5MHz)										
3.77	-65.4	H	3.0	-15.3	38.6	1.0	-53.0	-13.0	-40.0	
5.65	-68.0	H	3.0	-13.7	38.5	1.0	-51.2	-13.0	-38.2	
7.53	-70.4	H	3.0	-12.6	37.7	1.0	-49.3	-13.0	-36.3	
3.77	-65.2	V	3.0	-15.1	38.6	1.0	-52.8	-13.0	-39.8	
5.65	-66.3	V	3.0	-12.3	38.5	1.0	-49.9	-13.0	-36.9	
7.53	-70.9	V	3.0	-13.2	37.7	1.0	-50.0	-13.0	-37.0	
High Channel (1905MHz)										
3.81	-56.3	H	3.0	-6.1	38.6	1.0	-43.8	-13.0	-30.8	
5.72	-67.7	H	3.0	-13.3	38.5	1.0	-50.8	-13.0	-37.8	
7.62	-71.3	H	3.0	-13.4	37.7	1.0	-50.1	-13.0	-37.1	
3.81	-56.8	V	3.0	-6.6	38.6	1.0	-44.2	-13.0	-31.2	
5.72	-66.8	V	3.0	-12.7	38.5	1.0	-50.2	-13.0	-37.2	
7.62	-70.2	V	3.0	-12.4	37.7	1.0	-49.1	-13.0	-36.1	

Rev. 05.21.15

LTE B25 20MHz 16QAM

9.2.9. LTE BAND 26 (FCC PART 90S)

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 26 (90S), 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (819MHz)										
1.64	-57.4	H	3.0	-15.0	37.8	1.0	-51.9	-13.0	-38.9	
2.46	-64.5	H	3.0	-19.6	38.4	1.0	-57.0	-13.0	-44.0	
3.28	-67.1	H	3.0	-18.3	38.5	1.0	-55.7	-13.0	-42.7	
1.64	-56.3	V	3.0	-14.3	37.8	1.0	-51.1	-13.0	-38.1	
2.46	-65.2	V	3.0	-20.1	38.4	1.0	-57.5	-13.0	-44.5	
3.28	-67.5	V	3.0	-18.9	38.5	1.0	-56.3	-13.0	-43.3	

Rev. 05.21.15

LTE B26 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 26 (90S), 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (819MHz)										
1.64	-56.7	H	3.0	-14.2	37.8	1.0	-51.1	-13.0	-38.1	
2.46	-61.2	H	3.0	-16.3	38.4	1.0	-53.7	-13.0	-40.7	
3.28	-67.6	H	3.0	-18.7	38.5	1.0	-56.1	-13.0	-43.1	
1.64	-58.3	V	3.0	-16.2	37.8	1.0	-53.0	-13.0	-40.0	
2.46	-62.0	V	3.0	-16.9	38.4	1.0	-54.4	-13.0	-41.4	
3.28	-67.6	V	3.0	-19.0	38.5	1.0	-56.4	-13.0	-43.4	

Rev. 05.21.15

LTE B26 10MHz 16QAM

UL VERIFICATION SERVICES INC. FORM NO: CCSUP4031B
47173 BENICIA STREET, FREMONT, CA 94538, USA TEL: (510) 771-1000 FAX: (510) 661-0888
This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.2.10. LTE BAND 30

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 30, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B30

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (2310MHz)										
4.62	-66.5	H	3.0	-12.7	37.9	1.0	-49.6	-40.0	-9.6	
6.93	-68.8	H	3.0	-10.2	36.5	1.0	-45.7	-40.0	-5.7	
9.24	-71.4	H	3.0	-9.9	34.9	1.0	-43.8	-40.0	-3.8	
4.62	-65.6	V	3.0	-11.9	37.9	1.0	-48.8	-40.0	-8.8	
6.93	-68.9	V	3.0	-9.4	36.5	1.0	-44.8	-40.0	-4.8	
9.24	-71.3	V	3.0	-9.5	34.9	1.0	-43.4	-40.0	-3.4	

Rev. 05.21.15

LTE B30 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 30, 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	LTE B30

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (2310MHz)										
4.62	-67.0	H	3.0	-13.2	37.9	1.0	-50.2	-40.0	-10.2	
6.93	-68.7	H	3.0	-10.1	36.5	1.0	-45.5	-40.0	-5.5	
9.24	-70.6	H	3.0	-9.1	34.9	1.0	-42.9	-40.0	-2.9	
4.62	-67.2	V	3.0	-13.5	37.9	1.0	-50.4	-40.0	-10.4	
6.93	-69.7	V	3.0	-10.2	36.5	1.0	-45.7	-40.0	-5.7	
9.24	-71.9	V	3.0	-10.1	34.9	1.0	-44.0	-40.0	-4.0	

Rev. 05.21.15

LTE B30 10MHz 16QAM

9.2.11. LTE BAND 41

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #: 12204524
Date: 4/16/2018
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 41, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz)										
5.01	-63.7	H	3.0	-13.7	36.9	1.0	-49.6	-25.0	-24.6	
7.52	-69.2	H	3.0	-15.4	35.9	1.0	-50.3	-25.0	-25.3	
10.02	-72.2	H	3.0	-15.7	33.7	1.0	-48.3	-25.0	-23.3	
5.01	-64.7	V	3.0	-14.5	36.9	1.0	-50.4	-25.0	-25.4	
7.52	-68.8	V	3.0	-15.2	35.9	1.0	-50.1	-25.0	-25.1	
10.02	-71.5	V	3.0	-15.3	33.7	1.0	-48.0	-25.0	-23.0	
Mid Channel (2593MHz)										
5.19	-65.5	H	3.0	-15.2	36.8	1.0	-51.0	-25.0	-26.0	
7.78	-68.4	H	3.0	-14.3	35.7	1.0	-48.9	-25.0	-23.9	
10.37	-71.1	H	3.0	-14.4	33.7	1.0	-47.1	-25.0	-22.1	
5.19	-66.3	V	3.0	-15.8	36.8	1.0	-51.6	-25.0	-26.6	
7.78	-67.2	V	3.0	-13.3	35.7	1.0	-48.0	-25.0	-23.0	
10.37	-71.3	V	3.0	-15.0	33.7	1.0	-47.7	-25.0	-22.7	
High Channel (2680MHz)										
5.36	-67.0	H	3.0	-16.3	36.8	1.0	-52.1	-25.0	-27.1	
8.04	-69.4	H	3.0	-15.0	35.4	1.0	-49.4	-25.0	-24.4	
10.72	-70.9	H	3.0	-14.0	33.7	1.0	-46.7	-25.0	-21.7	
5.36	-66.9	V	3.0	-16.1	36.8	1.0	-51.9	-25.0	-26.9	
8.04	-69.3	V	3.0	-15.2	35.4	1.0	-49.6	-25.0	-24.6	
10.72	-70.8	V	3.0	-14.3	33.7	1.0	-47.1	-25.0	-22.1	

Rev. 05.21.15

LTE B41 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #: 12204524
Date: 4/16/2018
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 41, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz)										
5.01	-65.9	H	3.0	-15.9	36.9	1.0	-51.7	-25.0	-26.7	
7.52	-69.4	H	3.0	-15.6	35.9	1.0	-50.5	-25.0	-25.5	
10.02	-71.6	H	3.0	-15.0	33.7	1.0	-47.7	-25.0	-22.7	
5.01	-65.8	V	3.0	-15.6	36.9	1.0	-51.5	-25.0	-26.5	
7.52	-69.3	V	3.0	-15.6	35.9	1.0	-50.6	-25.0	-25.6	
10.02	-71.9	V	3.0	-15.7	33.7	1.0	-48.4	-25.0	-23.4	
Mid Channel (2593MHz)										
5.19	-65.6	H	3.0	-15.3	36.8	1.0	-51.1	-25.0	-26.1	
7.78	-67.5	H	3.0	-13.4	35.7	1.0	-48.1	-25.0	-23.1	
10.37	-70.5	H	3.0	-13.8	33.7	1.0	-46.5	-25.0	-21.5	
5.19	-66.7	V	3.0	-16.2	36.8	1.0	-52.0	-25.0	-27.0	
7.78	-68.6	V	3.0	-14.7	35.7	1.0	-49.4	-25.0	-24.4	
10.37	-69.9	V	3.0	-13.5	33.7	1.0	-46.2	-25.0	-21.2	
High Channel (2680MHz)										
5.36	-66.9	H	3.0	-15.3	36.8	1.0	-51.0	-25.0	-26.0	
8.04	-69.9	H	3.0	-15.5	35.4	1.0	-49.9	-25.0	-24.9	
10.72	-71.8	H	3.0	-14.9	33.7	1.0	-47.6	-25.0	-22.6	
5.36	-66.8	V	3.0	-16.0	36.8	1.0	-51.8	-25.0	-26.8	
8.04	-69.7	V	3.0	-15.6	35.4	1.0	-50.0	-25.0	-25.0	
10.72	-71.6	V	3.0	-16.2	33.7	1.0	-47.9	-25.0	-22.9	

Rev. 05.21.15

LTE B41 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.2.12. LTE BAND 66

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 66, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1720.0MHz)										
3.44	-63.5	H	3.0	-14.2	38.5	1.0	-51.7	-13.0	-38.7	
5.16	-66.7	H	3.0	-13.5	38.7	1.0	-51.1	-13.0	-38.1	
6.88	-69.3	H	3.0	-12.3	38.1	1.0	-49.5	-13.0	-36.5	
3.44	-69.6	V	3.0	-20.5	38.5	1.0	-58.0	-13.0	-45.0	
5.16	-66.4	V	3.0	-13.5	38.7	1.0	-51.2	-13.0	-38.2	
6.88	-68.6	V	3.0	-11.9	38.1	1.0	-49.1	-13.0	-36.1	
Mid Channel (1745.0MHz)										
3.49	-68.0	H	3.0	-18.6	38.5	1.0	-56.1	-13.0	-43.1	
5.16	-66.3	H	3.0	-13.1	38.7	1.0	-50.8	-13.0	-37.8	
6.98	-69.2	H	3.0	-12.1	38.1	1.0	-49.2	-13.0	-36.2	
3.49	-67.7	V	3.0	-18.5	38.5	1.0	-56.0	-13.0	-43.0	
5.16	-62.0	V	3.0	-9.1	38.7	1.0	-46.8	-13.0	-33.8	
6.98	-69.6	V	3.0	-12.7	38.1	1.0	-49.8	-13.0	-36.8	
High Channel (1770.0MHz)										
3.54	-55.2	H	3.0	-5.7	38.6	1.0	-43.2	-13.0	-30.2	
5.31	-68.4	H	3.0	-14.9	38.6	1.0	-52.5	-13.0	-39.5	
7.08	-69.5	H	3.0	-12.2	38.0	1.0	-49.3	-13.0	-36.3	
3.54	-68.5	V	3.0	-19.1	38.6	1.0	-56.6	-13.0	-43.6	
5.31	-68.4	V	3.0	-15.2	38.6	1.0	-52.9	-13.0	-39.9	
7.08	-70.0	V	3.0	-13.0	38.0	1.0	-50.0	-13.0	-37.0	

Rev. 02.24.17

LTE B66 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/09/18
Test Engineer: 44410
Configuration: EUT only
Mode: LTE Band 66, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1720.0MHz)										
3.44	-63.7	H	3.0	-14.4	38.5	1.0	-51.9	-13.0	-38.9	
5.16	-67.8	H	3.0	-14.6	38.7	1.0	-52.3	-13.0	-39.3	
6.88	-69.7	H	3.0	-12.8	38.1	1.0	-49.9	-13.0	-36.9	
3.44	-68.5	V	3.0	-19.4	38.5	1.0	-56.9	-13.0	-43.9	
5.16	-67.5	V	3.0	-14.6	38.7	1.0	-52.3	-13.0	-39.3	
6.88	-69.5	V	3.0	-12.8	38.1	1.0	-49.9	-13.0	-36.9	
Mid Channel (1745.0MHz)										
3.49	-67.3	H	3.0	-17.9	38.5	1.0	-55.4	-13.0	-42.4	
5.16	-67.5	H	3.0	-14.3	38.7	1.0	-52.0	-13.0	-39.0	
6.98	-70.0	H	3.0	-12.8	38.1	1.0	-49.9	-13.0	-36.9	
3.49	-68.1	V	3.0	-18.8	38.5	1.0	-56.4	-13.0	-43.4	
5.16	-67.2	V	3.0	-14.4	38.7	1.0	-52.0	-13.0	-39.0	
6.98	-69.5	V	3.0	-12.6	38.1	1.0	-49.7	-13.0	-36.7	
High Channel (1770.0MHz)										
3.54	-55.8	H	3.0	-6.3	38.6	1.0	-43.8	-13.0	-30.8	
5.31	-69.5	H	3.0	-16.0	38.6	1.0	-53.7	-13.0	-40.7	
7.08	-68.4	H	3.0	-11.1	38.0	1.0	-48.1	-13.0	-35.1	
3.54	-66.8	V	3.0	-17.4	38.6	1.0	-54.9	-13.0	-41.9	
5.31	-67.9	V	3.0	-14.7	38.6	1.0	-52.3	-13.0	-39.3	
7.08	-68.4	V	3.0	-11.4	38.0	1.0	-48.4	-13.0	-35.4	

Rev. 02.24.17

LTE B66 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.3. FIELD STRENGTH OF SPURIOUS RADIATION, ANT 3

9.3.1. LTE BAND 2

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 52275
Configuration: EUT
Mode: LTE Band 2, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-50.7	H	3.0	-2.7	37.4	1.0	-39.1	-13.0	-26.1	
5.58	-66.6	H	3.0	-15.6	36.7	1.0	-51.3	-13.0	-38.3	
7.44	-69.6	H	3.0	-15.8	36.0	1.0	-50.8	-13.0	-37.8	
3.72	-55.5	V	3.0	-7.5	37.4	1.0	-44.2	-13.0	-31.2	
5.58	-67.7	V	3.0	-16.6	36.7	1.0	-52.3	-13.0	-39.3	
7.44	-69.5	V	3.0	-15.9	36.0	1.0	-50.9	-13.0	-37.9	
Mid Channel (1880MHz)										
3.76	-49.2	H	3.0	-1.2	37.4	1.0	-37.6	-13.0	-24.6	
5.64	-68.4	H	3.0	-17.3	36.7	1.0	-53.0	-13.0	-40.0	
7.52	-70.6	H	3.0	-16.7	35.9	1.0	-51.7	-13.0	-38.7	
3.76	-58.8	V	3.0	-11.0	37.4	1.0	-47.3	-13.0	-34.3	
5.64	-68.3	V	3.0	-17.2	36.7	1.0	-52.9	-13.0	-39.9	
7.52	-71.6	V	3.0	-18.0	35.9	1.0	-52.9	-13.0	-39.9	
High Channel (1900MHz)										
3.80	-50.3	H	3.0	-2.3	37.3	1.0	-38.6	-13.0	-25.6	
5.70	-66.9	H	3.0	-15.7	36.7	1.0	-51.4	-13.0	-38.4	
7.60	-70.5	H	3.0	-16.6	35.8	1.0	-51.4	-13.0	-38.4	
3.80	-56.6	V	3.0	-8.7	37.3	1.0	-45.1	-13.0	-32.1	
5.70	-67.2	V	3.0	-16.0	36.7	1.0	-51.7	-13.0	-38.7	
7.60	-70.5	V	3.0	-16.8	35.8	1.0	-51.7	-13.0	-38.7	

Rev. 05.21.15

LTE B 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 52275
Configuration: EUT
Mode: LTE Band 2, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-48.6	H	3.0	-0.6	37.4	1.0	-37.0	-13.0	-24.0	
5.58	-64.9	H	3.0	-13.9	36.7	1.0	-49.7	-13.0	-36.7	
7.44	-70.4	H	3.0	-16.7	36.0	1.0	-51.7	-13.0	-38.7	
3.72	-54.0	V	3.0	-6.3	37.4	1.0	-42.6	-13.0	-29.6	
5.58	-68.2	V	3.0	-17.1	36.7	1.0	-52.9	-13.0	-39.9	
7.44	-69.9	V	3.0	-16.4	36.0	1.0	-51.4	-13.0	-38.4	
Mid Channel (1880MHz)										
3.76	-48.7	H	3.0	-0.7	37.4	1.0	-37.1	-13.0	-24.1	
5.64	-66.9	H	3.0	-15.8	36.7	1.0	-51.5	-13.0	-38.5	
7.52	-70.9	H	3.0	-17.0	35.9	1.0	-51.9	-13.0	-38.9	
3.76	-56.8	V	3.0	-8.0	37.4	1.0	-45.3	-13.0	-32.3	
5.64	-66.6	V	3.0	-15.4	36.7	1.0	-51.1	-13.0	-38.1	
7.52	-67.1	V	3.0	-13.5	35.9	1.0	-48.4	-13.0	-35.4	
High Channel (1900MHz)										
3.80	-49.1	H	3.0	-1.1	37.3	1.0	-37.4	-13.0	-24.4	
5.70	-62.4	H	3.0	-11.2	36.7	1.0	-46.9	-13.0	-33.9	
7.60	-70.5	H	3.0	-16.6	35.8	1.0	-51.4	-13.0	-38.4	
3.80	-55.3	V	3.0	-7.4	37.3	1.0	-43.7	-13.0	-30.7	
5.70	-68.7	V	3.0	-17.5	36.7	1.0	-53.2	-13.0	-40.2	
7.60	-71.0	V	3.0	-17.3	35.8	1.0	-52.1	-13.0	-39.1	

Rev. 05.21.15

LTE B2 20MHz 16QAM

9.3.2. LTE BAND 7

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 52275
Configuration: EUT
Mode: LTE Band 7, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)										
5.02	-67.6	H	3.0	-17.6	36.9	1.0	-53.5	-25.0	-28.5	
7.53	-72.1	H	3.0	-18.3	35.9	1.0	-53.2	-25.0	-28.2	
10.04	-74.0	H	3.0	-17.5	33.7	1.0	-50.1	-25.0	-25.1	
5.02	-66.6	V	3.0	-16.4	36.9	1.0	-52.3	-25.0	-27.3	
7.53	-71.2	V	3.0	-17.5	35.9	1.0	-52.4	-25.0	-27.4	
10.04	-71.8	V	3.0	-15.6	33.7	1.0	-48.3	-25.0	-23.3	
Mid Channel (2536MHz)										
5.07	-66.4	H	3.0	-16.3	36.9	1.0	-52.1	-25.0	-27.1	
7.61	-71.5	H	3.0	-17.5	35.8	1.0	-52.4	-25.0	-27.4	
10.14	-73.7	H	3.0	-17.1	33.7	1.0	-49.8	-25.0	-24.8	
5.07	-67.4	V	3.0	-17.1	36.9	1.0	-53.0	-25.0	-28.0	
7.61	-70.5	V	3.0	-16.8	35.8	1.0	-51.6	-25.0	-26.6	
10.14	-72.6	V	3.0	-16.4	33.7	1.0	-49.0	-25.0	-24.0	
High Channel (2560MHz)										
5.12	-67.7	H	3.0	-17.5	36.8	1.0	-53.4	-25.0	-28.4	
7.68	-71.7	H	3.0	-17.7	35.8	1.0	-52.5	-25.0	-27.5	
10.24	-72.2	H	3.0	-15.6	33.7	1.0	-48.3	-25.0	-23.3	
5.12	-66.5	V	3.0	-16.1	36.8	1.0	-52.0	-25.0	-27.0	
7.68	-70.1	V	3.0	-16.3	35.8	1.0	-51.1	-25.0	-26.1	
10.24	-73.3	V	3.0	-17.1	33.7	1.0	-49.8	-25.0	-24.8	

Rev. 05.21.15

LTE B7 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 52275
Configuration: EUT
Mode: LTE Band 7, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)										
5.02	-67.1	H	3.0	-17.1	36.9	1.0	-53.0	-25.0	-28.0	
7.53	-70.3	H	3.0	-16.5	35.9	1.0	-51.4	-25.0	-26.4	
10.04	-73.6	H	3.0	-17.1	33.7	1.0	-49.7	-25.0	-24.7	
5.02	-67.1	V	3.0	-16.9	36.9	1.0	-52.8	-25.0	-27.8	
7.53	-72.1	V	3.0	-18.5	35.9	1.0	-53.4	-25.0	-28.4	
10.04	-72.4	V	3.0	-16.2	33.7	1.0	-48.9	-25.0	-23.9	
Mid Channel (2536MHz)										
5.07	-66.8	H	3.0	-16.7	36.9	1.0	-52.5	-25.0	-27.5	
7.61	-71.3	H	3.0	-17.3	35.8	1.0	-52.2	-25.0	-27.2	
10.14	-71.4	H	3.0	-14.8	33.7	1.0	-47.5	-25.0	-22.5	
5.07	-68.0	V	3.0	-17.7	36.9	1.0	-53.6	-25.0	-28.6	
7.61	-72.1	V	3.0	-18.4	35.8	1.0	-53.3	-25.0	-28.3	
10.14	-72.9	V	3.0	-16.7	33.7	1.0	-49.4	-25.0	-24.4	
High Channel (2560MHz)										
5.12	-68.6	H	3.0	-18.4	36.8	1.0	-54.2	-25.0	-29.2	
7.68	-71.7	H	3.0	-17.7	35.8	1.0	-52.5	-25.0	-27.5	
10.24	-73.0	H	3.0	-16.4	33.7	1.0	-49.1	-25.0	-24.1	
5.12	-67.4	V	3.0	-17.0	36.8	1.0	-52.9	-25.0	-27.9	
7.68	-71.4	V	3.0	-17.6	35.8	1.0	-52.4	-25.0	-27.4	
10.24	-73.3	V	3.0	-17.0	33.7	1.0	-49.7	-25.0	-24.7	

Rev. 05.21.15

LTE B7 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.3.3. LTE BAND 25

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #: 12204524
Date: 04/16/18
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 25, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-58.8	H	3.0	-8.9	34.4	1.0	-42.3	-13.0	-29.3	
5.58	-66.3	H	3.0	-12.8	34.1	1.0	-45.9	-13.0	-32.9	
7.44	-70.1	H	3.0	-13.8	33.6	1.0	-46.3	-13.0	-33.3	
3.72	-55.2	V	3.0	-5.2	34.4	1.0	-38.7	-13.0	-25.7	
5.58	-66.6	V	3.0	-13.0	34.1	1.0	-46.1	-13.0	-33.1	
7.44	-69.4	V	3.0	-13.2	33.6	1.0	-45.8	-13.0	-32.8	
Mid Channel (1882.5MHz)										
3.75	-59.0	H	3.0	-9.0	34.4	1.0	-42.4	-13.0	-29.4	
5.63	-64.5	H	3.0	-10.9	34.1	1.0	-44.0	-13.0	-31.0	
7.53	-69.1	H	3.0	-12.7	33.5	1.0	-45.2	-13.0	-32.2	
3.75	-55.0	V	3.0	-4.9	34.4	1.0	-38.3	-13.0	-25.3	
5.63	-65.7	V	3.0	-12.0	34.1	1.0	-45.1	-13.0	-32.1	
7.53	-69.9	V	3.0	-13.6	33.5	1.0	-46.1	-13.0	-33.1	
High Channel (1905MHz)										
3.79	-60.1	H	3.0	-10.0	34.4	1.0	-43.4	-13.0	-30.4	
5.72	-66.4	H	3.0	-12.7	34.1	1.0	-45.8	-13.0	-32.8	
7.62	-70.6	H	3.0	-14.0	33.4	1.0	-46.5	-13.0	-33.5	
3.79	-53.5	V	3.0	-3.3	34.4	1.0	-36.7	-13.0	-23.7	
5.72	-66.8	V	3.0	-13.0	34.1	1.0	-46.1	-13.0	-33.1	
7.62	-68.9	V	3.0	-12.5	33.4	1.0	-45.0	-13.0	-32.0	

Rev. 05.21.15

LTE B25 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #: 12204524
Date: 4/16/2018
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 25, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber F	3m Chamber F	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-57.4	H	3.0	-7.5	34.4	1.0	-40.9	-13.0	-27.9	
5.58	-66.8	H	3.0	-13.3	34.1	1.0	-46.4	-13.0	-33.4	
7.44	-68.7	H	3.0	-12.4	33.6	1.0	-44.9	-13.0	-31.9	
3.72	-53.4	V	3.0	-3.5	34.4	1.0	-36.9	-13.0	-23.9	
5.58	-67.5	V	3.0	-13.8	34.1	1.0	-47.0	-13.0	-34.0	
7.44	-70.4	V	3.0	-14.2	33.6	1.0	-46.8	-13.0	-33.8	
Mid Channel (1882.5MHz)										
3.75	-56.7	H	3.0	-6.7	34.4	1.0	-40.1	-13.0	-27.1	
5.65	-65.8	H	3.0	-12.2	34.1	1.0	-45.3	-13.0	-32.3	
7.53	-68.6	H	3.0	-12.2	33.5	1.0	-44.7	-13.0	-31.7	
3.75	-52.0	V	3.0	-1.9	34.4	1.0	-35.3	-13.0	-22.3	
5.65	-65.4	V	3.0	-11.6	34.1	1.0	-44.7	-13.0	-31.7	
7.53	-70.1	V	3.0	-13.7	33.5	1.0	-46.3	-13.0	-33.3	
High Channel (1905MHz)										
3.81	-61.9	H	3.0	-11.7	34.4	1.0	-45.1	-13.0	-32.1	
5.72	-66.3	H	3.0	-12.6	34.1	1.0	-45.7	-13.0	-32.7	
7.62	-69.4	H	3.0	-12.8	33.4	1.0	-45.2	-13.0	-32.2	
3.81	-63.0	V	3.0	-12.7	34.4	1.0	-46.1	-13.0	-33.1	
5.72	-66.4	V	3.0	-12.6	34.1	1.0	-45.7	-13.0	-32.7	
7.62	-70.0	V	3.0	-13.5	33.4	1.0	-46.0	-13.0	-33.0	

Rev. 05.21.15

LTE B25 20MHz 16QAM

9.3.4. LTE BAND 30

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 52275
Configuration: EUT only
Mode: LTE Band 30, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H		Filter	LTE B30

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (2310MHz)										
4.62	-67.2	H	3.0	-13.4	37.9	1.0	-50.4	-40.0	-10.4	
6.93	-70.1	H	3.0	-11.4	36.5	1.0	-46.9	-40.0	-6.9	
9.24	-73.2	H	3.0	-11.6	34.9	1.0	-45.5	-40.0	-5.5	
4.62	-68.2	V	3.0	-14.5	37.9	1.0	-51.4	-40.0	-11.4	
6.93	-70.2	V	3.0	-10.7	36.5	1.0	-46.2	-40.0	-6.2	
9.24	-72.8	V	3.0	-11.0	34.9	1.0	-44.8	-40.0	-4.8	

Rev. 05.21.15

LTE B30 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 52275
Configuration: EUT only
Mode: LTE Band 30, 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H		Filter	LTE B30

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (2310MHz)										
4.62	-67.2	H	3.0	-13.4	37.9	1.0	-50.3	-40.0	-10.3	
6.93	-69.9	H	3.0	-11.3	36.5	1.0	-46.7	-40.0	-6.7	
9.24	-72.6	H	3.0	-11.0	34.9	1.0	-44.9	-40.0	-4.9	
4.62	-66.7	V	3.0	-13.0	37.9	1.0	-49.9	-40.0	-9.9	
6.93	-70.3	V	3.0	-10.9	36.5	1.0	-46.3	-40.0	-6.3	
9.24	-72.6	V	3.0	-10.8	34.9	1.0	-44.7	-40.0	-4.7	

Rev. 05.21.15

LTE B30 10MHz 16QAM

UL VERIFICATION SERVICES INC. FORM NO: CCSUP4031B
47173 BENICIA STREET, FREMONT, CA 94538, USA TEL: (510) 771-1000 FAX: (510) 661-0888
This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.3.5. LTE BAND 41

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 4/16/2018
Test Engineer: 52275
Configuration: EUT
Mode: LTE Band 41, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz)										
5.01	-65.5	H	3.0	-15.4	36.9	1.0	-51.3	-25.0	-26.3	
7.52	-69.8	H	3.0	-16.0	36.9	1.0	-50.9	-25.0	-25.9	
10.02	-72.3	H	3.0	-15.8	33.7	1.0	-48.5	-25.0	-23.5	
5.01	-66.3	V	3.0	-16.1	36.9	1.0	-52.0	-25.0	-27.0	
7.52	-69.7	V	3.0	-16.1	36.9	1.0	-51.0	-25.0	-26.0	
10.02	-73.2	V	3.0	-17.0	33.7	1.0	-49.7	-25.0	-24.7	
Mid Channel (2593MHz)										
5.19	-66.8	H	3.0	-16.5	36.8	1.0	-52.3	-25.0	-27.3	
7.78	-69.8	H	3.0	-15.7	35.7	1.0	-50.4	-25.0	-25.4	
10.37	-72.2	H	3.0	-15.5	33.7	1.0	-48.2	-25.0	-23.2	
5.19	-67.2	V	3.0	-16.7	36.8	1.0	-52.5	-25.0	-27.5	
7.78	-69.4	V	3.0	-15.6	35.7	1.0	-50.2	-25.0	-25.2	
10.37	-72.6	V	3.0	-16.3	33.7	1.0	-49.0	-25.0	-24.0	
High Channel (2680MHz)										
5.36	-66.4	H	3.0	-14.7	36.8	1.0	-50.5	-25.0	-25.5	
8.04	-69.4	H	3.0	-15.0	35.4	1.0	-49.4	-25.0	-24.4	
10.72	-72.1	H	3.0	-15.2	33.7	1.0	-47.9	-25.0	-22.9	
5.36	-66.5	V	3.0	-14.7	36.8	1.0	-50.5	-25.0	-25.5	
8.04	-70.6	V	3.0	-16.4	35.4	1.0	-50.9	-25.0	-25.9	
10.72	-72.3	V	3.0	-15.9	33.7	1.0	-48.6	-25.0	-23.6	

Rev. 05.21.15

LTE B41 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 4/16/2018
Test Engineer: 52275
Configuration: EUT
Mode: LTE Band 41, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz)										
5.01	-65.8	H	3.0	-15.8	36.9	1.0	-51.6	-25.0	-26.6	
7.52	-70.4	H	3.0	-16.5	36.9	1.0	-51.5	-25.0	-26.5	
10.02	-72.7	H	3.0	-16.2	33.7	1.0	-48.8	-25.0	-23.8	
5.01	-66.5	V	3.0	-16.3	36.9	1.0	-52.2	-25.0	-27.2	
7.52	-70.2	V	3.0	-16.6	36.9	1.0	-51.5	-25.0	-26.5	
10.02	-70.9	V	3.0	-14.7	33.7	1.0	-47.4	-25.0	-22.4	
Mid Channel (2593MHz)										
5.19	-66.1	H	3.0	-15.7	36.8	1.0	-51.6	-25.0	-26.6	
7.78	-71.9	H	3.0	-17.8	35.7	1.0	-52.5	-25.0	-27.5	
10.37	-74.1	H	3.0	-17.4	33.7	1.0	-50.1	-25.0	-26.1	
5.19	-65.5	V	3.0	-15.0	36.8	1.0	-50.8	-25.0	-25.8	
7.78	-70.0	V	3.0	-16.1	35.7	1.0	-50.8	-25.0	-25.8	
10.37	-71.8	V	3.0	-15.5	33.7	1.0	-48.2	-25.0	-23.2	
High Channel (2680MHz)										
5.36	-67.0	H	3.0	-16.3	36.8	1.0	-52.1	-25.0	-27.1	
8.04	-69.3	H	3.0	-14.8	35.4	1.0	-49.3	-25.0	-24.3	
10.72	-72.3	H	3.0	-15.4	33.7	1.0	-48.2	-25.0	-23.2	
5.36	-67.2	V	3.0	-16.4	36.8	1.0	-52.2	-25.0	-27.2	
8.04	-71.1	V	3.0	-17.0	35.4	1.0	-51.4	-25.0	-26.4	
10.72	-72.1	V	3.0	-15.6	33.7	1.0	-48.4	-25.0	-23.4	

Rev. 05.21.15

LTE B41 20MHz 16QAM

9.3.6. LTE BAND 66

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #: 12204524
Date: 04/16/18
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 66, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber E	3m Chamber E	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1720.0MHz)										
3.44	-63.7	H	3.0	-14.3	38.5	1.0	-51.9	-13.0	-38.9	
5.16	-65.8	H	3.0	-12.6	38.7	1.0	-50.3	-13.0	-37.3	
6.88	-69.0	H	3.0	-12.0	38.1	1.0	-49.2	-13.0	-36.2	
3.44	-63.9	V	3.0	-14.8	38.5	1.0	-52.3	-13.0	-39.3	
5.16	-65.3	V	3.0	-12.5	38.7	1.0	-50.1	-13.0	-37.1	
6.88	-69.9	V	3.0	-13.2	38.1	1.0	-50.4	-13.0	-37.4	
Mid Channel (1745.0MHz)										
3.49	-64.0	H	3.0	-14.5	38.5	1.0	-52.1	-13.0	-39.1	
5.24	-66.3	H	3.0	-12.9	38.7	1.0	-50.6	-13.0	-37.6	
6.98	-69.4	H	3.0	-12.2	38.1	1.0	-49.3	-13.0	-36.3	
3.49	-64.6	V	3.0	-15.3	38.5	1.0	-52.9	-13.0	-39.9	
5.24	-67.3	V	3.0	-14.3	38.7	1.0	-52.0	-13.0	-39.0	
6.98	-68.4	V	3.0	-11.5	38.1	1.0	-48.6	-13.0	-35.6	
High Channel (1770.0MHz)										
3.54	-64.9	H	3.0	-15.4	38.6	1.0	-52.9	-13.0	-39.9	
5.31	-66.9	H	3.0	-13.3	38.6	1.0	-51.0	-13.0	-38.0	
7.08	-69.7	H	3.0	-12.4	38.0	1.0	-49.5	-13.0	-36.5	
3.54	-63.9	V	3.0	-14.5	38.6	1.0	-52.0	-13.0	-39.0	
5.31	-67.8	V	3.0	-14.6	38.6	1.0	-52.3	-13.0	-39.3	
7.08	-68.7	V	3.0	-11.7	38.0	1.0	-48.7	-13.0	-35.7	

Rev. 02.24.17

LTE B66 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #: 12204524
Date: 04/16/18
Test Engineer: 10643
Configuration: EUT Only
Mode: LTE Band 66, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1720.0MHz)										
3.44	-63.8	H	3.0	-16.0	37.7	1.0	-52.7	-13.0	-39.7	
5.16	-65.9	H	3.0	-15.6	36.8	1.0	-51.5	-13.0	-38.5	
6.88	-67.8	H	3.0	-14.7	36.4	1.0	-50.1	-13.0	-37.1	
3.44	-65.5	V	3.0	-18.3	37.7	1.0	-55.0	-13.0	-42.0	
5.16	-64.6	V	3.0	-14.1	36.8	1.0	-50.0	-13.0	-37.0	
6.88	-68.6	V	3.0	-15.7	36.4	1.0	-51.1	-13.0	-38.1	
Mid Channel (1745.0MHz)										
3.49	-64.1	H	3.0	-16.3	37.6	1.0	-52.9	-13.0	-39.9	
5.24	-66.7	H	3.0	-16.3	36.8	1.0	-52.1	-13.0	-39.1	
6.98	-67.7	H	3.0	-14.5	36.4	1.0	-49.9	-13.0	-36.9	
3.49	-63.5	V	3.0	-16.2	37.6	1.0	-52.9	-13.0	-39.9	
5.24	-67.8	V	3.0	-17.2	36.8	1.0	-53.0	-13.0	-40.0	
6.98	-69.2	V	3.0	-16.1	36.4	1.0	-51.5	-13.0	-38.5	
High Channel (1770.0MHz)										
3.54	-65.2	H	3.0	-17.3	37.6	1.0	-53.9	-13.0	-40.9	
5.31	-67.4	H	3.0	-16.8	36.8	1.0	-52.6	-13.0	-39.6	
7.08	-69.8	H	3.0	-16.4	36.3	1.0	-51.7	-13.0	-38.7	
3.54	-64.1	V	3.0	-16.8	37.6	1.0	-53.4	-13.0	-40.4	
5.31	-67.1	V	3.0	-16.4	36.8	1.0	-52.2	-13.0	-39.2	
7.08	-69.4	V	3.0	-16.2	36.3	1.0	-51.5	-13.0	-38.5	

Rev. 02.24.17

LTE B66 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.4. FIELD STRENGTH OF SPURIOUS RADIATION, ANT 4

9.4.1. LTE BAND 2

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 12482
Configuration: EUT Only
Mode: LTE Band 2, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber G	3m Chamber G	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-64.6	H	3.0	-17.8	36.2	1.0	-53.0	-13.0	-40.0	
5.58	-68.1	H	3.0	-17.7	36.1	1.0	-52.8	-13.0	-39.8	
7.44	-70.5	H	3.0	-17.4	35.2	1.0	-51.6	-13.0	-38.6	
3.72	-61.8	V	3.0	-14.6	36.2	1.0	-49.8	-13.0	-36.8	
5.58	-68.5	V	3.0	-18.4	36.1	1.0	-53.5	-13.0	-40.5	
7.44	-70.0	V	3.0	-17.0	35.2	1.0	-51.1	-13.0	-38.1	
Mid Channel (1880MHz)										
3.76	-63.6	H	3.0	-16.7	36.2	1.0	-51.9	-13.0	-38.9	
5.64	-67.8	H	3.0	-17.4	36.1	1.0	-52.5	-13.0	-39.5	
7.52	-70.1	H	3.0	-16.9	35.1	1.0	-51.1	-13.0	-38.1	
3.76	-60.2	V	3.0	-12.9	36.2	1.0	-48.1	-13.0	-35.1	
5.64	-64.3	V	3.0	-14.1	36.1	1.0	-49.2	-13.0	-36.2	
7.52	-69.6	V	3.0	-16.4	35.1	1.0	-50.6	-13.0	-37.6	
High Channel (1900MHz)										
3.80	-63.4	H	3.0	-16.4	36.2	1.0	-51.5	-13.0	-38.5	
5.70	-68.8	H	3.0	-18.2	36.1	1.0	-53.3	-13.0	-40.3	
7.60	-70.8	H	3.0	-17.6	35.1	1.0	-51.6	-13.0	-38.6	
3.80	-59.4	V	3.0	-12.0	36.2	1.0	-47.1	-13.0	-34.1	
5.70	-62.5	V	3.0	-12.1	36.1	1.0	-47.2	-13.0	-34.2	
7.60	-68.0	V	3.0	-14.8	35.1	1.0	-48.9	-13.0	-35.9	

Rev. 05.21.15

LTE B 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 12482
Configuration: EUT only
Mode: LTE Band 2, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber G	3m Chamber G	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-63.4	H	3.0	-16.6	36.2	1.0	-51.8	-13.0	-38.8	
5.58	-66.6	H	3.0	-16.3	36.1	1.0	-51.4	-13.0	-38.4	
7.44	-70.2	H	3.0	-17.1	35.2	1.0	-51.3	-13.0	-38.3	
3.72	-65.5	V	3.0	-18.3	36.2	1.0	-53.5	-13.0	-40.5	
5.58	-68.5	V	3.0	-18.3	36.1	1.0	-53.4	-13.0	-40.4	
7.44	-70.7	V	3.0	-17.7	35.2	1.0	-51.8	-13.0	-38.8	
Mid Channel (1880MHz)										
3.76	-62.3	H	3.0	-15.4	36.2	1.0	-50.6	-13.0	-37.6	
5.64	-69.1	H	3.0	-18.7	36.1	1.0	-53.8	-13.0	-40.8	
7.52	-68.7	H	3.0	-15.5	35.1	1.0	-49.6	-13.0	-36.6	
3.76	-58.3	V	3.0	-11.0	36.2	1.0	-46.2	-13.0	-33.2	
5.64	-68.6	V	3.0	-18.3	36.1	1.0	-53.4	-13.0	-40.4	
7.52	-70.2	V	3.0	-17.1	35.1	1.0	-51.3	-13.0	-38.3	
High Channel (1900MHz)										
3.80	-62.0	H	3.0	-15.0	36.2	1.0	-50.2	-13.0	-37.2	
5.70	-68.4	H	3.0	-17.8	36.1	1.0	-52.9	-13.0	-39.9	
7.60	-69.6	H	3.0	-16.3	35.1	1.0	-50.4	-13.0	-37.4	
3.80	-58.9	V	3.0	-11.5	36.2	1.0	-46.6	-13.0	-33.6	
5.70	-69.0	V	3.0	-18.6	36.1	1.0	-53.7	-13.0	-40.7	
7.60	-69.7	V	3.0	-16.6	35.1	1.0	-50.6	-13.0	-37.6	

Rev. 05.21.15

LTE B2 20MHz 16QAM

9.4.2. LTE BAND 7

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/17/18
Test Engineer: 44366
Configuration: EUT Only
Mode: LTE Band 7, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)										
5.02	-66.2	H	3.0	-16.2	36.9	1.0	-52.1	-25.0	-27.1	
7.53	-71.5	H	3.0	-17.6	35.9	1.0	-52.6	-25.0	-27.6	
10.04	-72.2	H	3.0	-15.6	33.7	1.0	-48.3	-25.0	-23.3	
5.02	-67.2	V	3.0	-17.0	36.9	1.0	-52.9	-25.0	-27.9	
7.53	-71.1	V	3.0	-17.5	35.9	1.0	-52.4	-25.0	-27.4	
10.04	-72.5	V	3.0	-16.3	33.7	1.0	-49.0	-25.0	-24.0	
Mid Channel (2536MHz)										
5.07	-66.2	H	3.0	-16.1	36.9	1.0	-51.9	-25.0	-26.9	
7.61	-68.9	H	3.0	-15.0	35.8	1.0	-49.8	-25.0	-24.8	
10.14	-70.0	H	3.0	-13.4	33.7	1.0	-46.1	-25.0	-21.1	
5.07	-66.3	V	3.0	-16.0	36.9	1.0	-51.8	-25.0	-26.8	
7.61	-71.1	V	3.0	-17.4	35.8	1.0	-52.2	-25.0	-27.2	
10.14	-72.9	V	3.0	-16.7	33.7	1.0	-49.3	-25.0	-24.3	
High Channel (2560MHz)										
5.12	-65.9	H	3.0	-15.7	36.8	1.0	-51.5	-25.0	-26.5	
7.68	-71.5	H	3.0	-17.5	35.8	1.0	-52.3	-25.0	-27.3	
10.24	-71.9	H	3.0	-15.3	33.7	1.0	-48.0	-25.0	-23.0	
5.12	-66.4	V	3.0	-15.0	36.8	1.0	-50.8	-25.0	-25.8	
7.68	-71.4	V	3.0	-17.6	35.8	1.0	-52.4	-25.0	-27.4	
10.24	-72.8	V	3.0	-16.5	33.7	1.0	-49.2	-25.0	-24.2	

Rev. 05.21.15

LTE B7 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/17/18
Test Engineer: 44366
Configuration: EUT Only
Mode: LTE Band 7, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	LTE B7

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2510MHz)										
5.02	-66.1	H	3.0	-16.1	36.9	1.0	-51.9	-25.0	-26.9	
7.53	-71.2	H	3.0	-17.3	35.9	1.0	-52.2	-25.0	-27.2	
10.04	-73.0	H	3.0	-16.5	33.7	1.0	-49.1	-25.0	-24.1	
5.02	-67.8	V	3.0	-17.6	36.9	1.0	-53.5	-25.0	-28.5	
7.53	-70.9	V	3.0	-16.4	35.9	1.0	-51.3	-25.0	-26.3	
10.04	-71.9	V	3.0	-15.7	33.7	1.0	-48.4	-25.0	-23.4	
Mid Channel (2536MHz)										
5.07	-67.1	H	3.0	-17.0	36.9	1.0	-52.8	-25.0	-27.8	
7.61	-70.5	H	3.0	-16.6	35.8	1.0	-51.4	-25.0	-26.4	
10.14	-72.9	H	3.0	-16.3	33.7	1.0	-49.0	-25.0	-24.0	
5.07	-67.7	V	3.0	-17.4	36.9	1.0	-53.3	-25.0	-28.3	
7.61	-69.3	V	3.0	-15.6	35.8	1.0	-50.5	-25.0	-25.5	
10.14	-72.8	V	3.0	-16.6	33.7	1.0	-49.3	-25.0	-24.3	
High Channel (2560MHz)										
5.12	-67.4	H	3.0	-17.2	36.8	1.0	-53.0	-25.0	-28.0	
7.68	-71.5	H	3.0	-17.5	35.8	1.0	-52.3	-25.0	-27.3	
10.24	-73.4	H	3.0	-16.7	33.7	1.0	-49.4	-25.0	-24.4	
5.12	-67.0	V	3.0	-16.6	36.8	1.0	-52.5	-25.0	-27.5	
7.68	-71.2	V	3.0	-17.4	35.8	1.0	-52.1	-25.0	-27.1	
10.24	-73.2	V	3.0	-16.9	33.7	1.0	-49.6	-25.0	-24.6	

Rev. 05.21.15

LTE B7 20MHz 16QAM

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.4.3. LTE BAND 25

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 12482
Configuration: EUT Only
Mode: LTE Band 25, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber G | Pre-amplifer: 3m Chamber G | Filter: Filter | Limit: EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-63.4	H	3.0	-16.7	36.2	1.0	-51.9	-13.0	-38.9	
5.58	-67.6	H	3.0	-17.2	36.1	1.0	-52.3	-13.0	-39.3	
7.44	-70.0	H	3.0	-16.9	35.2	1.0	-51.0	-13.0	-38.0	
3.72	-62.1	V	3.0	-14.9	36.2	1.0	-50.1	-13.0	-37.1	
5.58	-68.4	V	3.0	-18.2	36.1	1.0	-53.3	-13.0	-40.3	
7.44	-69.8	V	3.0	-16.7	35.2	1.0	-50.9	-13.0	-37.9	
Mid Channel (1882.5MHz)										
3.77	-62.5	H	3.0	-15.7	36.2	1.0	-50.8	-13.0	-37.8	
5.65	-68.9	H	3.0	-18.4	36.1	1.0	-53.5	-13.0	-40.5	
7.53	-70.3	H	3.0	-17.1	35.1	1.0	-51.2	-13.0	-38.2	
3.77	-62.4	V	3.0	-15.1	36.2	1.0	-50.3	-13.0	-37.3	
5.65	-69.2	V	3.0	-19.0	36.1	1.0	-54.1	-13.0	-41.1	
7.53	-68.7	V	3.0	-15.5	35.1	1.0	-49.7	-13.0	-36.7	
High Channel (1905MHz)										
3.81	-64.0	H	3.0	-17.1	36.1	1.0	-52.2	-13.0	-39.2	
5.72	-68.4	H	3.0	-17.8	36.1	1.0	-52.9	-13.0	-39.9	
7.62	-70.0	H	3.0	-16.8	35.1	1.0	-50.8	-13.0	-37.8	
3.81	-63.5	V	3.0	-16.1	36.1	1.0	-51.2	-13.0	-38.2	
5.72	-69.3	V	3.0	-18.9	36.1	1.0	-54.0	-13.0	-41.0	
7.62	-70.2	V	3.0	-16.9	35.1	1.0	-51.0	-13.0	-38.0	

Rev. 05.21.15

LTE B25 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/16/18
Test Engineer: 12482
Configuration: EUT only
Mode: LTE Band 25, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber G | Pre-amplifer: 3m Chamber G | Filter: Filter | Limit: EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1860MHz)										
3.72	-65.3	H	3.0	-18.5	36.2	1.0	-53.8	-13.0	-40.8	
5.58	-68.2	H	3.0	-17.9	36.1	1.0	-53.0	-13.0	-40.0	
7.44	-69.9	H	3.0	-16.8	35.2	1.0	-51.0	-13.0	-38.0	
3.72	-62.9	V	3.0	-15.7	36.2	1.0	-50.9	-13.0	-37.9	
5.58	-69.0	V	3.0	-18.9	36.1	1.0	-54.0	-13.0	-41.0	
7.44	-70.5	V	3.0	-17.5	35.2	1.0	-51.7	-13.0	-38.7	
Mid Channel (1882.5MHz)										
3.77	-64.1	H	3.0	-17.2	36.2	1.0	-52.4	-13.0	-39.4	
5.65	-67.6	H	3.0	-17.2	36.1	1.0	-52.3	-13.0	-39.3	
7.53	-69.6	H	3.0	-16.4	35.1	1.0	-50.5	-13.0	-37.5	
3.77	-62.0	V	3.0	-14.6	36.2	1.0	-49.8	-13.0	-36.8	
5.65	-69.4	V	3.0	-19.1	36.1	1.0	-54.2	-13.0	-41.2	
7.53	-69.4	V	3.0	-16.3	35.1	1.0	-50.4	-13.0	-37.4	
High Channel (1905MHz)										
3.81	-64.5	H	3.0	-17.5	36.1	1.0	-52.6	-13.0	-39.6	
5.72	-68.7	H	3.0	-18.1	36.1	1.0	-53.2	-13.0	-40.2	
7.62	-71.0	H	3.0	-17.7	35.1	1.0	-51.7	-13.0	-38.7	
3.81	-62.4	V	3.0	-14.9	36.1	1.0	-50.1	-13.0	-37.1	
5.72	-69.7	V	3.0	-19.3	36.1	1.0	-54.3	-13.0	-41.3	
7.62	-70.5	V	3.0	-17.3	35.1	1.0	-51.4	-13.0	-38.4	

Rev. 05.21.15

LTE B25 20MHz 16QAM

9.4.4. LTE BAND 30

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/17/18
Test Engineer: 44366
Configuration: EUT only
Mode: LTE Band 30, 10MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber H | Pre-amplifer: 3m Chamber H | Filter: Filter | Limit: LTE B30

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (2310MHz)										
4.62	-67.0	H	3.0	-13.2	37.9	1.0	-50.1	-40.0	-10.1	
6.93	-70.2	H	3.0	-11.6	36.5	1.0	-47.1	-40.0	-7.1	
9.24	-69.8	H	3.0	-8.2	34.9	1.0	-42.1	-40.0	-2.1	
4.62	-66.6	V	3.0	-12.9	37.9	1.0	-49.8	-40.0	-9.8	
6.93	-70.3	V	3.0	-10.8	36.5	1.0	-46.3	-40.0	-6.3	
9.24	-71.9	V	3.0	-10.1	34.9	1.0	-44.0	-40.0	-4.0	

Rev. 05.21.15

LTE B30 10MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/17/18
Test Engineer: 44366
Configuration: EUT only
Mode: LTE Band 30, 10MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber: 3m Chamber H | Pre-amplifer: 3m Chamber H | Filter: Filter | Limit: LTE B30

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Mid Channel (2310MHz)										
4.62	-65.4	H	3.0	-11.6	37.9	1.0	-48.5	-40.0	-8.5	
6.93	-68.2	H	3.0	-9.6	36.5	1.0	-45.0	-40.0	-5.0	
9.24	-71.8	H	3.0	-10.2	34.9	1.0	-44.1	-40.0	-4.1	
4.62	-65.9	V	3.0	-12.1	37.9	1.0	-49.1	-40.0	-9.1	
6.93	-68.2	V	3.0	-8.7	36.5	1.0	-44.1	-40.0	-4.1	
9.24	-71.8	V	3.0	-10.0	34.9	1.0	-43.9	-40.0	-3.9	

Rev. 05.21.15

LTE B30 10MHz 16QAM

UL VERIFICATION SERVICES INC. FORM NO: CCSUP4031B
47173 BENICIA STREET, FREMONT, CA 94538, USA TEL: (510) 771-1000 FAX: (510) 661-0888
This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

9.4.5. LTE BAND 41

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/17/18
Test Engineer: 44366
Configuration: EUT Only
Mode: LTE Band 41, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz)										
5.01	-66.7	H	3.0	-16.7	36.9	1.0	-52.6	-25.0	-27.6	
7.52	-69.8	H	3.0	-15.9	36.9	1.0	-50.8	-25.0	-25.8	
10.02	-73.2	H	3.0	-16.6	33.7	1.0	-49.3	-25.0	-24.3	
5.01	-67.5	V	3.0	-17.2	36.9	1.0	-53.1	-25.0	-28.1	
7.52	-71.3	V	3.0	-17.7	36.9	1.0	-52.6	-25.0	-27.6	
10.02	-71.9	V	3.0	-15.7	33.7	1.0	-48.4	-25.0	-23.4	
Mid Channel (2593MHz)										
5.19	-65.8	H	3.0	-15.4	36.8	1.0	-51.3	-25.0	-26.3	
7.78	-70.8	H	3.0	-16.6	35.7	1.0	-51.3	-25.0	-26.3	
10.37	-71.9	H	3.0	-15.2	33.7	1.0	-47.9	-25.0	-22.9	
5.19	-66.5	V	3.0	-16.0	36.8	1.0	-51.8	-25.0	-26.8	
7.78	-71.8	V	3.0	-17.9	35.7	1.0	-52.6	-25.0	-27.6	
10.37	-73.0	V	3.0	-16.7	33.7	1.0	-49.4	-25.0	-24.4	
High Channel (2680MHz)										
5.36	-66.7	H	3.0	-16.1	36.8	1.0	-51.9	-25.0	-26.9	
8.04	-69.8	H	3.0	-15.4	35.4	1.0	-49.8	-25.0	-24.8	
10.72	-71.9	H	3.0	-16.0	33.7	1.0	-47.7	-25.0	-22.7	
5.36	-67.3	V	3.0	-16.5	36.8	1.0	-52.3	-25.0	-27.3	
8.04	-70.5	V	3.0	-16.3	35.4	1.0	-50.8	-25.0	-25.8	
10.72	-72.0	V	3.0	-15.6	33.7	1.0	-48.3	-25.0	-23.3	

Rev. 05.21.15

LTE B41 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/17/18
Test Engineer: 44366
Configuration: EUT Only
Mode: LTE Band 41, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	LTE B41

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (2506MHz)										
5.01	-67.4	H	3.0	-17.4	36.9	1.0	-53.3	-25.0	-28.3	
7.52	-70.4	H	3.0	-16.6	36.9	1.0	-51.5	-25.0	-26.5	
10.02	-73.4	H	3.0	-16.8	33.7	1.0	-49.5	-25.0	-24.5	
5.01	-67.0	V	3.0	-16.8	36.9	1.0	-52.7	-25.0	-27.7	
7.52	-71.4	V	3.0	-17.7	36.9	1.0	-52.7	-25.0	-27.7	
10.02	-73.2	V	3.0	-17.0	33.7	1.0	-49.7	-25.0	-24.7	
Mid Channel (2593MHz)										
5.19	-66.9	H	3.0	-16.5	36.8	1.0	-52.3	-25.0	-27.3	
7.78	-69.7	H	3.0	-15.5	35.7	1.0	-50.2	-25.0	-25.2	
10.37	-74.0	H	3.0	-17.2	33.7	1.0	-49.9	-25.0	-24.9	
5.19	-66.9	V	3.0	-16.4	36.8	1.0	-52.2	-25.0	-27.2	
7.78	-71.4	V	3.0	-17.6	35.7	1.0	-52.2	-25.0	-27.2	
10.37	-71.7	V	3.0	-15.4	33.7	1.0	-48.1	-25.0	-23.1	
High Channel (2680MHz)										
5.36	-68.0	H	3.0	-17.4	36.8	1.0	-53.2	-25.0	-28.2	
8.04	-71.3	H	3.0	-16.9	35.4	1.0	-51.3	-25.0	-26.3	
10.72	-72.4	H	3.0	-15.6	33.7	1.0	-48.3	-25.0	-23.3	
5.36	-67.5	V	3.0	-16.7	36.8	1.0	-52.5	-25.0	-27.5	
8.04	-70.9	V	3.0	-16.7	35.4	1.0	-51.2	-25.0	-26.2	
10.72	-74.0	V	3.0	-17.6	33.7	1.0	-50.3	-25.0	-25.3	

Rev. 05.21.15

LTE B41 20MHz 16QAM

9.4.6. LTE BAND 66

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/17/18
Test Engineer: 44366
Configuration: EUT Only
Mode: LTE Band 66, 20MHz QPSK

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1720.0MHz)										
3.44	-64.8	H	3.0	-16.9	37.7	1.0	-53.6	-13.0	-40.6	
5.16	-67.3	H	3.0	-17.0	36.8	1.0	-52.8	-13.0	-39.8	
6.88	-69.6	H	3.0	-16.5	36.4	1.0	-51.9	-13.0	-38.9	
3.44	-64.2	V	3.0	-17.1	37.7	1.0	-53.8	-13.0	-40.8	
5.16	-67.0	V	3.0	-16.6	36.8	1.0	-52.4	-13.0	-39.4	
6.88	-69.8	V	3.0	-16.8	36.4	1.0	-52.3	-13.0	-39.3	
Mid Channel (1745.0MHz)										
3.49	-63.5	H	3.0	-15.6	37.6	1.0	-52.2	-13.0	-39.2	
5.24	-67.4	H	3.0	-17.0	36.8	1.0	-52.8	-13.0	-39.8	
6.98	-69.8	H	3.0	-16.6	36.4	1.0	-52.0	-13.0	-39.0	
3.49	-60.2	V	3.0	-13.0	37.6	1.0	-49.6	-13.0	-36.6	
5.24	-68.1	V	3.0	-17.5	36.8	1.0	-53.4	-13.0	-40.4	
6.98	-69.9	V	3.0	-16.9	36.4	1.0	-52.3	-13.0	-39.3	
High Channel (1770.0MHz)										
3.54	-64.1	H	3.0	-16.2	37.6	1.0	-52.8	-13.0	-39.8	
5.31	-67.7	H	3.0	-17.2	36.8	1.0	-53.0	-13.0	-40.0	
7.08	-67.3	H	3.0	-13.9	36.3	1.0	-49.2	-13.0	-36.2	
3.54	-64.3	V	3.0	-17.0	37.6	1.0	-53.5	-13.0	-40.5	
5.31	-67.2	V	3.0	-16.5	36.8	1.0	-52.3	-13.0	-39.3	
7.08	-69.6	V	3.0	-16.4	36.3	1.0	-51.7	-13.0	-38.7	

Rev. 02.24.17

LTE B66 20MHz QPSK

High Frequency Substitution Measurement
UL Fremont Radiated Chamber

Company:
Project #:
Date: 04/17/18
Test Engineer: 44366
Configuration: EUT Only
Mode: LTE Band 66, 20MHz 16QAM

Test Equipment:
Substitution: Horn T59 Substitution, and 8ft SMA Cable

Chamber	Pre-amplifer	Filter	Limit
3m Chamber H	3m Chamber H	Filter	EIRP

Frequency (GHz)	SA reading (dBm)	Ant. Pol. (H/V)	Distance	EIRP @ TX Ant End (dBm)	Preamp	Attenuator	EIRP	Limit	Delta	Notes
Low Channel (1720.0MHz)										
3.44	-65.1	H	3.0	-17.2	37.7	1.0	-53.9	-13.0	-40.9	
5.16	-67.2	H	3.0	-16.9	36.8	1.0	-52.8	-13.0	-39.8	
6.88	-69.9	H	3.0	-16.8	36.4	1.0	-52.2	-13.0	-39.2	
3.44	-64.7	V	3.0	-17.6	37.7	1.0	-54.3	-13.0	-41.3	
5.16	-67.9	V	3.0	-17.4	36.8	1.0	-53.2	-13.0	-40.2	
6.88	-70.1	V	3.0	-17.2	36.4	1.0	-52.6	-13.0	-39.6	
Mid Channel (1745.0MHz)										
3.49	-62.5	H	3.0	-14.7	37.6	1.0	-51.3	-13.0	-38.3	
5.24	-67.7	H	3.0	-17.3	36.8	1.0	-53.1	-13.0	-40.1	
6.98	-70.1	H	3.0	-16.9	36.4	1.0	-52.3	-13.0	-39.3	
3.49	-60.2	V	3.0	-13.0	37.6	1.0	-49.7	-13.0	-36.7	
5.24	-68.2	V	3.0	-17.6	36.8	1.0	-53.4	-13.0	-40.4	
6.98	-68.2	V	3.0	-15.1	36.4	1.0	-50.5	-13.0	-37.5	
High Channel (1770.0MHz)										
3.54	-65.3	H	3.0	-17.4	37.6	1.0	-54.0	-13.0	-41.0	
5.31	-66.2	H	3.0	-15.7	36.8	1.0	-51.5	-13.0	-38.5	
7.08	-69.3	H	3.0	-16.0	36.3	1.0	-51.3	-13.0	-38.3	
3.54	-65.9	V	3.0	-18.6	37.6	1.0	-55.2	-13.0	-42.2	
5.31	-67.8	V	3.0	-17.1	36.8	1.0	-52.9	-13.0	-39.9	
7.08	-68.9	V	3.0	-15.8	36.3	1.0	-51.1	-13.0	-38.1	

Rev. 02.24.17

LTE B66 20MHz 16QAM

END OF REPORT

This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.

10. SETUP PHOTOS

Please refer to 12204524-EP1V1 for setup photos

UL VERIFICATION SERVICES INC. FORM NO: CCSUP4031B
47173 BENICIA STREET, FREMONT, CA 94538, USA TEL: (510) 771-1000 FAX: (510) 661-0888
This report shall not be reproduced except in full, without the written approval of UL Verification Services Inc.