



RSE Co-location Result

Operating Mode	2	Polarization	Horizontal
Operating Function	Normal Link		

Level (dBuV/m) Date: 2016-09-12 Time: 17:58:47

Frequency (MHz)

	Freq	Level	Limit	Over	Read	CableAntenna	Preamp	A/Pos	T/Pos	Remark	Pol/Phase
	MHz	dBuV/m	dBuV/m	dB	dBuV	dB	dB/m	dB	cm	deg	
1	1124.96	40.75	74.00	-33.25	49.12	3.41	24.76	36.54	168	85 Peak	HORIZONTAL
2	1125.02	34.21	54.00	-19.79	42.58	3.41	24.76	36.54	168	85 Average	HORIZONTAL

RSE Co-location Result

Operating Mode	2	Power Phase	Vertical
Operating Function	Normal Link		

Level (dBuV/m) Date: 2016-09-12 Time: 18:02:57

The graph shows the measured signal level (red line) and the FCC CLASS-B PK and AV limits (red lines) across a frequency range from 1000 to 40000 MHz. The measured signal is consistently below the limits, indicating compliance with the FCC CLASS-B limits.

	Freq	Level	Limit	Over	Read	CableAntenna	Preamp	A/Pos	T/Pos	Remark	Pol/Phase
	MHz	dBuV/m	dBuV/m	dB	dBuV	dB	dB/m	dB	cm	deg	
1	1124.98	34.47	54.00	-19.53	42.84	3.41	24.76	36.54	116	304 Average	VERTICAL
2	1125.01	41.11	74.00	-32.89	49.48	3.41	24.76	36.54	116	304 Peak	VERTICAL