FCC PART 15B, CLASS B

TEST REPORT

For

LiveFree Emergency Response, Inc.

3780 Woodhaven Lane, Idaho Falls, Idaho United States

FCC ID: XTX-110

Report Type:	**Product Type:**
Original Report	*Ez care*

Test Engineer:	Mike Hu
Report Number:	RSZ151022014-00
Report Date:	2015-11-04
Reviewed By:	Bell Hu RF Engineer
Prepared By:	Bay Area Compliance Laboratories Corp. (Shenzhen) 6/F, the 3rd Phase of WanLi Industrial Building ShiHua Road, FuTian Free Trade Zone Shenzhen, Guangdong, China Tel: +86-755-33320018 Fax: +86-755-33320008 www.baclcorp.com.cn

TABLE OF CONTENTS

GENERAL INFORMATION

Product Description for Equipment under Test (EUT)

The *LiveFree Emergency Response, Inc.*'s product, model number: *EZC (FCC ID: XTX-110)* or the "EUT" in this report was an *Ez care,* which was measured approximately: 18.8 cm (L) x 14.8 cm (W) x 3.2 cm (H), rated with input voltage: DC 9.0 V from adapter. The highest operating frequency is 315MHz.

Adapter Information:
Model: CP0910
Input: AC 100-240V, 50/60Hz, 0.5A
Output: DC 9.0V, 1A

**All measurement and test data in this report was gathered from production sample serial number: 1506874. (Assigned by Shenzhen BACL). The EUT supplied by the applicant was received on 2015-10-22.*

Objective

This test report is prepared on behalf of *LiveFree Emergency Response, Inc.* in accordance with Part 2-Subpart J, Part 15-Subparts A and B of the Federal Communication Commissions rules.

The objective of the manufacturer is to determine the compliance of the EUT with FCC Part 15 B.

Related Submittal(s)/Grant(s)

Submitted with the part of a system with FCC ID: XTX-EZV

Test Facility

The test site used by Bay Area Compliance Laboratories Corp. (Shenzhen) to collect test data is located on the 6/F, the 3rd Phase of WanLi Industrial Building, ShiHua Road, FuTian Free Trade Zone Shenzhen, Guangdong, China.

Test site at Bay Area Compliance Laboratories Corp. (Shenzhen) has been fully described in reports submitted to the Federal Communication Commission (FCC). The details of these reports have been found to be in compliance with the requirements of Section 2.948 of the FCC Rules on October 31, 2013. The facility also complies with the radiated and AC line conducted test site criteria set forth in ANSI C63.4-2014.

The Federal Communications Commission has the reports on file and is listed under FCC Registration No.: 382179. The test site has been approved by the FCC for public use and is listed in the FCC Public Access Link (PAL) database.

SYSTEM TEST CONFIGURATION

Description of Test Configuration

The system was configured for testing in a manufacturer testing fashion.

EUT Exercise Software

N/A

Special Accessories

No special accessory.

Equipment Modifications

No modification was made to the EUT tested.

Support Equipment List and Details

Manufacturer	Description	Model	Serial Number
HP	Signal Generator	8341B	2624A00116
COM POWER	Dipole Antenna	AD-100	041000
Yike	PBX	N/A	35879653
Kinhao	Telephone	N/A	14589612

External I/O Cable

Cable Description	Length (m)	From/Port	To
Un-shielding detachable AC Cable	1.0	Mains	Socket
Un-shielding un-detachable DC Cable	1.7	Adapter	EUT
Un-shielding detachable RJ11 Cable	1.5	EUT	PBX
Un-shielding detachable RJ11 Cable	1.5	PBX	Telephone

Block Diagram of Test Setup

Out the range of the test table site.



SUMMARY OF TEST RESULTS

FCC Rules	Description of Test	Results
§15.107	AC Line Conducted Emissions	Compliance
§15.109	Radiated Spurious Emissions	Compliance

FCC §15.107 – AC LINE CONDUCTED EMISSIONS

Applicable Standard

According to FCC §15.107

Measurement Uncertainty

Input quantities to be considered for conducted disturbance measurements maybe receiver reading, attenuation of the connection between LISN/ISN and receiver, LISN/ISN voltage division factor, LISN/ISN VDF frequency interpolation and receiver related input quantities, etc.

Based on CISPR 16-4-2:2011, the expended combined standard uncertainty of conducted disturbance test at Bay Area Compliance Laboratories Corp. (Shenzhen) is shown as below. And the uncertainty will not be taken into consideration for the test data recorded in the report

Port	Measurement uncertainty
AC Mains	3.26 dB (k=2, 95% level of confidence)
CAT 3	3.70 dB (k=2, 95% level of confidence)
CAT 5	3.86 dB (k=2, 95% level of confidence)
CAT 6	4.64 dB (k=2, 95% level of confidence)

EUT Setup



Note: 1. Support units were connected to second LISN.
2. Both of LISNs (AMN) 80 cm from EUT and at the least 80 cm from other units and other metal planes support units.

The measurement procedure of EUT setup is according with per ANSI C63.4-2014. The related limit was specified in FCC Part 15.107 Class B.

The spacing between the peripherals was 10 cm.

The Adapter was connected to a 120 VAC/60 Hz power source.

EMI Test Receiver Setup

The EMI test receiver was set to investigate the spectrum from 150 kHz to 30 MHz.

During the conducted emission test, the EMI test receiver was set with the following configurations:

Frequency Range	IF B/W
150 kHz – 30 MHz	9 kHz

Test Procedure

During the conducted emission test, the adapter was connected to the first LISN and the other relevant equipments were conncected to the second LISN.

Maximizing procedure was performed on the six (6) highest emissions of the EUT.

All data was recorded in the Quasi-peak and average detection mode.

Test Equipment List and Details

Manufacturer	Description	Model	Serial Number	Calibration Date	Calibration Due Date
Rohde & Schwarz	EMI Test Receiver	ESCS30	100176	2015-06-03	2016-06-03
Rohde & Schwarz	LISN	ENV216	3560.6650.12-101613-Yb	2014-12-01	2015-12-01
Rohde & Schwarz	LISN	ESH2-Z5	892107/021	2015-06-09	2016-06-09
Rohde & Schwarz	Transient Limitor	ESH3Z2	DE25985	2015-05-14	2016-05-14
Rohde & Schwarz	CE Test software	EMC 32	V8.53	NCR	NCR

*** Statement of Traceability:** Bay Area Compliance Laboratories Corp. (Shenzhen) attests that all calibrations have been performed in accordance to requirements that traceable to National Primary Standards and International System of Units (SI).

Corrected Factor & Margin Calculation

The Corrected factor is calculated by adding LISN/ISN VDF (Voltage Division Factor), Cable Loss and Transient Limiter Attenuation. The basic equation is as follows:

Correction Factor = LISN VDF + Cable Loss + Transient Limiter Attenuation

The "**Margin**" column of the following data tables indicates the degree of compliance with the applicable limit. For example, a margin of 7 dB means the emission is 7 dB below the limit. The equation for margin calculation is as follows:

Margin = Limit – Corrected Amplitude

Test Results Summary

According to the recorded data in following table, the EUT complied with the FCC Part 15.107, the worst margin as below:

3.3 dB at **0.415730 MHz** in the **Neutral** conducted mode

Refer to CISPR16-4-2:2011 and CISPR 16-4-1:2009, the measured level is in compliance with the limit if

$$L_m + U_{(Lm)} \leq L_{lim} + U_{cispr}$$

In BACL., $U_{(Lm)}$ is less than U_{cispr}, if L_m is less than L_{lim}, it implies that the EUT complies with the limit.

Test Data

Environmental Conditions

Temperature:	25 ℃
Relative Humidity:	50 %
ATM Pressure:	101.0 kPa

The testing was performed by Mike Hu on 2015-10-28.

EUT Operation Mode: Receiving

AC 120V/60 Hz, Line



Frequency (MHz)	Corrected Amplitude (dBµV)	Correction Factor (dB)	Limit (dBµV)	Margin (dB)	Detector (PK/Ave./QP)
0.173500	54.5	20.0	64.8	10.3	QP
0.173500	45.5	20.0	54.8	9.3	Ave.
0.229500	51.1	20.0	62.5	11.4	QP
0.229500	42.2	20.0	52.5	10.3	Ave.
0.348690	43.6	19.9	59.0	15.4	QP
0.348690	33.7	19.9	49.0	15.3	Ave.
0.419730	50.5	19.9	57.5	7.0	QP
0.419730	37.7	19.9	47.5	9.7	Ave.
0.451310	46.7	19.9	56.9	10.1	QP
0.451310	34.8	19.9	46.9	12.1	Ave.
0.455070	45.6	19.9	56.8	11.2	QP
0.455070	33.7	19.9	46.8	13.1	Ave.

AC 120V/60 Hz, Neutral



Frequency (MHz)	Corrected Amplitude (dBµV)	Correction Factor (dB)	Limit (dBµV)	Margin (dB)	Detector (PK/Ave./QP)
0.297500	47.1	19.9	60.3	13.2	QP
0.297500	38.3	19.9	50.3	12.0	Ave.
0.415730	53.9	19.9	57.5	3.6	QP
0.415730	44.2	19.9	47.5	**3.3**	Ave.
0.455250	49.4	19.9	56.8	7.4	QP
0.455250	39.3	19.9	46.8	7.5	Ave.
0.506410	45.1	19.9	56.0	10.9	QP
0.506410	34.0	19.9	46.0	12.0	Ave.
1.514990	44.2	20.0	56.0	11.8	QP
1.514990	32.1	20.0	46.0	13.9	Ave.
1.598270	43.8	20.0	56.0	12.2	QP
1.598270	30.9	20.0	46.0	15.1	Ave.

Note:
1) Correction Factor =LISN VDF (Voltage Division Factor) + Cable Loss + Transient Limiter Attenuation
2) Corrected Amplitude = Reading + Correction Factor
3) Margin = Limit – Corrected Amplitude

FCC §15.109 - RADIATED SPURIOUS EMISSIONS

Applicable Standard

FCC §15.109

Measurement Uncertainty

All measurements involve certain levels of uncertainties, especially in field of EMC. The factors contributing to uncertainties are spectrum analyzer, cable loss, antenna factor calibration, antenna directivity, antenna factor variation with height, antenna phase center variation, antenna factor frequency interpolation, measurement distance variation, site imperfections, mismatch (average), and system repeatability.

Based on CISPR 16-4-2:2011, the expended combined standard uncertainty of radiation emissions at Bay Area Compliance Laboratories Corp. (Shenzhen) is shown in below table. And the uncertainty will not be taken into consideration for the test data recorded in the report

Frequency	Polarity	Measurement uncertainty
30 MHz~200 MHz	Horizontal	4.62 dB (k=2, 95% level of confidence)
	Vertical	4.54 dB (k=2, 95% level of confidence)
200 MHz~1 GHz	Horizontal	4.84 dB (k=2, 95% level of confidence)
	Vertical	5.91 dB (k=2, 95% level of confidence)
1 GHz~6 GHz	Horizontal/Vertical	4.68 dB (k=2, 95% level of confidence)

EUT Setup



The radiated emission tests were performed in the 3 meters chamber test site, using the setup accordance with the ANSI C63.4-2014. The specification used was the FCC Part 15.109 Class B limits.

The external I/O cables were draped along the test table and formed a bundle 30 to 40 cm long in the middle.

The spacing between the peripherals was 10 cm.

The Adapter was connected to a 120 VAC/60 Hz power source.

EMI Test Receiver Setup

The system was investigated from 30 MHz to 2 GHz.

During the radiated emission test, the EMI test receiver was set with the following configurations:

Frequency Range	RBW	Video B/W	IF B/W	Detector
30 MHz – 1000 MHz	100 kHz	300 kHz	120 kHz	QP
Above 1 GHz	1MHz	3 MHz	/	PK
	1MHz	10 Hz	/	Ave.

Test Procedure

Maximizing procedure was performed on the highest emissions to ensure that the EUT complied with all installation combinations.

All data was recorded in the Quasi-peak detector mode from 30 MHz to 1 GHz and PK and average detector modes for frequencies above 1 GHz.

Test Equipment List and Details

Manufacturer	Description	Model	Serial Number	Calibration Date	Calibration Due Date
HP	Amplifier	HP8447E	1937A01046	2015-05-06	2016-05-06
Rohde & Schwarz	EMI Test Receiver	ESCI	101120	2014-11-03	2015-11-03
Sunol Sciences	Bi-log Antenna	JB1	A040904-2	2014-12-07	2017-12-06
A.H. System	Horn Antenna	SAS-200/571	135	2013-02-10	2016-02-10
Rohde & Schwarz	Signal Analyzer	FSIQ26	8386001028	2014-12-11	2015-12-11
Mini	Pre-amplifier	ZVA-183-S+	5969001149	2015-04-23	2016-04-23
TDK	Chamber	Chamber A	2#	2013-10-15	2016-10-15
TDK	Chamber	Chamber B	1#	2015-07-23	2018-07-22
R&S	Auto test Software	EMC32	V9.10	NCR	NCR

*** Statement of Traceability:** Bay Area Compliance Laboratories Corp. (Shenzhen) attests that all calibrations have been performed in accordance to requirements that traceable to National Primary Standards and International System of Units (SI).

Corrected Amplitude & Margin Calculation

The Corrected Amplitude is calculated by adding the Antenna Factor and Cable Loss, and subtracting the Amplifier Gain from the Meter Reading. The basic equation is as follows:

Corrected Amplitude = Meter Reading + Antenna Factor + Cable Loss - Amplifier Gain

The "**Margin**" column of the following data tables indicates the degree of compliance with the applicable limit. For example, a margin of 7 dB means the emission is 7 dB below the limit. The equation for margin calculation is as follows:

Margin = Limit – Corrected Amplitude

Test Results Summary

According to the data in the following table, the EUT complied with the FCC §15.109 Class B, the worst margin reading as below:

10.79 dB at **44.56 MHz** in the **Vertical** polarization mode

Refer to CISPR16-4-2:2011 and CISPR 16-4-1:2009, the measured level is in compliance with the limit if

$$L_m + U_{(Lm)} \leq L_{lim} + U_{cispr}$$

In BACL, $U_{(Lm)}$ is less than U_{cispr}, if L_m is less than L_{lim}, it implies that the EUT complies with the limit.

Test Data

Environmental Conditions

Temperature:	25 ℃
Relative Humidity:	50 %
ATM Pressure:	101.0 kPa

The testing was performed by Mike Hu on 2015-10-28.

EUT Operation Mode: Receiving

30 MHz – 2.0 GHz

Frequency (MHz)	Receiver		Turntable Degree	Rx Antenna		Corrected Factor (dB/m)	Corrected Amplitude (dBµV/m)	FCC Part 15B	
	Reading (dBµV)	Detector (PK/QP/Ave.)		Height (m)	Polar (H/V)			Limit (dBµV/m)	Margin (dB)
40.25	45.49	QP	200	1.1	V	-13.5	26.62	40.00	13.38
44.56	54.30	QP	224	1.3	V	-16.7	29.21	40.00	**10.79**
51.50	55.71	QP	0	1.1	V	-20.0	24.43	40.00	15.57
109.70	49.20	QP	298	1.1	V	-14.4	11.71	43.50	31.79
151.84	40.71	QP	0	1.0	V	-13.9	21.05	43.50	22.45
313.54	37.62	QP	63	1.1	H	-12.1	35.12	46.00	10.88
1429.54	39.28	PK	93	1.9	V	0.07	39.35	74	34.65
1429.54	20.18	AV	93	1.9	V	0.07	20.25	54	33.75
1998.33	40.35	PK	132	1.2	V	5.19	45.54	74	28.46
1998.33	20.07	AV	132	1.2	V	5.19	25.26	54	28.74

Note:
1) Correction Factor=Antenna factor (RX) + cable loss – amplifier factor
2) Corrected Amplitude = Correction Factor + Reading
3) Margin = Limit - Corrected Amplitude

******* END OF REPORT *******